This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`

War 30.30 Bd. Dec. 1891.

Harvard College Library

FROM

The Bureau of Navigation.

12 Oct. 1885 – 19 Sept. 1891.

1885, Oct. 12 - 1891, Sept. 19.

Bureau of Navigation.

General Information Series, No. III.

INFORMATION FROM ABROAD.

VII. 2662

EXAMPLES, CONCLUSIONS, AND MAXIMS

OF

MODERN NAVAL TACTICS.

1884.

TEXT AND PLATES.

GENERAL INFORMATION SERIES, No. III.

INFORMATION FROM ABROAD.

EXAMPLES, CONCLUSIONS, AND MAXIMS

OF

MODERN NAVAL TACTICS,

BY

COMMANDER WM. BAINBRIDGE-HOFF,
UNITED STATES NAVY.

OFFICE OF NAVAL INTELLIGENCE,
BUREAU OF NAVIGATION,
NAVY DEPARTMENT.
1884.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1884.

~~VIII. 2662~~
War 30.30

The Office
of Naval Intelligence

PREFACE.

In placing these thoughts and remarks upon Naval Tactics before those who may be interested in the subject, I feel obliged to acknowledge a certain lack of experience, in a practical way, that must necessarily exist in a navy where an evolutionary fleet is not kept up.

Those nations which have always maintained large navies, and whose history and prestige date back to glorious pasts, have ever had great commanders and intelligent writers, who have made this branch of naval science a life-long study, both practically and theoretically. Upon the experience of these men, and from the writings of their naval editors, I have endeavored to give certain examples, deduce certain conclusions, and formulate certain maxims.

Naval Tactics means more than the handling of squadrons. It means the whole science of the conduct of vessels, whether they act singly or in concert; how to keep them together at sea; how to operate along a coast; how to conduct them through the inland waters of an enemy's country; how best to govern them in regard to any peculiar environment, whether of wind, weather, or adversary; whether to attack or to retreat, and, if the former, how best to employ their weapons of offense and defense.

The tactical integer is at all times changing according as the mechanical arts make prominent some one point in naval science, whether it be artillery or torpedoes, or the construction of the vessel itself. With wooden walls, broadside guns, and sails, it was the great fleet of many vessels. To-day, with the armor-clad and its all-round fire, torpedoes, and ram, it is the single ship.

Formerly the ship was a component of the fleet. To-day the fleet is a combination of ships.

Our own Navy has but marked its first century, yet its past history is filled with examples which teach startling and important lessons to the tacticians of older organizations.

During the war of 1812 a knowledge of this branch of naval science enabled us to add in nearly every equal encounter the name of the enemy's ship to our list of prizes.

The war of 1861 taught the lesson how to maintain the blockade of an enormous extent of coast, and the feasibility or riding out the heaviest gales of wind, anchored in the open sea, almost anywhere on available soundings. In this war too, was developed the tactics of the

War 30.30 Bd. Dec. 1891.

Harvard College Library

FROM

The Bureau of Navigation.

12 Oct. 1885 – 19 Sept. 1891.

1885, Oct. 12 – 1891, Sept. 19.

Bureau of Navigation.

GENERAL INFORMATION SERIES, NO. III.

INFORMATION FROM ABROAD.

VII .2662

EXAMPLES, CONCLUSIONS, AND MAXIMS

OF

MODERN NAVAL TACTICS.

1884.

TEXT AND PLATES.

CHAPTER XII.—CONCLUSION.

I.—Loss of the Grosser Kurfürst, owing to the want of a knowledge of fleet sailing.—What the loss of a man-of-war might entail.—Necessity for a knowledge of fleet tactics.—Is not to be gained in the class room.—Admiral Randolph's remarks.—Necessity for a practical course in the maneuvering of ships and squadrons. II.—Squadron of instruction in the Russian service.—Fleet drill by means of steam launches.—Captain Colomb's war game. III.—"Ocean greyhounds."—Tactical changes likely to occur from great improvement in speed.—In conclusion.

INTRODUCTION.

I.

Admiral Aube, in his most excellent treatise on "La Guerre Maritime et les Ports Militaires de la France," makes the following remark:

"The object of all navies is war. The fundamental problem which devolves upon us, before all others, in our researches, is, "What will a naval war be?" Curious idea! No one at present, not even the most distinguished seaman, can answer this question."

It may seem strange that large navies are built up, and yet the requisite knowledge as to how ships can best be combined and employed together in warfare is wanting.

Nevertheless the tactician, either by studying theory or by means of such experience as in time of peace can be obtained, strives to answer the question, "How will modern ships fight at sea?"

II.

Naval Tactics is one of the most important branches of knowledge that can engage the attention of the naval officer, since it teaches how to apply in a fight the different arms which constitute the power of a naval vessel. These lessons are as numerous and as varied as are the ends in view to be attained in a maritime war.

Until actual experience in war decides otherwise the naval power of a country shows itself in its superior squadrons, that is to say, the reunion in number, more or less great, of war vessels of the most recent type.

To have a share in the great dominion of the sea a nation must enter the contest with a strong fleet, ready to fight; supplied with the most modern weapons, and with a well-disciplined and thoroughly intelligent corps of officers. It should be borne in mind that a war once begun, the naval power of a nation will hardly increase, since ships take so long to build. In fact its naval strength will steadily run down through withdrawal of vessels for repairs incident to service, from damage done by the enemy, and from inevitable losses.

One of the maxims of war, according to Captain Harris, of the British Navy, is that—

> Every unit of a mercantile fleet, with the exception of its fastest steamers, is a national weakness in maritime war, so also is every unfortified town on the seaboard.

Since this is the case, we can easily see how necessary an efficient, if not a large, navy is to a nation having a large carrying trade on the seas, and a proper jealousy of her rights; how vital it is to have the ships of this navy, through drill and by experience in squadron, ready at all times to prevent imposition on the part of unscrupulous powers who may choose to be aggressive. It is the part of Naval Tactics to teach this navy how best to serve this end.

III.

The modern ship is a complex engine of war. It contains, to be effective, a combination of all the offensive weapons that science can devise. To be complete it must be supplied with the best guns, great power of engine and facility of turning; greatest strength of hull, in order that its ram may be efficient; and in it must be installed the best method for discharging automobile torpedoes. For a ship to possess only one or two of these weapons of offense is to put herself at a decided disadvantage in regard to some other vessel, otherwise less commendable, possessed of all three. Perhaps, in order to equip ourselves with these weapons, we may have to buy in a foreign market, but to have complete ships we must have the best weapons. To use domestic inventions of less warlike value is to handicap ourselves in a fatally stupid manner.

In regard to the knowledge required for the management of these new vessels we can do best by quoting the words of Vice-Admiral Randolph, R. N.:

> The first step towards discovering a means to an end must be to define clearly what that end is, and the following is submitted as the desideratum in naval tactics:
>
> It will be considered that the vastly increased cost, size, power, and capabilities of the modern ship of war increases also the importance of its being ably and carefully handled.
>
> We may assume that the one supreme object of a ship of war, though not its only *raison d'être*, is to beat the enemy at sea. Superior seamanship, combined with superior gunnery, are the means.

From the words of a French writer we can gather when and how this knowledge is to be applied:

> A fight between ships of similar or different caliber or class, an engagement between squadrons, the pursuit of a weaker opponent, the retreat from a stronger foe, engagements against fortifications, such are at a glance the operations that a fleet may have to perform, and upon which Naval Tactics must enlighten us, not only by mathematical precepts, but by general information.
>
> In order to combine the evolutions of ships in such a manner as to draw out of these engines of war the greatest usefulness—that is to say, to cause the greatest injury to the enemy—it is necessary to establish certain rules. These measures intended to preserve the singleness of design, always different and often numerous, have in themselves but one end—they constitute *evolutions*.
>
> Evolutions are the means employed to move squadrons under ordinary circumstances at sea and to take fleets into action in the most advantageous manner. They form an important part of naval tactics, but do not constitute it entirely. Two nations may have the general principles of tactics in common, and the means of applying them, that is to say, the system of evolutions, different.

From the following, we see that Naval Tactics has to deal with a number of recognized conditions, from which may be derived certain *postulates*. These have been framed in the following language by Admiral Randolph:

1st. The maximum power of attack requires the freest possible use by each ship of its ram and artillery (torpedo included) without injury to friends.

2d. The utmost mutual support should be given by friends, and protection from hostile rams.

3d. The closest order consistent with due regard to safety to each other should be maintained in order to meet the preceding demand, and to avoid the danger of one ship being unnecessarily exposed to the fire of two or more of the enemy.

4th. Utmost freedom to each ship of increasing or reducing speed, as well as altering course, or hauling out of action, or for other sufficient cause, is highly desirable.

5th. Facility of passing quickly from one enemy to another, either after partial or effectual collision or unavoidable separation, is important.

6th. Facility for the reforming of separated ships for renewed attack, or mutual support after the first shock of battle, is of high value.

7th. When possible, two ships, or at least a decisive superiority of force, should be thrown upon one.

8th. A reserve should, when possible, be retained to consummate and secure the fruits of victory.

I cannot more fitly close this introduction than by quoting the language of Lieutenant Campbell, R. N., in his admirable paper on "Steam tactics in a general action."

I would urge in conclusion what an important place tactical maneuvers should take in our naval education. From the earliest period of his career, no officer can study too carefully the signal books and the system of large fleets and squadrons acting in unison.

CHAPTER I.

DEFINITIONS AND EXPLANATIONS.

I.

In regard to the value of certain terms used in connection with this work so much diversity of opinion exists, that it will be as well to define, as nearly as possible, the meaning intended to be conveyed.

Strategy.—Combinations made by the commander-in-chief of a force acting on different points over a large area, to compel or annul certain movements of the enemy, or to unite or separate portions of a large sea force. Strategy refers not to the conduct of a battle but of a campaign, and orders the locality in which the fleet is to cruise and the object which it is to have specially in view, such as the blockade of a port, raising a blockade; or simply the meeting with and engaging the enemy. It is the greater science, as including all those vast combinations which lead to the subsequent available displays of naval tactics.

Naval tactics has sometimes been misused in the sense of strategy, whereas in fact it is a subordinate division of this science, since it refers to the execution of the detailed plans of strategical objects. It is the art of disposing naval forces in order of battle, and performing evolutions in the face or vicinity of the enemy; also, of performing all the possible evolutions with ships, sections, groups, divisions, squadrons, or fleets when acting together; *i. e.*, in such order that they are controlled by general signal—the employment of all the offensive powers of a ship, artillery, rams, torpedoes, or any naval weapons. Naval tactics is sometimes improperly restricted to the absolute performance of evolutions and forming of orders.

II.

Formation or Order.—Any arrangement or combination of vessels, on a line of bearing, or on lines of bearing, designed for cruising, for attacking, or for retreat.

Evolutions.—The necessary movement or combination of movements by which a fleet, or lesser number of ships acting together, proceed from one formation to another. Evolutions in the case of a single ship are when she proceeds from one point to another to gain some tactical advantage.

Movement or Maneuver.—Action of the whole force, or any detached portion of it, moving in the presence of the main body by which a position of advantage is sought to be gained. A component part of an evolution.

Change of Course.—Bringing the ship's head in some other direction.

Change of Direction.—Altering the compass bearing of the line of bearing that the formation is already on.

Line of Bearing.—An imaginary straight line passing through the same point of all the ships in some formation. It is designated by its direction in regard to the points of the compass as, "On a line of bearing SE. - NW." Or if the signal came from the Admiral, he would designate the line by its bearing *from* the flag-ship; as, "Form on line of bearing SE."

Absolute Bearing.—The compass bearing of one ship from another; as, "Bearing of A from B, NW. by N."

Relative Bearing.—The bearing of one ship from another, expressed in regard to the ship itself; as, "A bears from B two points abaft the beam."

A *ship* can *change her course*, which for her is a *change of direction*, or can *move* or *maneuver* in such a manner as to perform an *evolution*.

A *section*, *group*, *division*, *squadron*, or *fleet* can *change course*, by each ship's head coming to some other common compass bearing; or by a *movement*, which is a *maneuver*, can *change direction* or the bearing of its *line of bearing*, which will produce the same or another *formation* on another *line of bearing*. Or when, in any *formation*, this assemblage of vessels, either by a *simultaneous*, *successive*, or *direct movement*, or by a *conversion*, or by a *wheel in concentric circles*, or by a combination of two or more of these, or by performing the same movement more than once, can execute *evolutions*, and so pass to some other *formation*.

If ships bear relatively right ahead and right astern of one another, they are in "*line ahead.*" If they bear right abeam of one another, they are in "*line abreast.*" If they bear bow and quartering from each other, they are "*in échelon.*" (See Plate I, Figs. 1, 2, 3, 4, 5.) These formations are termed *simple.*

If any combination of vessels divide and form on more than one line of bearing, it assumes a *compound* or *complex formation*, and is then said to be in "*line ahead in two columns*" or "*in double line ahead;*" "*in alternate line ahead;*" "*in line ahead in groups;*" "*in double line abreast;*" "*in alternate line abreast;*" *in groups in line abreast;*" "*in naval square;*" "*in double échelon;*" or "*in groups in double échelon.*" If when in double échelon the angle and the ships' heads lie in the same general direction, the fleet is in "*chase formation;*" when the angle and the ships' heads are in opposite directions, it is in "*retreat formation.*" (See Plates II & III.)

Alternate Lines are those where the ships in one line are opposite the spaces in the other. This formation is also known by the names of "*checkered lines*" and "*supplementary lines*."

Naval Square is a formation of equal front and depth. The ships are so disposed that the distances and intervals are equal and the same in number.

Distance is the space between ships on the same line of bearing.

Interval is the perpendicular distance between two lines of bearing.

III.

THE TURNING CIRCLE.

(See Plate IV, Fig. 1.)

Octant.—A turn of 4 points, Pd^1, d^2, d^3, &c.

Final Circle.—The path a ship ultimately takes, assumed to be the circumference of a circle through the points reached at the end of the second, third, and fourth octants, as the arc d^2, d^3, d^4, of which C is the center.

Final Diameter and Radius.—The diameter and radius of the final circle.

Advance.—The distance traveled over at any point of the turn measured in a line parallel to the original course. Thus $f^1\ d^1$ is the advance at 4 points; $f^2\ d^2$ the advance at 8 points, and so on.

Transfer.—The distance traveled over at any point of the turn to the right or left of the prolongation of the original course, measured in a line at right angles to it. Thus, $e^3\ d^3$ is the transfer at 12 points, and $e^4\ a^4$ is the transfer at 16 points.

NOTE.—*The advance is the ordinate, and the transfer the abscissa of the curve at any point.*

Tactical Diameter is the transfer at 16 points, as $e^4\ d^4$, or the distance between the two courses when the original course is reversed.

Drift Angle is the angle included between the keel line of the ship and the tangent to the turning circle passing through the pivoting point of the ship. This drift angle is said to be the principal cause of the decrease of speed in turning, and the rudder pressure has little to do with it. Owing to the drift angle it is incorrect to assume that the ship has passed through a quarter, half, or whole circle when the ship's head has turned through 90°, 180°, or 360°, respectively.

Chord of so many points is the distance between the center of the middle line at the moment of moving the helm and its position when so many points have been turned. Thus, Pd^3 is the chord of 12 points. It is a convenient measure of turning powers so far as space is concerned.

Length is the length of the ship between perpendiculars. It is sometimes used to compare the space-measures of different ships' turning powers. Thus, the advance is so many *lengths;* the transfer so many; the chord so many, and so on. When one ship shows a greater number of *lengths* than another in any of these magnitudes, she has so much worse turning powers, so far as space is concerned.

Time-Length is the time it takes a ship to pass over her own length. It is necessarily varied with the speed, but it is a useful time measure for comparing the turning powers of any two ships. Thus, a ship is said to turn 4, 8, 12, or 16 points in so many *time-lengths*, and if another ship is shown to take more *time-lengths* to make the same turn, she has worse maneuvering power, so far as time is concerned.

Kick is the irregularity of the path of the ship observable when the helm is put down in turning. It is caused by the stern tending to swing out at right angles with the course when the rudder force begins to act. (See Plate IV, Fig. 2.)

Heeling Angle is due chiefly to centrifugal force, and varies—

1. Directly as the square of the speed of the ship.
2. Inversely with the metacentric height.
3. Inversely with the radius of the circle.

CHAPTER II.

WAR VESSELS.

I.

It comes within our province to consider only the war vessel in its connection with naval tactics. That is to say, to meet the enemy on the open sea we must oppose him with a fleet at least equal to his own in number, construction, speed, and offensive power. To protect our coasts we must be supplied with proper vessels, which can keep the sea, yet be of sufficiently light draft to enter most of our harbors. They must be protected in their construction against the projectiles of the armored fleet of the enemy, and they must possess weapons of offense and defense of the most commendable pattern.

To assist these fleets we need protected vessels of large size, termed cruisers; also a smaller class of the same name, corvettes, and gun-vessels. These should all be of great speed, have batteries of great penetration, and be fitted with automobile torpedoes. They should be of such heavy construction and possess such facility of turning as to be efficient rams against unarmored vessels.

Torpedo vessels of different sizes, armed with automobile torpedoes, machine guns, and possessed of great speed, are pre-eminently war vessels, but not of the line of battle.

A great diversity of opinion exists as to what kind of a vessel shall be entitled to this place in an engagement, but we think that a list of standard qualifications would be something like the following, suggested by Mr. Campbell:

1st. Great speed and coal-carrying power.
2d. Armor protection; unsinkability.
3d. Quickness in turning.
4th. Ability to keep the sea in all weathers.
5th. Capacity for stowing a large supply of provisions.
6th. A heavy armament of guns of the greatest penetrating power.

To these should be added a—

7th. Installation of the automobile torpedo.

Each ship of the line is a unit. She should therefore combine in herself all the elements of offense and defense. Her speed should be great, her turning power good, and in order to possess this quality, her helm should be moved by steam or by hydraulic power. She should be protected by sufficient and properly-distributed armor. She should be built with a ram bow, and be divided into numerous water-tight compartments. Her battery should consist of a few heavy guns, several lighter ones, a number of mechanical guns, also automobile torpedoes. As spar and divergent torpedoes are necessary at times, she should be fitted for them. Among her boats should be two torpedo launches, handy and of high speed. They should be as unsinkable as possible, and be well armed with torpedoes and machine guns.

It is not to be supposed that each line-of-battle ship will combine all these qualities, but the most eminent will decide her tactical value and will assign to her a proper place in the line. In fact we know, nowadays, that a fleet of vessels of the same size, build, and battery would be hardly possible, but each ship will have her value either for ram, artillery, or torpedo.

II.

Probably the most formidable line-of-battle ship is the sea-going armor-clad. She should combine the maximum of aggressive power with the maximum of resisting qualities.

The functions of the sea-going armored fleet would be to attack in line of battle the enemy's fleet wherever found; to drive it from our shores; to follow it, and confine it to its own harbors; to maintain an unchallenged command of the sea routes leading to our coasts; to protect our harbors against the enemy's fleet, and to oppose all attempts under cover of the enemy's fleet of the landing of troops for invasion at any point of the coast.

III.

Comparing the merits of the armor-clad with the merits of the protected or unarmored vessel for position in the line of battle, Admiral Sir Geoffrey Hornby, K. C. B., uses the following argument in favor of the armored vessel:

> You may put an iron-clad in any position you please, and if she is attacked by three of these unarmored vessels she will make a run at one vessel or the other, attack her with her guns, and threaten her with her ram, and it must be death to that vessel if she touches her any way. The two other vessels, you say, will follow and disturb the action of the iron-clad; but it must be recollected that the iron-clad will always be firing at them, one gun at least, and with shells, the bursting power of which must necessarily, as far as we know, destroy the fighting power of the cruiser. If any one contemplates what the bursting of a shell filled with 37 pounds of powder in the center of any unarmored vessel would be, I think he will agree there would be no more fight left in the ship. It is no answer to say that the ship is armed with a gun as heavy as the iron-clad has; the *morale* of the people will be destroyed, and they will be unable to continue the action against the concentrated force to which they are opposed. For that reason I hold that the unarmored ship cannot contend against the armored.

To cite a contrary opinion, we give that of Sir William G. Armstrong, C. B., F. R. S., expressed in these words:

> Not only did we see that armor was unavailing against torpedo attack and ram-

ming, but we were justified in concluding that every attempt to increase resistance to projectiles would be quickly followed by a corresponding increase in the power of artillery.

As to the comparative liability of an iron-clad and an unarmored ship to be sunk by projectiles, there was much less difference between them than was generally supposed; because the unarmored ship, though freely penetrable, might be so constructed that the entrance of water by perforation would not extensively flood the ship, unless it took place at a great number of critical places. Indeed, by introducing an under-water deck with divisional spaces, and by the partial application of cork, as in the Inflexible, for displacing influent water and thereby preserving stability, and also by a proper distribution of coal for the same purpose, an unarmored ship might be rendered almost incapable of being sunk; and it was rather surprising that so little attention had been directed to the attainment of that object. It was not too much to say that for the cost of one iron-clad we could have three unarmored ships of far higher speed and carrying collectively three armaments, each equal to that of the armored vessel.

It might be asked, which would be the better investment? If it were imagined that the three were matched in combat against the one, it would be perceived that, in addition to their numerical superiority, the former would possess many advantages. Being smaller, they would be more difficult to hit. Being swifter, they could choose their positions, and be free to attack or retreat at pleasure. Being more nimble in turning, they would be better adapted both for ramming and for evading the ram of their adversary. Finally, the conditions of superior speed and agility would favor their use of torpedoes and submarine projectiles.

It might, perhaps, be rash entirely to abandon armor so long as other nations continued to use it, because nothing but the experience of an actual war would remove all question as to its possible utility; but considering the indisputable value of a numerous fleet of swift and powerfully-armed ships, built with a view of obtaining the maximum amount of unarmored defense, and considering that such vessels, unlike armor-clads, could never grow much out of date, it did seem to be expedient that the chief expenditure should be upon ships of that description. Lightness should be the special aim in the construction of such vessels. Steel plates should be used for the hulls, and guns and engines should be of the least possible weight consistent with the necessary power. Every ton of weight saved would enable higher speed to be attained, and there was probably no quality in a fighting ship which would so much develop in importance as that of swiftness.

The question, notwithstanding the opinions of these eminent men, may still be considered as open. It cannot yet be said that it is decided whether an armor-clad, fit for the line of battle, is able to cope with a ram, armed with one gun of great power and caliber, and, say, four torpedo-vessels attacking simultaneously; all these vessels being supposed to have greater speed than the armor-clad. Experience alone will teach this lesson, but the maxim can be set down that if the question of money is put aside, in a contest between two vessels equal in offensive equipment and tactical qualities, the one with the strongest, most invulnerable hull will be the victor.

IV.

Cruising will be the most efficient way to ruin the enemy's commerce. It is therefore necessary to build a number of special cruisers. These vessels must have great speed and great coal-carrying capacity. Mr.

J. D'A. Samuda, at a meeting of the Institution of Naval Architects, had the following to say in reference to this class of vessel:

> Cruisers will be specially adapted and properly employed in protecting and convoying commerce, keeping open the seas to enable merchantmen to trade without interruption between the principal ports, lending naval assistance when needed, and performing many similar secondary services; and it may be freely admitted a very large number of them are required for such services, but they will be wholly unfitted to fight in line of battle and stand up against an armor-clad fleet, where endurance alone will determine the result of the encounter, and where the endurance of the iron-clad fleet may be reckoned by hours against minutes on the part of the unarmored cruisers, even if they elected to oppose the fighting fleet at all, for really, beyond possessing great value for guerrilla warfare, no decisive victory could be obtained or even hoped for against an iron-clad fleet by vessels whose safety, when hard pressed, would only be secured by their running away.

For a description of an efficient class of vessel of the type under consideration we read that—

> Light unarmored ships, designed by Mr. George Rendel, have lately been built in this country for foreign powers which with a displacement of only 1,300 tons had attained a speed of 16 knots an hour. They carried coal for steaming 4,000 miles and have already actually steamed 3,500 miles without replenishing. They were each armed with two 10-inch new-type guns, which had nearly an all-round fire, and were capable of piercing 18 inches of iron armor; and with four 40-pounders on the broadsides.

We will notice that Mr. Samuda does not contemplate putting cruisers in the line of battle, but his opinion is not sustained by that of Vice-Admiral Penhoat, of the French Navy, who thinks that these vessels should be built so staunchly, and be so well armed, as to qualify for this position in action. The Admiral believes that they could serve the fleet better by being placed in the line than by confining their operations to acting together as a lookout squadron, or as a reserve to tow disabled vessels out of action.

Of the smaller war vessels it will hardly be possible to enumerate all their duties. Corvettes must be the eyes of the armored fleet; they must drive off the cruisers of the enemy; they must unceasingly pursue and capture the merchant marine of the opposing nation. Where the lines of ocean commerce come together there must be the corvette to protect and to destroy.

To be worth anything small vessels should have good speed and coal-carrying power. If they are without these qualities, they should act with the coastwise fleet, or as tenders, or as flag-ships for the torpedo flotillas.

Altered merchant steamers become a class of coal and ammunition supply vessels, large torpedo-boat carriers, and commerce destroyers.

V.

Captain Noel, R. N., in common with a good many others, does not believe that the gun is the most important weapon of the fleet, while quite a number of writers agree with Mr. Laughton, who is of a contrary opinion, and says:

> The gun must still be held to be primarily the armament of ships, though secondarily the ram must enter largely into any scheme of battle.

All vessels, with perhaps the exception of the "Boston" class, are so designed that their bow-fire is stronger than their stern-fire. If the vessels of this class turn out to be all that is promised for them, we will perhaps be able to come nearer a solution of some of the vexed problems as regards defense of single vessels in action. It may be, though, that this class of vessel has a large gun installed in a position of least efficiency.

As regards the sizes of guns to be carried by vessels, whose calling is on the open sea, Admiral Penhoat does not believe that their artillery should be of large caliber, as the weight of the projectiles to be carried reduces their number in a great degree. Vessels will naturally come together in a fight, and artillery practice will be at short range. Large guns will come in for bombardments where the supply of ammunition can be kept up.

This question of ammunition supply is a very burning one, and has become a prominent problem in naval strategy and bears strongly upon tactics.

The weight of opinion is that the ram is the most formidable of a ship's offensive powers. Many authorities believe that it will be used as the ordinary fighting weapon, and that all methods and plans of attack should be based upon its employment; others think that it will probably only be used like the bayonet of the infantry soldier to give the *coup de grâce*. The reason for this being that it is so hard to maneuver a vessel to ram effectively where the target is animated by a spirit as active and as intelligent as your own. Official records of trials in Germany show this; and more than one writer is of the opinion that there must be some accidental disadvantage to allow a vessel to be rammed.

A vessel built for a ram *pur et simple*, to be unarmed in regard to battery, once so favorably looked upon by naval economists, seems to be losing its prestige as a fighting factor, since you pin your faith on one weapon. If your engines happen to break down you are at the mercy of the enemy.

Vessels designed to act as rams should be very handy, and therefore not large. Since they are pre-eminently of the line of battle, they should be armored or at least well protected.

It may be set down as a maxim that machine guns will play a prominent part in future naval combats. Every ship should have machine guns for the destruction of torpedo-boats close alongside.

Musketry and mechanical gun fire from on deck and aloft will be most useful. Not only do the decks offer a field for destruction, but the open gun-ports give entrance to the battery, into which your heavier projectiles may fail to penetrate.

All authorities are agreed that ships will fight at great speed; they will come close to one another on a charge and then separate, turn and charge again; therefore, the time through which small-arm fire can act and be useful is very short. The crew should be trained sharpshooters, being armed with rifles distinguished for rapidity and accuracy of fire rather than for length of range. Boarding will seldom or never be resorted to.

In an action the smaller guns of the battery, as well as the machine-guns, should fire at the enemy's upper deck and lightly-protected portions.

So much progress has been made in foreign navies with the automobile torpedo, that it is considered a perfectly reliable weapon within 400 yards, and that any nearer approach than this of the enemy makes it an extremely hazardous undertaking for him. In fact, the risk is so very great that, in the opinion of a German writer, ramming will hardly be attempted against any but defenseless ships. It may be mentioned here that the French, in addition to the automobile torpedo, are now using *divergent torpedoes*, which are towing-torpedoes, with a short scope of line.

VI.

It has been proposed to classify torpedo-steamers as follows:

To a class capable of operating outside of harbors, and of keeping the sea in bad weather, but generally to be carried by a special vessel, the name of *torpedo-vessels.*

The next smaller size to be used in harbor defense, and which will not accompany the fleet, the name of *torpedo boat.*

And, for the smallest class, such as are fitted to be carried by cruising vessels, the name of *torpedo-launches* or *torpedo-pinnaces.*

Lieutenant Campbell does not believe that line-of-battle ships should be fitted to carry torpedoes; but that they should have two "torpedo cutters," that they can always lower and use either aggressively or for defense. They should be capable of good speed, and be lowered ready for action when up with the enemy.

However, with all the varying phases of wind and weather on the open sea, it is hard to conceive how a line-of-battle ship can carry torpedo-boats large enough to be of service in an engagement. It will be difficult to lower them, and, if they have to be towed, it will interfere with the movements of the fleet, and they will at all times be liable to be swamped. They carry so little coal and provisions that they will need filling up very often, which will be difficult to do. Torpedo-boats of this kind are veritable *impedimenta* to the fleet, especially when, having lowered them, the fleet is obliged to defend them in retreat.

But, if they have these drawbacks, they should still be carried by ships of the line, as their utility in fleets will not be the less for defending ships at anchor, in acting as "lookouts," and to fight, if necessary.

The typical sea torpedo boat is a sea-going cruiser, able to carry its own crew, provisions, and coals. She should be a vessel of from 200 to 400 tons displacement, and should have immense speed and great turning power. There should be two to each ship of the line of battle, and they should cruise close to them. They should render offensive and defensive succor at all times, and might be used to tow out of action any disabled vessel. They should also keep an eye on the smaller torpedo-boats.

The most modern idea is that there should be a special vessel not of the line of battle, which should accompany a fleet, and which should be fitted to carry as many as possible of the largest-sized torpedo-vessels. She should be able to get her boats out and lower them, or pick them up, in the open sea.

The Italians have lately brought to notice a vessel of war, about 150 feet long, displacing 600 tons, and capable of making 25 knots. She is protected; almost, if not quite, unsinkable, and has excellent turning power, being fitted with two screws. Her weapons are the ram, two light guns forward, a heavy gun aft with great sweep of fire, and three decks of machine guns, about forty-five in all, which admit of fire in all necessary directions. There are two or more tubes for discharging automobile torpedoes. She is designed as a torpedo-boat destroyer, and is probably intended to accompany and act with the fleet.

CHAPTER III.

THE SHIP AND HER CAPTAIN.

I.

To command a modern vessel of war, the captain is called upon to post himself on points that formerly could, very properly, be left to his subordinates. Now he commands more than a ***ship*** ; he is in supreme charge of a missile, which is projected by power within itself. This missile, instead of moving in the medium of air, moves in air and water, both elements influencing its trajectory. It acts either as a ***shot***, and rams an opponent, or like a ***shell***, extending its destructive influence outside the confines of figure by means of guns or torpedoes.

The commander should thoroughly understand that he must, as the soul of this huge machine, comprehend fully all the complex results of invention which science, working through the mechanical arts, has accomplished, enabling him to transmit his scheme of action to the ponderous mass beneath him. His ship has her strong points and her weak ones. How to keep his mail between himself and the enemy, how, in case of extensive penetration, to save his ship, are points demanding his constant study.

What does the command of the modern ship in action require further, for the proper employment of the ram and torpedo? Let three eminent authorities speak.

Admiral the Count de Gueydon says:

> Above all, ***steady nerves***, an accurate eye, and a sure hand. Science cannot develop these qualities; practice alone can.

Admiral Bourgois remarks:

> There is nothing like quick judgment and ***sangfroid***. In action, captains must expect to have their designs frustrated by smoke from funnels and guns. The ordinary fleet maneuvers are in no way capable of teaching a captain his duty; this must come from drill against properly-constructed targets.

Admiral Jurien de la Gravière has described in graphic language the sort of training which is necessary in order to prepare officers for the rapid and desperate maneuvers of a battle with the ram. He remarks that after the first charge has taken place on both sides, the fight can only be renewed by the fleets turning and charging again. This turning will be the cause of innumerable fatal collisions between ships of the same side, unless the captains are thoroughly drilled. They must not only know tactics theoretically, but they must be perfectly certain of their ships, know what they are capable of, and, in case of breaking down or other accident, how to act to keep them out of the way of friendly vessels, and how best to present them to the enemy to offset their crippled condition. This experience cannot be obtained in the class-room or in small vessels. To be successful, the nerve of the captain must grow with his experience, and this condition of affairs can only be brought about by drilling in fleet tactics in line-of-battle ships, where collision means fatal damage, or by exercising at night in close order.

Unquestionably *nerve* is to be obtained only by actual experience, and unfortunately the use of large vessels for purposes of drill is expensive. If, however, this quality is *necessary*, our officers must be given the chance of actual practice, or they will fall behind those of other navies who have had it. Without preliminary exercise it is impossible to acquire that skill and precision in maneuvering which will be necessary for the conduct and safety of the ship or the fleet in the day of battle.

II.

The duty of the captain does not end with his own vessel; each captain, to be successful, must be thoroughly versed in naval tactics, which is now of more importance than ever before.

The Signal Book must be his constant study. Plans of actions must therein be laid down, and their minutest details committed to memory. A wrong turn, a slacking of the speed in time of battle, may mean confusion, if not destruction, to the fleet, as may also the rendering of inefficient support, through ignorance or inexperience, to one's neighbor.

III.

Captain the honorable Edmund R. Fremantle, R. N., asks the question:

> How many naval officers care to know the number of degrees of helm that can be given to their ships; the tending of the screw to turn the ship unassisted by the rudder; the effect of turning the engines astern when the ship has head or stern way; the result of increasing or reducing speed on the circle described in turning; what the nature of the so-called circle is; what the reduction of speed by putting the helm hard over; what heel a helm hard over may be expected to give the ship; what the drift angle means; what is the time of completing a circle at different speeds and its diameter?

Yet all these things must be known and more too. When the vessel leaves the dockyard she develops a strategical and tactical character requiring perhaps unlooked-for care, study, and watchfulness on the part of the captain. He must know how much coal is used at the different speeds and under different conditions of environment; what is the most economical expenditure of coal for speed developed. The working of the helm; can it be moved from side to side as rapidly as it should be to obtain the best results? Her easiness at sea; to what extent is she influenced by it in her rolling and pitching? Are her guns capable of use at all times, and can concentration of fire be quickly effected, &c.?

It would take too much space and be unnecessary, we think, to enter into details concerning the internal offensive and defensive economy of the ship, but it all bears upon naval tactics, and demands deep thought on the part of the commander.

After her speed has been established, and after the "Speed Table" has been filled out, comes in the determination of the ship's turning qualities. Experiments must be made under all circumstances called for in the "Helm Table," in which should be all the points bearing on fleet evolutions. Captain Noel, R. N., sums up these requirements, as follows:

1st. Speed at various revolutions of the engines.

2d. Everything in connection with the ship's turning qualities, including backing with and without the helm.

3d. Time required to bring the vessel to a state of rest by stopping and reversing the engines. This to be known for different speeds.

4th. The amount of helm required to turn at a certain standard speed on a certain standard arc.

Then as to the *sheering* of the ship (it is most important to be posted on this point); with a certain helm-angle and a certain speed, to find out the exact instant when to use the wheel in order to pass over a certain spot. Then again, as regards the engines, the captain must know what they are capable of doing under great stress; the amount of power that can be developed in going ahead or astern, and the length of time that it can be kept up.

The captain should see that his subordinates likely to succeed him in a fight are also fully informed on all these points.

A new element is the electric light. The best place for its installation on board ship is a question; where to put it so that the glare will least interfere with the observer. Officers will have much to learn concerning the judging of distances and the recognition of objects when this light furnishes the means of illumination.

After the captain has become familiar with his ship, his command must be associated with another vessel, and the two captains must be thoroughly drilled in their duties of mutual support. Upon the interdependence of vessels hangs the chances of victory. This section-drill should be had under all conditions of wind, weather, and speed. By it alone can the captain hope to take his place in the line of battle with any feeling of security.

IV.

We come now to consider the commanding officer's duty in action. The most eminent question is, what is the proper target for the ship? Is it the enemy's armor or the boilers and engines or the people on board? We should strive to deprive the enemy of his most important war factor, and we believe this to be the crew and officers. Knowing the ship, we should fire into the least protected part where the men are congregated, concentrating, of course, as many guns as possible upon her. We should remember that a ship lying still is not necessarily deprived of the use of *all* her weapons, so that disabling the machinery is of less value than killing the crew. The general rule to fire at the funnels is worthless. Not only should the captain and his officers be thoroughly conversant with the construction, as regards vulnerability, of the enemy's vessels, but this knowledge should extend to the leading seamen of the ship's company.

Another question arises: Is the *capture* of the vessel the principal object of the fight? From the opinions advanced by the leading naval minds we answer in the negative. Rams and torpedoes are used with but one view—the total destruction of the ship. If by killing the ship's company we reduce the enemy to a harmless state, we should, of course, take him as a prize; but the rule is to *sink* and *destroy.*

In order to use fore-and-aft fire in chase or retreat, or to know at any time the distance of the enemy, some quick method must be used to measure the interval separating ships, as nowadays such great speed is kept up, and a table of mast-head angles is too slow and too uncertain a method to furnish the necessary information. Too uncertain from the fact that some vessels are not sparred, and if they are sparred, the housing of light masts destroys the efficiency of the tables. Buckner's method is probably the best, or the distance should be determined by some kind of telemeter.

It may sometimes come within the experience of a captain to determine whether or not he should refuse combat. His action will be more or less governed by the following considerations, especially if the vessel is a great distance from home:

1st. Are the means at hand for repairing and for refitting safe and sufficient?

2d. Do not the interests of our specific work demand our not running the risk of getting crippled, and thus hinder us from keeping the sea?

V.

There are two opinions, each directly opposed to the other and each covering the ground pretty well, bearing on the subject of the protection of the captain in action.

One side is represented by the writer of an article in the German Naval Official Publication. His opinion seems to be based on the results obtained lately in the German evolutionary squadron. The author is strongly opposed to proof-protections for the commanding officer. The captain is, in his opinion, in no greater danger *now* than he was a hundred years ago; but the fighting is livelier, and the methods of conducting a battle are more varied. If the captain is hidden he cannot see and control his ship. With smoke obscuring the fight, with guns above and rams and torpedoes below the water-line, he must be everywhere at the same time, otherwise in the confusion of battle he cannot be properly prepared to meet the dangers which beset him. To confine him at this time to a shelter is to circumscribe his view, as upon his sight, his actions depend and his judgment is governed.

On the other hand, M. Dislère in his work entitled "La Guerre d'Escadre et la Guerre de Côtes," takes exactly the opposite stand. He urges most strongly protection for the captain. It may be observed that Mr. Dislère represents the opinion of the larger number of writers upon this subject when he says:

> The captain must be protected against small-arm and shell fire for two reasons:
>
> First. Because it is necessary to put into the hands of the captain the steering of the ship, or at least under his direct supervision should be the person stationed to steer the ship. It is necessary then to have a fighting wheel on the bridge; and, if so, it must be protected.
>
> Secondly. It is difficult to replace the commanding officer during a fight.

There is still another reason for protecting the captain. If he falls during the performance of an evolution, no one, not even the officer by his side, can continue the train of thought and action to any profitable conclusion, or follow the first impulse of this instant, and upon which may depend the success of the fight.

CHAPTER IV.

EVOLUTIONS OF THE SHIP.

I.

In the last chapter we said that the following must be known of the ship:

1. Speed at different number of revolutions of the engines.
2. Turning power at different speeds.
3. Helm angle required to turn on a certain arc at a certain speed.

We will proceed now to discuss in detail the methods by which all these *data* may be obtained.

To use the different arms effectively requires one of these qualities to be more prominent than the others; for instance, in the opinion of many, turning power may be looked upon as the most important for a ship when used as a ram or to discharge torpedoes; whereas, for general work, speed is the most desirable quality.

For the use of artillery we need steadiness of platform, besides the evolutionary qualities under consideration. But this hardly comes within the province of tactics, belonging more properly to the naval architect.

II.

The reason that a ship in turning does not describe a circle is due to the fact that when the helm is put over she is moving in a straight line, which her momentum seeks to continue. It is only by degrees that she yields to the rudder, and then she is always some time behind it. The quicker that the helm can be put over the quicker will the vessel respond, and also more rapidly will the diameter of the turning circle decrease, and the time, if the helm angle can be increased up to 40° or more. We must have great angular movement for rudders and their connections, and quick-acting power immediately available to move the helm.

The radius of the turning circle for ordinarily large vessels is about 300 yards with a working speed of 8 knots.

Seamen generally agree that all single-screw steamers turn more quickly to one side than to the other under similar helm angles, and it is important to the naval officer to ascertain his ship's qualities in this respect. The rule is that the bow turns towards that side to which the descending blade of the screw falls. Thus a ship with a left-handed screw turns to port, or must be steered with port helm to keep her on her course. With ships of light draught it is said the contrary is the case.

Prof. Osborne Reynolds states that the distance required to bring a screw steamer to rest from full speed ahead, by the reversal of her engines, is independent, or nearly so, of the power of the engines, but depends on the size and build of the ship, and is generally between four and six times the ship's length.

III.

The two subjoined tables must now be filled out by every ship which expects to drill with the fleet, or to take her place in the line of battle. The "speed-table" takes cognizance of the speed of the ship for the different number of revolutions, and under different circumstances of wind and sea. The "helm-table" is a record of the ship's *advance* and *transfer*, also the *time* it takes the ship to turn through 45°, 90°, 135°, and 180°, under all conditions of wind and sea, and whether the turn is made toward or away from the wind. There must be a helm-table made out for each speed, say three speeds, which may be denominated "full," "fast," and "slow."

The speed-table is intended for ships steaming in squadron. To use it, we must have one filled out for every vessel associated with us. Suppose the leader of a line ahead makes a certain speed with 70 revolutions with sea rough, wind abeam, with a force of 4. Some other ship, in order to keep her place in the formation, in other words to make the leader's speed, can by reference to the leader's and her own table, having received the leader's signal as to the number of revolutions he is making, see that she need, under these circumstances, make only 60 revolutions.

So with the helm-table, every ship must have her own and her associates' for each speed. We are steaming in line ahead, and the signal is made to change direction 8 points to port, the sea being rough, the turn being made towards the wind, its force being 6. Turning to the table for this particular speed of the ship with the largest tactical diameter, and knowing that she will use 40° helm angle, we find a certain number of yards "advance," a certain number of yards "transfer," and a certain number of minutes for "time." Turning now to our own table for this same speed we see that the nearest figures under the same circumstances give us a helm angle of 35°. We therefore use this and find we keep our station and fulfill the required conditions.

FORM OF SPEED-TABLE.

Number of revolutions.	State of the sea.	Wind.																	
		Ahead.						Abeam.						Aft.					
		Force.						Force.						Force.					
		1.		4.		7.		1.		4.		7.		1.		4.		7.	
		K.	F.	K.	F.	K.	F.	K.	F.	K.	F.	K.	F.	K.	F.	K.	F.	K.	F.
75	Smooth	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
	Rough	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
	Very rough	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
70	Smooth	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
	Rough	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
	Very rough	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
65	Smooth	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
	Rough	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
	Very rough	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
60	Smooth	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
	Rough	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
	Very rough	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
55	Smooth	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
	Rough	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
	Very rough	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
50	Smooth	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
	Rough	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
	Very rough	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
45	Smooth	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
	Rough	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
	Very rough	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
40	Smooth	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
	Rough	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
	Very rough	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
35	Smooth	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
	Rough	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....
	Very rough	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....	....

FORM OF HELM-TABLE.

[One for each speed.]

Helm angle.	Turning as to wind.	Direction of turn.	Force of wind.	Advance.												Transfer.												Time.											
				45°.			90°.			135°.			180°.			45°.			90°.			135°.			180°.			45°.			90°.			135°.			180°.		
				Smooth.	Rough.	Very rough.	Smooth.	Rough.	Very rough.	Smooth.	Rough.	Very rough.	Smooth.	Rough.	Very rough.	Smooth.	Rough.	Very rough.	Smooth.	Rough.	Very rough.	Smooth.	Rough.	Very rough.	Smooth.	Rough.	Very rough.	Smooth.	Rough.	Very rough.	Smooth.	Rough.	Very rough.	Smooth.	Rough.	Very rough.	Smooth.	Rough.	Very rough.
Hard over	Towards	Starboard	0 to 4																																				
			4 to 8																																				
		Port	0 to 4																																				
			4 to 8																																				
	From	Starboard	0 to 4																																				
			4 to 8																																				
		Port	0 to 4																																				
			4 to 8																																				
40°	Towards	Starboard	0 to 4																																				
			4 to 8																																				
		Port	0 to 4																																				
			4 to 8																																				
	From	Starboard	0 to 4																																				
			4 to 8																																				
		Port	0 to 4																																				
			4 to 8																																				
30°	Towards	Starboard	0 to 4																																				
			4 to 8																																				
		Port	0 to 4																																				
			4 to 8																																				

30°	From	Starboard	0 to 4																																				
			4 to 8																																				
		Port	0 to 4																																				
			4 to 8																																				
20°	Towards	Starboard	0 to 4																																				
			4 to 8																																				
		Port	0 to 4																																				
			4 to 8																																				
	From	Starboard	0 to 4																																				
			4 to 8																																				
		Port	0 to 4																																				
			4 to 8																																				
10°	Towards	Starboard	0 to 4																																				
			4 to 8																																				
		Port	0 to 4																																				
			4 to 8																																				
	From	Starboard	0 to 4																																				
			4 to 8																																				
		Port	0 to 4																																				
			4 to 8																																				

It is of the utmost importance that all the elements of the turning-circle should be known. There are many methods of finding them, but we will confine ourselves to those of Captain Colomb and of Mr. White, R. N.

In Captain Colomb's experiments with the Thunderer all the elements can be derived if the discussion is carried through a whole turn, or 32 points.

Some of the qualities of the turning circle bear more on naval tactics than do others, for instance, the *advance* and *transfer* are of the highest importance, especially to a ram; they should be known, however, for every ship. The determination of *tactical diameter* is also imperative.

The *loss of speed* in turning through a whole circle may be assumed at three times the length of the vessel.

A vessel with two screws, if she goes ahead on one and backs on the other, describes a spiral which constantly diminishes until its diameter becomes nothing, when its motion of translation ceases. If this vessel went ahead on one screw and stopped the other she would describe a turn of less diameter than if she went ahead on both screws and used her helm hard over.

The curve, which a ship with a single screw makes in turning, has generally been set down as a circle, and when the helm is righted she is supposed to start off on a tangent to this circle. As we have before stated, this is not so. Although the assumption may answer for the ordinary purposes of fleet drill, it would prove wofully inaccurate in fighting with the ram. The question then is, what curve does the ship make? On this point we trust the authorities we quote will enlighten us.

IV.

Captain Colomb, R. N., in discussing the turning-circles of vessels expresses substantially the following ideas as the result of his experience:

The maneuvering powers of ships comprise their powers of turning and of losing and gathering way. The measures of these powers are always twofold, *time* and *space.*

The time and space measurements of turning powers are much more numerous than those of losing and gathering way; but we are not masters of the maneuvering power of any ship until we know both and the principles which govern them.

We now take up the analysis of a single turning experiment to see what principles govern it.

Plate IV, Fig. 1, shows the trace of the curve made by a vessel in turning. The curve is drawn differently from what has been usual in the first part of the turn. When the trace is assumed to be that of the center of gravity, near the middle point of the ship, it has been usual to show the arc it describes at the beginning of the turn as tangential to the original course. There are, however, good reasons for believing that the curve described is more truly represented in the figure. It is certain that the stern of the vessel does not describe a curve to which the original course is a tangent, and of this we will be given one conclusive proof. If two ships are steaming in line ahead in smooth water, and the order is given to alter course in succession, say to starboard, the sternmost ship will see that the foremast of the headmost ship does not alter its bearing for some time after the stern has swung to port, and the wake of the leading ship will have a bend in it to port, which becomes an excellent mark for the sternmost ship to go by for putting over her own helm when she comes to this point. It is called the "kick." (See Plate IV, Fig. 2.)

The two things which oppose a ship's turning when the helm is put down, the ship steaming ahead, are *inertia* and *water-resistance.* They are remarkably different in effects, inasmuch as inertia, as an opposing element, is at its *maximum* when motion *begins*, and when water-resistance is at its *minimum.* Then, as we go on applying the accelerating force of rudder-power, or other force which has a moment about the pivoting point of the ship, we generate angular momentum, and then water-resistance. When we have once started the ship, so that every point in the middle line begins to revolve around the pivoting point, we get momentum of all the particles in the ship around this point. There are in fact moments of momentum set up by the first action of the rudder, which are added to the moment of rudder-power and increase as the angular velocity increases. But a check to this growing angular velocity is developed by the increasing resistance of the water. Then we have tending to turn the ship round on the pivoting point moments of momentum and moments of rudder-power, which are opposed by moments of water-resistance. It is evident that ultimately moments of momentum must be equal to moments of water-resistance, and that there will remain the constant force of the moments of rudder-power opposed also by equal moments of water-resistance, leaving no unbalanced forces, and so giving a uniform angular velocity to the middle fore-and-aft line of the ship, and she turns in a circle. This circle is spoken of as the *final circle.*

By absolute experiment it has been determined that the first quadrant of the circle is passed through in the quickest time, although the distance traversed is greater than in any subsequent quadrant. Until the final circle is entered upon, these three phenomena present themselves for every successive quadrant, less speed, shorter paths to traverse, and a longer time to perform that part of the turn.

Captain Colomb gives us a method for measuring the turning powers of the ship, which is as follows (some slight modifications have been made in the instruments used, others having been suggested, but the plan of the experiment has not been interfered with):

Choose a calm, still day in the open sea, but in view of a distant point of land or object sufficiently conspicuous for observation. Prepare two casks with flags or staffs, each flag to be of a different color. Care must be taken to weight the casks, so that a very few inches remain above water; this in order to prevent wind-drift, an element calculated to mar the accuracy of the experiment.

Alidades with dumb compasses or plane-tables, and sight-vanes or gun-directors, are to be placed one forward and one aft on the side towards which the turn is to be made. These sighting instruments are to be put the same distance from the fore-and-aft middle line of the ship. The distance between them to be as great as the length of the ship will allow. All angles observed will be reckoned from a *zero point*, which is right abeam. The distance between the sighting instruments is the base line of the triangle. The graduated ring of the standard compass and the alidade mounted thereon will be used for observing the distant point of land. Four observers are necessary; one to note the successive bearings of the distant point and change of direction of the ship's head for every 4 points, one to note the times, and one at each alidade to note the angles between the perpendicular to the base line and the bearing of the buoy about which the ship is turning.

All being in readiness, the two buoys are to be dropped about 1,500 yards apart, on a bearing convenient for observing the distant object at each point in the turn around either of them. A hand is stationed to sound the engine-room gong and another hand is stationed at the steam whistle or steam siren, if the ship is fitted with one. The engineers are ordered to note the engine counter at each sound of the gong, and the man at the whistle is directed to sound it at the orders, "Stand-by!" and "Stop!" the gong to the engine-room being struck at the order "Stop!"

The ship is now put on a course nearly parallel to the line of the buoys and at the speed desired. (See Plate V, Fig. 1.) One buoy is passed in this manner, but when the second buoy comes about 4 points on the bow, the observer, noting the time, gives the words, "Stand by!" and "Stop!" The siren sounds for each, and at the second, the helm is moved to the determined angle, the observer at the compass notes the position of the ship's head both by the compass and the bearing of the distant point of land, and the engineers note the engine counter, while the observers at the bow and stern note the bearing of the buoy. As the ship arrives at 4, 8, 12, and 16 points change of course, the observer at the compass in like manner gives the words, "Stand-by!" and "Stop!" when the siren or whistle sounds and the time, bearings, angles, and revolutions are taken.

When a series of observations completing the turn of 16 points is thus taken, the ship proceeds on a course nearly parallel to the line of buoys, and a turn of 16 points is made around the other buoy, either at the same speed and helm angle or with any desired variations of either or both. The experiment may, of course, be varied by stopping or reversing one or both engines in a vessel with twin-screws at any point in the turn; and in all cases the exact position of the ship, when she has turned through 4, 8, 12, and 16 points, respectively, can be laid down from the observations. The method, Captain Colomb says, works exceedingly well and speedily, and is remarkably accurate.

The plan will be understood from Plate IV, Fig. 1, which represents an actual complete experiment. Here the ship has arrived on a straight course at the point P, then going 5 to 5½ knots with 35 revolutions. At this moment the helm is ordered 34° a port; the angles *abh* and *bah* are observed, the engine counter noted and the time taken. At d^1 the ship has turned by compass and bearing 4 points. At d^2 she has turned 8 points, and so on, and at each position the observations are repeated, the experiment being complete when the middle point of the ship is at d^4. The respective positions can easily be laid down to scale by a protractor with sufficient accuracy for practical purposes. The object of having two buoys is to save time and to allow the ship to recover herself on a straight cause before repeating the experiment.

It will be noted that this plan of measuring the turning-circle of a ship is only very good where the length of the ship is great, on account of the shortness of the base line.

V.

Mr. W. H. White, naval constructor, R. N., goes very thoroughly into the subject which we are considering, as may be seen by reading his lecture delivered before the Royal United Service Institute, a report of a portion of which is as follows:

> It is worth notice that when a ship is moving ahead under the assumed conditions in smooth water and a dead calm she is in *unstable equilibrium* so far as the maintenance of the straight course is concerned. That is to say, the action of a very small disturbing force will suffice to deflect her from that course. Directly the helm is put over, and an unbalanced pressure is developed on the rudder, that pressure constitutes a disturbing force, and the vessel begins to turn. Her angular motion is gradually accelerated as the helm angle is increased, and after the helm is "hard over." After reaching its maximum rate the angular motion of the vessel becomes uniform; and thenceforward if the helm angle and revolutions of the engines remain unaltered the vessel continues to swing round through equal angles in equal times, her center of gravity describing a circular path, and all other points moving in concentric circles. When there is powerful mechanical steering gear, capable of putting rudders of large area over to good angles in very small times, this condition of uniform angular motion is quickly reached, probably by the time the head of the ship has swung through 360° or even a less angle from the original course. With manual power at the helm, it is stated on good authority that similar uniformity of angular motion is not obtained until the ship has completed two circuits or even more. The longer time occupied in putting the helm over with manual power accounts for this difference.
>
> In order to determine the motion of the ship in turning it is convenient to take the following:
>
> (1.) The original straight course, as *line of reference*, from which to measure the angles turned through by the keel line of the ship in specified times.

(2.) The position of the center of the ship on the straight course at the instant when the helm begins to move over, as an *origin of co-ordinates.*

(3.) The path which the center of gravity describes while the ship turns, as that to be determined by observation. This will practically agree with the middle of the length in most ships.

It will be obvious that if by observation we can determine the place of the center of gravity at any instant with respect to the original course and the selected origin of co-ordinates, the path can be constructed. Also, that if the angles through which the head of the ship has turned are noted at the same times as the positions of the center of gravity are observed, the instantaneous positions of the keel line are found, and the instantaneous inclinations of the keel line to the corresponding tangents to the path of the center of gravity can be ascertained.

When the motion of rotation has become uniform, and the center of gravity is moving in a circle, the keel line of the ship makes a *constant* angle with the tangent to the circular path of the center of gravity. Plate IV, Fig. 3, illustrates this case. A represents the bow and B the stern of a ship. G shows the position of the center of gravity on the keel line AB. O is the center of the circular paths in which G, A, and B are moving. TGT_1 is the tangent to the path (G, G_1, G_2) of the center of gravity; and the angle (AGT) made by the keel line with the tangent is termed by the French *angle de dérive*, or "drift angle." The value of this drift angle varies considerably in different vessels, and in the same vessel under different conditions of speed and helm angle. In the Thunderer, for example, with a constant helm angle, but with variations in the speed, the following results were obtained:

Speed on straight.	Drift angle.	Diameters of circles (feet).	
		Bow.	Stern.
Knots.	°		
8.2	5¼	1,350	1,410
9.4	8¼	1,255	1,345
10.4	9¼	1,240	1,340
11.14	9½	1,240	1,340

Other cases are on record where the drift angle has been 16° or 18°. No general law has yet been formulated for the magnitude of the drift angle, but it is generally agreed that it increases (*a*) with increase in speed, when helm angle and rudder area are constant; (*b*) also with increase in rudder area and helm angle, speed being constant. As a consequence of the drift angle, the bow and stern of the ship revolve in circles of different diameters, and in the above table the results for the Thunderer furnish an illustration of the fact. Furthermore, in any given time the head of the ship must have turned through an angle from the original course which exceeds the angle turned through by the center of gravity by a quantity equal to the drift angle.

Turning again to Plate IV, Fig. 3, let P be the foot of a perpendicular let fall from the center O upon the middle line of the ship (AB). Then to an observer on board the ship, P will appear to be the "pivot point" about which the angular motion of the ship is being performed at each instant; for it will be seen that the keel line AB coincides with the tangent to the path of the point P, which is not true of any other point on the keel-line. In other words, at P there is no drift angle; whereas for every other point in the keel line there is a drift angle, the value of which is easily determined when that for the center of gravity, G, and the radius, OG, have been determined. In the case of the Thunderer the pivot point, P, varied from 67 to 103 feet before the center of gravity, or from about 80 to 40 feet from the stem. As the speed and drift angle increased, so the pivot point moved forward. It need hardly be added that the point G is the true center of the motion of the ship in turning, although P appears to an observer on board to be the pivot on which the ship turns during the time she has uniform angular velocity.

Another circumstance requiring notice in connection with the uniform turning motion now under consideration is the *loss of speed* sustained by the ship when turning, as compared with her speed on the straight course from which she began to turn. Taking several cases where this loss has been carefully measured, I find that the speed of advance on the circular path has only been *seven-tenths* or *eight-tenths* of the speed on the straight. It is often supposed that this loss of speed is chiefly due to the "drag" of the rudder. Any one who investigates the matter will become convinced that the rudder pressure has little to do with this considerable decrease in speed; the real cause is to be found in the drift angle. Glancing once more at Plate IV, Fig. 3, it will be evident that, at each instant, while the propelling force is delivered along or parallel to the keel line, the actual motion of the vessel in turning is not directly ahead, but sideways. In fact, the motion bears a considerable resemblance to the motion of a ship sailing on a wind; and there is a considerable pressure developed on the side of the bow most distant from the center, O. This pressure not merely checks the speed of the ship, but exercises a considerable turning effect, assisting the pressure on the rudder. The importance of this assistance will appear more clearly when it is considered that owing to the rotary motion of the vessel while turning, the flow of water at the stern is different, even in screw steamers, from that which would take place before the angular motion became considerable. In fact, the *effective* helm angle becomes considerably reduced from the angle RBD, Plate IV, Fig. 3, which the rudder makes with the keel line AB, produced. So far as I am aware, we have no exact data for estimating the amount of this reduction; but French experimentalists assert that it approaches to equality with the drift angle for the rudder axis B. If OB is joined, and BQ drawn perpendicular to it, then the effective helm angle, according to the French rule, should be taken as approximately equal to RBQ, and not to DBR, or a reduction of at least *one-half* from the angle made with the keel line, even in single-screw ships. Approximately the pressure on the rudder may be expressed as a function of the speed of the ship, and the *sine* of the effective angle of helm; so that the loss of rudder pressure consequent upon such a reduction in the effective angle as is asserted to take place will be very considerable. Apart from exact measures of the reduction, there can be no question as to the fact; and it is one of the matters upon which further experiments might well be made in English ships. With the assistance of a dynamometer to register the strains on the tiller end when the helm is first put over, and after the turning motion has become uniform, it would be an easy matter to discover the variations in the effective helm angle if the revolutions of the engines and speed of the ship were also observed.

In concluding these remarks on uniform angular motion, it may be well to refer to the *heeling* which accompanies turning. The forces which tend to produce heeling are as follows:

1. The centrifugal force acting outwards through the center of gravity of the ship and tending to make her heel away from the center of the circle.

2. The lateral component of the rudder pressure, acting through the center of pressure of the rudder at some depth below the center of gravity of the ship, and tending to make her heel inwards towards the center of the circle.

3. The lateral component of the fluid resistance on the outer side of the ship, which equals in magnitude the resultant of the centrifugal force and the rudder pressure, and acts through the center of lateral resistance.

Plate V, Fig. 2, shows the distribution of these forces in the Thunderer, determined from the turning trials made at Portland. Here again it is common to find the rudder pressure credited with the heeling effect; whereas it may, in most cases, be neglected in comparison with the centrifugal force. A fair approximation to the angle of heel for a ship in turning is given by the following equation:

$$\sin \theta = \frac{1}{32} \times \frac{d}{m} \times \frac{v^2}{R},$$

where $\theta =$ angle of heel,
$v =$ speed of ship in feet per second,
$R =$ radius of circle turned (in feet),
$m =$ "metacentric height"—height of transverse metacentric above center of gravity,
$d =$ distance of center of gravity above center of lateral resistance.

In the Thunderer, the center of lateral resistance was found to be from .43 to .49 of the mean draft below the water line; probably a fair approximation for war ships or ordinary form would be from .45 to .5 of the mean draft. From the foregoing equation it will be seen that—

The angle of heel varies (1) Directly as the *square of the speed* of ship;
(2) Inversely with the *metacentric height;*
(3) Inversely with the *radius* of the circle.

Hence it is obvious that ships of high speed, fitted with steam-steering gear, capable of turning on circles of comparatively small diameter, are those in which heeling may be expected to be greatest. Moderate values of the metacentric height further tend to increase the heeling. If the speed be *doubled*, the angle of heel will be about *quadrupled*, if the radius of the circle turned and the metacentric height remain constant. In order to maintain a certain angle of heel under these altered conditions of speed, the metacentric height would also have to be quadrupled; but such an increase in stiffness is clearly undesirable even if it were practicable. The following figures may be interesting:

	Speed on straight.	Diameter of circle.	Draft.	Metacentric height.	Angle of heel.
	Knots.	*Feet.*	*Ft. in.*	*Feet.*	° '
Thunderer	8.2	1,340	26 3	3.12	0 52
	9.4	1,250	26 1		1 11
	10.4	1,240	26 1		1 14
Tourville (French)	15	2,030	....	....	3 30
Victorieuse (French)	10	1,290	....	....	2 0

It is important to notice that in taking observations of the angle of heel for a ship in turning, allowance must be made for the effect of the centrifugal force upon the indications of pendulums or clinometers. The error of indication is always in excess, and the correction is very easily made when the diameter of the circle and time of turning have been ascertained.

In treating at some length the case of a ship turning uniformly in a circular path, I have endeavored to clear the ground somewhat for the discussion of the more difficult case, which has far more practical importance, where the angular motion of the ship is not uniform and the path of her center of gravity is not circular. When the helm of a ship is put down, and she begins to turn away from a straight course, it is interesting to know (1) whether she will readily answer her helm; (2) what will be the path traversed by her center of gravity; (3) what will be the rate of growth of her drift angle; (4) what will be her gradual loss of speed as compared with her speed on the straight course. Probably the most important pieces of information in relation to naval tactics will be as follows: 1. The place of the center of gravity of the ship when her head has swung through 90° from her original course; that place being fixed (in the manner previously described) with reference to the original course and the position of the center of gravity thereon at the instant the helm begins to move over. 2. The speed of the ship when she has turned through the first 90°. 3. The time occupied in turning 90°. 4. The time and space required to reverse the course, turning through 180°.

It is singular to find on inquiry how meager is the information recorded on the first three of these points. I can discover no case except that of the Thunderer in which the actual path traversed by the center of gravity of the ship has been determined from the instant the helm was put down to the time when the turning motion had become uniform. All the facts as to these trials have been published in the report of the Inflexible committee, and they deserve the careful study of all naval officers. I do not propose to reproduce them there, but to use a few of the results only for purposes of illustration. Plate IV, Fig. 4, shows the course traversed by that ship, when turning from a straight path on which her speed has been 10.44 knots. On analyzing the companion diagrams for this speed, I find the following results, reckoning times from the instant when the helm was begun to be put over:

	Time.	At end of time.	
		Speed of ship.	Angular velocity per second.
	Seconds.	*Knots.*	° ′
To put helm over 31°	19	10.4	0 20
To turn ship's head 45°	56	9.25	1 18
To turn ship's head 90°	89	8.3	1 18
To turn ship's head 135°	123	7.75	1 15
To turn ship's head 180°	159	7.5	1 12
To turn ship's head 360°	320	7.14	1 6¼

At 360° the turning motion had become practically uniform. The conditions here traced for the Thunderer are representative for all steamships when turning under the action of their rudders from a straight course on which they were originally moving ahead. There will, of course, be differences in different ships as regards the times occupied in putting the helm down, or in passing through the various changes which precede the attainment of uniform angular velocity, as well as in the value of that velocity. But in all cases as a ship turns from her straight course she will be subjected to angular acceleration, her drift angle will gradually increase, she will heel more and more, and her speed will decrease. But by degrees these transitory conditions will pass away, if the helm is kept at a constant angle, and the engines at a nearly constant speed, and ultimately a state of uniform motion and steady heel will be reached such as I have previously attempted to describe.

Purely theoretical investigation does not enable one to lay down the path of the center of gravity of a ship from her straight course to the position occupied when the head has turned through 90°; nor are we much better off for the remaining part of her path until the turning becomes uniform. The greatest difficulty in framing the equations of motion arises from the uncertain state of our knowledge respecting the resistance offered by the water to the motion of the ship in turning. Hence it becomes necessary that the problem should be attacked by actual experiment, and careful observations made, which would enable the path traversed to be subsequently plotted. French writers assert that the curve traversed by a ship from the place where her helm is put over to her place when she has turned through 180°, can be treated without serious error as a circle touching the original course. The perpendicular distance from the place of the center of gravity when the head has turned through 180°, to the original course, is termed by the French the "diameter of evolution." Captain Colomb has proposed to call it the "tactical diameter." Unfortunately the Thunderer experiment shows that the French assumption as to the character of the curve is only a rough approximation; and apart from those experiments it is obvious that for different ships the character of the curve is likely to vary. Among the controlling circumstances which chiefly need attention are:

1. The area of the rudder, the maximum angle to which the helm can be put over, the rapidity with which it can be put hard over.

2. The speed of the ship or that of her propeller, as well as other causes influencing the flow of water relatively to the rudder, and the consequent development of an unbalanced pressure on the rudder, which exercises a turning effect on the ship.

3. The moment of inertia of the ship taken about a vertical axis passing through the center of gravity of the ship.

4. The moment of the resistance offered by the water to the lateral, rotary, and endwise motions of the ship.

It would be out of place for me to give any explanation of the causes which produce and determine the magnitude of the pressure on the rudder, since the matter is fully discussed in text books of naval architecture. Moreover, the ship comes into the hands of her commanding officer furnished with her rudder and steering gear, which have been tested in the constructor's trials. Experience may suggest improvements, of course; but, as a rule, the changes made are not great, and consequently in the management of the ship an officer can take advantage only of variations in the helm angle below a certain fixed maximum, and of variations in speed or direction of motion. It is generally agreed that—

1. Other things being equal, the turning effect of a rudder increases with an increase in the helm angle up to 40° or 45° with the keel line.

2. Other things being equal, the rate of acquisition of angular velocity, or the rapidity with which a ship turns, increases as the time occupied in putting the helm hard over is diminished.

Hereafter I shall mention a case or two illustrating the effect of putting the helm over more quickly upon the turning of ships; but as illustrations of the advantages of large helm angles, I may quote at once a few figures from actual trials. Admiral Sir Cooper Key found that the Delight gunboat behaved as under, when the helm angle alone was varied:

Helm angle.	Time of turning full circle.	Diameter of circle.
°	*Min. Sec.*	*Feet.*
10	3 52	615
20	3 18	405
30	2 57	275
40	2 47	205

Admiral Halstead, in the trials conducted with the floating battery Terror, obtained the following results:

Helm angle.	Time of turning full circle.
°	*Min. Sec.*
10	6 19
20	5 28
30	5 1
40	4 42

Lieutenant Coumes, of the French Navy, gives the following results for the iron-clad corvette Victorieuse, for an initial speed of about 12½ knots:

Helm angle.	Time of turning full circle.		Diameter of circle.
°	*Min.*	*Sec.*	*Meters.*
7	9	48	1,060
14	6	50	933
21	5	50	750
27	5	20	572
32½	5	20	475

Respecting the remaining circumstances enumerated above as affecting the turning motion, a very few remarks will suffice. In arranging the longitudinal distribution of the weights in a new ship, the naval architect cannot be governed by consideration of the effect which the *moment of inertia* has upon the turning qualities. But it is well known that if the weights are carried far away towards the ends of a ship, and her moment of inertia is great, she will be *slow* to *answer her helm*, as compared with a ship of similar form and equal displacement having the weights more concentrated towards the middle of the length.

Although the true character of the path traversed by a ship in turning has been determined in very few cases, it is known that it is more or less spiral up to the time that uniform angular velocity is reached. This departure from a true circle is of the character indicated in Plate IV, Fig. 4, and it places the ship, when she has turned through 360° and is again pointing in the original direction, somewhat to port or starboard of the original course, according as the ship is turning to port or starboard. The space occupied in turning through 180° and reversing the course has been termed the tactical diameter (*diamètre d'évolution*); it considerably exceeds the diameter of the circular orbit in which the ship turns after her motion has become uniform, or "final diameter" (*diamètre de gyration*). The reason is obvious; in the earlier part of the turning motion of the ship she is acquiring angular motion, that is to say, is subject to angular acceleration, and the curvature of her path is less pronounced than it is in the subsequent stages. It may be interesting to illustrate the ratio of the tactical and final diameters by a few figures drawn from actual trials:

	Helm angle.	Speed on straight.	Diameters.	
			Tactical.	Final.
	°	*Knots.*	*Feet.*	*Feet.*
Thunderer (English)	31	8.2	1,405	1,340
		9.4	1,320	1,250
		10.4	1,320	1,240
Victorieuse (French)	33	10.0	1,440	1,230

At present the published information on the ratio of tactical to final diameters is very limited; it is a subject to which further experiments may well be devoted. But for all practical purposes the determination of the tactical diameters is the more important. In the constructors' turning trials the diameter of the circle, as usually determined, is practically the tactical diameter, as will appear from the description given hereafter. With manual power and ordinary rudders the diameter of the circle for large ships has been found to vary between six and eight times the length of the ships; for small ships, wherein manual power suffices to put the helm over rapidly and the speed is low, the diameter falls to three or five times the length. For swift torpedo-boats, with manual power only at the helm and very small angles of helm, the diameter of the circle for full speed has reached about twelve times the length, and for half speed about four or six times the length. With manual power and *balanced* rudders the diameter for large ships has been reduced to four or five times the length; and nearly equal results have been obtained with ordinary rudders worked by steam or hydraulic steering gear. About three times the length is the minimum diameter yet obtained in large ships turning under the action of their rudders. These figures apply chiefly to full-speed trials; but it appears that differences of speed do not greatly affect the diameter of the circles, although they do affect the time of turning, so long as the time occupied in putting the helm hard over is nearly constant. For the same ship with the same angle of helm, and about the same time occupied in putting the helm over, the time occupied in turning the circle appears to vary nearly inversely as the speed. The time occupied in putting the helm hard over considerably affects the time of turning, and also influences the diameter of the circle. In the case of one of Her Majesty's ships, where the conditions remained almost unchanged, except that a steam steering engine was fitted, and the time occupied in putting the helm hard over was reduced from 90 seconds to 20 seconds, the time occupied in turning the circle was reduced from 8¼ minutes to a little over 7 minutes, and the diameter of the circle was reduced from 970 yards to 885 yards. Before steam steering engines became common in the Royal Navy balanced rudders furnished the best means of putting a large rudder area over quickly to a large angle, and the Bellerophon, Hercules, Monarch, and other vessels so fitted performed admirably in turning under steam. But now that mechanical steering appliances are available, ordinary rudders, hinged at their fore edge, are once more preferred, because they are simpler and less liable to derangement than balanced rudders, besides being more suitable for use in ships having sail as well as steam power.

The determination of the tactical diameter is an important matter, but it does not furnish a complete or sufficient account of the space necessary for a ship to reverse her course; for it gives only a measurement at right angles to the original course—which may be termed the "transfer" of the ship—and affords no measure of her "advance" in the direction of her original course. Taking the case of the Thunderer (Plate IV, Fig. 4), it appears that, reckoning from the instant when the helm began to move over, the ship *advanced* about 1,000 feet in the direction of her straight course before her head had swung through 90°, and was *transferred* (at right angles to her course) about 700 feet. When her head had turned through 180° and the course was reversed, the *advance* had been reduced to 520 feet, while the *transfer* (or tactical diameter) had increased to 1,320 feet. It is most important to ascertain the advance and transfer for the 90° position; the necessary observations are easily made, and I shall not occupy space with a description of any one among the many methods that might be used.

Passing from these general considerations, I will now endeavor to sketch briefly the methods adopted for measuring the diameters of the circles turned by ships on their constructors' trials.

The first is that commonly used in trials of Her Majesty's ships; it was introduced about fifteen years ago by Mr. Martin, chief constructor of Pembroke dock-yard, and is illustrated by Plate V, Fig. 3.

At any assigned place in the length of the ship two vertical battens, *b*, *b*, are fixed in the same transverse plane, and an observer is stationed at the position fixed by one of these battens. A second observer is stationed at B, at a certain longitudinal distance, *l*, from the first observer, and this second observer has to operate a very simple instrument for measuring angles, which is shown on a larger scale in Plate V, Fig. 5. The zero line of this measuring instrument is made to coincide with, or be parallel to, the middle line of the ship. When the helm begins to move over, a box, C, is thrown overboard from the station *b*, at which the fixed battens are placed. After the ship has turned through such an angle that the line joining the two fixed battens again bears upon the box C, a signal is made to the second observer, who instantly notes the angle (ABC) which the line of sight to the box C makes with the zero line of his measuring instrument; let this angle be termed α. Then a simple trigonometrical ratio gives—

$$\text{Diameter of circle} = l \tan \alpha,$$

if the semicircle is supposed to be completed when the angle α is measured. This is a good practical method for smooth water and a calm. Obviously it takes no account of a possible drift of the box, and it assumes the omission of the "drift angle" for the ship, on the supposition that the semicircle of rotation is not completed until the line joining CD is a diameter of the circle. As a matter of fact, owing to the creation of the drift angle, the head of the ship will have turned through 180° *before* her center of gravity has traversed so large an arc in its path. The amount of this possible error in most large ships is not great, and for ascertaining the diameter of the circle simply the plan is a good one. It may be added that since the diameter determined is for the points in the ship at which the fixed battens are placed, by fixing them first at the bow and next transposing them to the stern it would be possible to ascertain the diameters of the respective circles for the bow and stern, and thence to determine the drift angle approximately.

Lieutenant Coumes, of the French Navy, has recently published an extension of the English method, which deserves to be widely known. It is illustrated in Plate V, Fig. 4. He assumes the path of the ship from the straight course to a little beyond the place where she has turned through 180° to be an arc of a circle. At the position C, a buoy is dropped overboard abreast the fixed battens, just as is done in the English plan. At the position marked D the head of the ship has swung through 180° and the line joining the two fixed battens bears upon the box at C. An observer stationed at B, at a known distance from the fixed battens, notes the value of the angle ABC (α) at that instant, and simultaneously a second box, D, is dropped overboard. The ship moves on to a position, E, a little beyond D, and the observer stationed at the fixed battens notes the angle EDC (β), which the two boxes, C and D, then subtend. These are all the observations needed. Suppose O to be the center of the circular path, join CO and produce it to meet the circle at F, also join DF. Then the angle, DFC, is equal to β, being in the same segment, and the angle, CDF, being in a semicircle, is a right angle. Hence—

$$\text{Diameter of circle} = \text{CD} \times \operatorname{cosec} \beta.$$
$$\text{Diameter of circle} = l \tan. \alpha \operatorname{cosec} \beta.$$

Further, it will be seen that the drift angle (δ) equals the angle CDO, which is equal to DCO, and is therefore the complement of β.

The maximum correction produced by substituting Lieutenant Coumes's method for Mr. Martin's in estimating the "tactical diameter" is expressed by the product of the radius into the versed sine of the angle of drift, or algebraically—

$$\text{Error} = \text{radius} \times \text{versine } \delta,$$

where δ varies between 10° and 20° and versine δ varies between .015 and .06. This correction is evidently of little importance in most cases.

Another plan, which has been extensively used in estimating the diameter of the circles turned, is to tow a patent log astern and note the distance it registers while the ship turns through 360°. This registered distance is afterwards treated as the circumference of a circle, and the diameter is obtained by a simple calculation. Opinions are divided as to the trustworthiness of this plan. I do not pretend to be in a position to decide the matter, but feel confident that the chances of error must be greater than in the geometrical methods above described. Even with the best logs available towed behind a vessel moving at a varying speed and turning, there must be great danger that their indications will vary with differences of speed or will be affected with the wake of the vessel. The French have made comparative trials of the geometrical method and of log-measurement, the result being unfavorable to the latter.

Still another plan, well adapted for small vessels, is that devised by Sir Cooper Key and used in the turning trials of Her Majesty's gunboat Delight, conducted at Devonport in 1863. The register of a Massey's patent sounding machine was removed from the lead and attached to a long staff. At the commencement of a circle the register was immersed, when the circle was completed it was immediately raised. The distance registered was read off, and this was treated as the circumference of the circle traversed.

In the French squadrons of 1864-'66 the turning trials were conducted differently from any of the foregoing methods. Captain Bourgois gives the particulars in his pamphlet previously noticed; it may be briefly described as follows: One ship of the squadron was anchored, and the vessel whose movements were to be recorded turned about the stationary vessel. Two observers were stationed at a known distance apart on board the moving vessel. At frequent and regular intervals of time these observers noted simultaneously and recorded the angular elevation of a mast head in the anchored vessel. The height of this mast head above the water being known, this series of observations gave the distances of the anchored ship from each observer at each time of observation. Meanwhile observers stationed on board the anchored vessel took frequent and simultaneous observations of the angular elevations and bearings of a mast head in the ship that was turning. And further, other observers on board the moving ship noted at frequent intervals the angles subtended by a mast in the anchored ship with some fixed and distant object. These observations would have sufficed to determine the path traversed by the ship from the time her helm was put down; but it is a remarkable fact that the important motions of the ships through the first 90° of rotation were designedly neglected, and the observations were begun only when approximately uniform circular motion had been attained. On the other hand, it is in these records one finds attention first given to the importance of determining the drift angle.

The French appear to attach great importance to the determination of the tactical diameter corresponding to various revolutions of the screw and various helm angles for individual ships. I leave naval officers to say what this knowledge may be worth in its bearing upon the movements of the ships composing a squadron; but it is obvious that if the ships are of various sizes and types, combined movements under steam can be performed with greater uniformity if the admiral has this kind of information for all the ships under his command. Perhaps it may be as well to add that the plan which has been sometimes adopted for estimating the diameter of the circle turned by counting the revolutions of the engines, and thence deducing the speed, is liable to lead into serious error. Owing to the drift angle the speed corresponding to a given number of revolutions is much less when a ship is turning than it is when she is on a straight course. In the Thunderer, for example, a speed of 10.4 knots was obtained with 65 revolutions, whereas on the circle 59 revolutions only gave a speed of 7.14 knots.

In concluding these remarks on methods of recording the behavior of ships when turning, I may be permitted to add that in the trials with the Thunderer the method of procedure embraced many of the foregoing principles, and enabled a most searching check and counter-check to be put upon the observations. Any officer familiar with nautical observations will find no difficulty in arranging his own programme should he decide to accurately determine the path of his ship in turning under certain assumed conditions. But he can only derive benefit from a study of what was done in the Thunderer, the report of the trials of that ship containing the most thorough information yet published on this subject.

It is impossible to discuss the "Turning Powers of Ships," even in the outline to which I am compelled to confine myself in the present paper, without referring to the maneuvering power given to a ship by *duplicate propellers*, and more especially by twin screws. Twin screws are now almost universally adopted in the most powerful war ships, and their efficiency as propellers is well established. But they have the further advantage of enabling a vessel, by reversing one of her screws while the other drives her ahead, to turn in a very small circle—almost in her own length. The rate of turning under these circumstances is often slow, but the power of giving rotation to a ship practically destitute of headway and independently of the rudder is of great value. Twin screws are, of course, associated with rudders, and no one at all conversant with the subject would propose to trust to twin screws alone for maneuvering purposes. They are really only valuable auxiliaries to the rudder, and in no sense rivals to it.

It may be interesting to add, with regard to the turning effect of twin screws when working in opposite directions, that in deep-draft ships the time occupied in turning is usually greater than the time for turning the circle with both screws working ahead at full speed; whereas for shallow-draft ships the corresponding difference in time is small. For example, in the Captain, the time for circle at full speed ahead was 5 minutes 24 seconds; that for circle with screws working in opposite directions, 6 minutes 52 seconds. In the shallow-draft gunboats of the Medina class, on the other hand, the full-speed turning trial gave about 3 minutes 6 seconds for the circle, and with screws working in opposite directions the time was only 3 minutes 13 seconds. It will be obvious that in the shallow-draft ships the ratio of the moment of resistance to rotation to the turning moment of the screws is much less than the corresponding ratio for deep-draft ships.

Trustworthy data are much needed respecting one feature in the steerage of twin-screw ships. It is well known that with one screw only at work a small angle of helm will keep a twin-screw ship on a straight course; and this is a proof of the moderate turning moment obtained with twin screws working in opposite directions. But I have searched unsuccessfully for records of exact experiments determining what angle of helm suffices to balance one of twin screws working alone; and I shall be much indebted to gentlemen who may be good enough to give me the needed information. The facts to be noted are very few and simple, viz: (1) the revolutions of the screw; (2) the speed of the ship; (3) the angle of helm required to keep the vessel straight.

When I speak of the moderate turning effect of twin screws, it will be understood that I have in mind the corresponding effect of even a small rudder at a small angle, in a ship steaming at full speed ahead. The normal pressure on such a rudder will be considerable when compared with the thrust of a screw; but the greatest gain for the rudder pressure is the *leverage* with which it acts. Roughly speaking, this leverage is equal to the product—*half length of ship* × *cosine of helm angle;* whereas for the twin screws the corresponding leverage is only about equal to the tranverse distance between the screw shafts, or less than one-half the extreme breadth of the ship. It must not be forgotten, however, that for the rudder to act most efficiently, a ship must have good headway; whereas in the twin-screw ship there is a possibility of turning with very little motion ahead.

The steering effect of a single screw, which has the greatest practical interest, is that in ships where the rudder is placed abaft the screw. It is well known that, in such cases, if the screw be turned ahead or astern when a vessel is at rest, the impact of the screw-race upon the rudder will give steerage power before the vessel has acquired sensible headway. By this means it is possible to slew a single-screw ship round in a very limited space in calm weather, although the operation is a very tedious one. But there is another steering effect of a single screw independent of the rudder, with which sailors are familiar; I mean the effect which produces a turning motion in a ship of which the helm is kept amidships while the screw revolves. The principal causes of this turning motion are (1) the difference of the transverse thrust on the blades of the screw in the upper and lower halves of their orbit; (2) the difference in the lateral pressures, due to the momentum of the streams delivered by the upper and lower blades of the screw upon the stern-post and body of the ship. The ordinary result in ships of the royal navy is that with *well-immersed* screws, the head of the ship turns in the same direction as the *upper* blades of the screws move; but that with screws which are near the surface, or which sweep above the surface, the contrary holds good, and the head of the ship turns in the direction in which the lower blades are moving. I am aware that there are exceptions to these rules, but think they generally hold good for ships moving *ahead*. When the screws are turning astern, the conditions are altered materially.

Auxiliary rudders of many kinds have been proposed and tried. In the museum of naval models at the Royal Naval College, Greenwich, a good collection of these plans may be seen, and it shows how frequently an invention is reinvented by persons who have the same object in view, but are working in ignorance of what has been done by their predecessors. I have only space to allude to the most recent and most successful trials of auxiliary rudders made in the Comus class of the royal navy. These vessels have an ordinary rudder at the stern, and an auxiliary rudder fitted in a recess in the after part of the hull below the screw shaft. This auxiliary rudder has side plates fitted at some distance from the body, on the plan proposed by M. Jöessel, of the French Navy. On trial it was found to answer fairly, keeping the vessel under control, although its effect did not compare favorably with that of the main rudder; nor was this anticipated, since the rudder is fitted as an auxiliary only for use when the main rudder is disabled in action.

The steerage of a screw steamship having engines reversed, while she has either *headway* or *sternway*, supposing her to be fitted only with an ordinary rudder at the stern, is a subject for experimental inquiry rather than for mathematical investigation. It is easy to see what causes are in operation tending to control the behavior of the vessel; but these causes are so conflicting and variable as to make any general statement of little value. The following extract from the report of the committee appointed by the British Association "to investigate the effect of propellers on the steering of vessels," may be read with interest, as it represents the conclusions reached after a considerable number of experiments had been made by Prof. Osborne Reynolds and other members of the committee:

"It appears both from the experiments made by the committee, and from other evidence, that the distance required by a screw steamer to bring herself to rest from full speed by the reversal of her screw is independent, or nearly so, of the power of her engines, but depends upon the size and build of the ship, and generally lies between four and six times the ship's length. It is to be borne in mind that it is to the behavior of the ship during this interval that the following remarks apply.

"The main point the committee have had in view has been to ascertain how far the reversing of the screw in order to stop a ship did, or did not, interfere with the action of the rudder during the interval of stopping; and it is as regards this point that the most important light has been thrown on the question of handling ships. It is found an invariable rule that, during the interval in which a ship is stopping herself by the reversal of her screw, the rudder produces none of its usual effects to turn the ship; but that under these circumstances the effect of the rudder, such as it is, is to turn the ship in the opposite direction from that in which she would turn if the screw were going ahead. The magnitude of this reverse effect of the rudder is always feeble, and is different for different ships, and even for the same ship under different conditions of lading.

"It also appears from the trials that, owing to the feeble influence of the rudder over the ship during the interval in which she is stopping, she is then at the mercy of any other influences that may act upon her. Thus the wind, which always exerts an influence to turn the stem (or forward end) of the ship into the wind, but which influence is usually well under control of the rudder, may, when the screw is reversed, become paramount, and cause the ship to turn in a direction the very opposite of that which is desired. Also the reversed screw will exercise an influence which increases as the ship's way is diminished to turn the ship to starboard or port, according as it is right or left handed; this being particularly the case when the ships are in light draft.

"These several influences, the reversed effect of the rudder, the effect of the wind, and the action of the screw, will determine the course the ship takes during the interval of stopping. They may balance, in which case the ship will go straight on; or any one of three may predominate and determine the course of the ship. The utmost effect of these influences when they all act in conjunction, as when the screw is right handed, the 'helm starboarded, and the wind on the starboard side, is small as compared with the influence of the rudder as it acts when the ship is steaming ahead. In no instance has a ship tried by the committee been able to turn with the screw reversed on a circle of less than double the radius of that on which she would turn when steaming ahead. So that even if those in charge could govern the direction in which the ship will turn while stopping, she turns but slowly, whereas in point of fact those in charge have little or no control over this direction, and unless they are exceptionally well acquainted with their ship they will be unable even to predict the direction."

There is much in these conclusions which has been well known for many years to men engaged in handling screw steamers; and trials were made in the Great Britain to determine the effect of the screw race upon the steerage. But no one can look through the reports of the committee from which the above quotation is made without feeling that their experiments are very valuable and deserving of being carefully studied by all officers in command of screw steamships. Differences of opinion which exist as to the wisdom of some of the recommendations for avoiding collisions made by the committee will not prevent any one interested in the subject from acknowledging the great merits of the work done by the committee, or at its request.

Throughout this paper it has been assumed that the ship's maneuvering capabilities are ascertained in smooth water and in a calm or light breeze. These are the conditions most suitable for exact experiments and comparison; but I need hardly say that such trials do not represent the conditions of actual service. It would be idle to attempt any discussion of the influence which the wind and sea have upon the turning powers of ships, since that influence is so variable. But, on the other hand, it must be remembered that the principles previously laid down for turning in smooth water hold good also in a seaway; only the effects of the rudder, of the inertia, and resistance are then supplemented by the effects of wind and sea. This branch of the subject is, in fact, one of seamanship, and not one to be discussed by the naval architect.

The general conclusions to which my study of the subject of this paper has led me may be briefly summarized as follows:

(1.) On the whole, the ordinary rudder hung at the stern of a ship has not been equaled for maneuvering purposes when a ship has *headway*.

(2.) When associated with steam or hydraulic steering gear the ordinary rudder hinged at its forward edge to the stern-post is to be preferred to all other kinds of rudders. Balanced rudders are chiefly useful, if mechanical steering gear is not available, in large ships.

(3.) Twin screws furnish the best combination of economical propulsion with maneuvering power which has yet been produced.

(4.) The various inventions hitherto tried for rendering the trust of a single propeller available for maneuvering purposes involve risks and drawbacks too serious to be encountered in large ships, although the contrary may be true in small crafts.

(5.) Bow rudders are chiefly useful to assist steerage in ships moving astern Balanced or "drop" bow rudders are to be preferred for use when ships are moving ahead.

(6.) It is desirable that further and careful observations should be made of the actual behavior of ships when turning at various speeds and with different helm angles. Accurate plottings of the path traversed while the head of the ship swings through he first 90° from her original course are especially needed.

Turning experiments with the steamship Hankow, copied from the report of the British Association Committee for Inquiry into the steering of steamships, 1877.

The Hankow is a single-screw steamship, of 3,594.12 gross tonnage; net, 2,331.75 tons; length, 389 feet; breadth, 42 feet 1 inch; depth, 28 feet 8 inches.

Her propeller is four-bladed, right-handed, with a diameter of 20 feet, and a pitch from 24 to 26 feet. The mean angle of its surface with a vertical athwartship plane would be 21°, hence the streams would be delivered on an average at an angle of 21° from the vertical fore and aft plane.

Experiments were conducted on March 8, 1877, in lat. 8° 50′ S., long. 153° 58′ E., between 9.20 and 11.30 a. m., as follows:

Sea smooth, or between 1 and 2 of Beaufort scale; ship drawing probably 24 feet 8 inches forward and 23 feet 8 inches aft.

FIRST EXPERIMENT.

Ship going ahead full speed (say 10 knots), engines were suddenly reversed, helm put hard aport; immediately the engines started, time noted, and bearing of ship's head by standard Admiralty compass noted, and the bearing of the ship's head also noted at every 15 seconds, until the ship came to a dead stop.

Time.			Interval.		Ship's head by compass.	Head turned to—	
						Port.	Starboard.
h.	*min.*	*secs.*	*m.*	*secs.*			
9	20	7	....		N. 62 W.	....	....
9	20	22	0	15	N. 62½ W.	0½	....
9	20	37	0	15	N. 66 W.	3½	....
9	20	52	0	15	N. 69 W.	3	....
9	21	7	0	15	N. 73½ W.	4½	....
9	21	22	0	15	N. 77 W.	3½	....
9	21	37	0	15	N. 80 W.	3½	....
9	21	52	0	15	N. 84½ W.	4	....
9	22	7	0	15	N. 88 W.	3½	....
9	22	22	0	15	N. 88 W.	Stationary.	....
9	22	37	0	15	N. 87 W.	....	1
9	22	52	0	15	N. 85½ W.	....	1½
9	23	7	0	15	N. 84 W.	....	1½
9	23	22	0	15	N. 82½ W.	....	1½
9	23	37	0	15	N. 79½ W.	....	3
0	3	30	3	30	....	26	8½

Ship came to a dead stop in 3 m. 30 secs., and turned to port 26° in 2 m., and then to starboard 8½° for 1½ m.

SECOND EXPERIMENT.

Ship going ahead full speed, say 10 knots. Engines suddenly reversed to full speed astern; helm put hard astarboard, bearing on ship's head taken, and time as before.

Time.			Interval.		Ship's head by compass.	Head turned to—	
						Port.	Starboard.
h.	*min.*	*secs.*	*m.*	*secs.*			
9	45	30	....		N. 3 W.	....	....
9	45	45	0	15	N. 21 W.	2	....
9	46	0	0	15	N. 41 W.	Stationary.	....
9	46	15	0	15	N. 49½ W.	....	1½
9	46	30	0	15	N. 37½ W.	....	2
9	46	45	0	15	N. 32½ W.	....	5
9	47	0	0	15	N. 38 W.	....	4½
9	47	15	0	15	N. 24½ W.	....	3½
9	47	30	0	15	N. 21½ W.	....	3
9	47	45	0	15	N. 28 W.	....	3½
9	48	0	0	15	N. 13 W.	....	5
9	48	15	0	15	N. 19 W.	....	4
9	48	30	0	15	N. 5 W.	....	4
9	48	45	0	15	N. 2½ W.	....	2½
9	48	53	0	8	N. 2 W.	....	0½
0	3	23	3	23	....	2	39

Ship came to a dead stop in 3 m. 23 secs. Her head payed off to port 2° during the first 15 secs., and afterwards turned to starboard 39° before coming to rest.

THIRD EXPERIMENT.

Ship going full speed ahead, say 10 knots, the engines suddenly reversed to full speed astern the helm put amidships, the bearing of ship's head noted by azimuth compass as before. Sea, wind, and weather as before.

Time.			Interval.		Ship's head by compass.	Head turned to—	
						Port.	Starboard.
h.	*min.*	*secs.*	*m.*	*secs.*			
10	34	16	....		N. 29½ E.	....	....
			0	15	N. 29 E.	0½	....
			0	15	N. 29½ E.	....	0½
			0	15	N. 30½ E.	....	1
			0	15	N. 32 E.	....	1½
			0	15	N. 36 E.	....	4
			0	15	N. 39 E.	....	3
			0	15	N. 44 E.	....	5
			0	15	N. 46½ E.	....	2½
			0	15	N. 48 E.	....	1½
			0	15	N. 50½ E.	....	2½
			0	15	N. 51½ E.	....	1
			0	15	N. 52 E.	....	0½
			0	15	N. 53½ E.	....	1½
			0	15	N. 54 E.	....	0½
			0	15	N. 54½ E.	....	0½
			0	15	N. 55 E.	....	0½
10	38	31	0	15	N. 56 E.	....	1
0	4	15	4	15	....	0½	27

Ship came to absolute rest in 4 m. 15 secs.; her head turned to port 0½°, and then 27° to starboard, before coming to rest.

FOURTH EXPERIMENT.

In this case ship was going full speed astern, say about 9 knots, when the engines were suddenly reversed to full speed ahead; helm put hard to port; time and azimuth of ship's head noted as before. Sea, wind, and weather as before.

Time.			Interval.		Ship's head by compass.	Head turned to—	
						Port.	Starboard.
h.	*min.*	*secs.*	*m.*	*secs.*			
11	3	11	....		S. 65½ E.	....	....
			0	15	S. 66 E.	0½	....
			0	15	S. 67 E.	1	....
			0	15	S. 67½ E.	0½	....
			0	15	S. 67½ E.	Stationary.	....
			0	15	S. 66½ E.	....	1
			0	15	S. 65½ E.	....	1
			0	15	S. 63½ E.	....	2
			0	15	S. 60½ E.	....	3
			0	15	S. 57½ E.	....	3
			0	15	S. 53½ E.	....	4
11	5	56	0	15	S. 48 E.	....	5½
0	2	45	2	45	....	2	19½

Ship came to dead stop in 2 m. 45 secs., and her head turned 2° to port in the first 45 secs., and 19½° to starboard in the next 2 minutes.

FIFTH EXPERIMENT

Making the circle from rest; hard to port; full speed ahead. Wind and sea as before.

Ship started at full speed from absolute rest, with the helm hard aport, and at the instant of starting an empty flour barrel was dropped from the stern, to mark the point started from.

Time.			Interval.		Ship's head by compass.	Arc turned.
h.	*min.*	*secs.*	*m.*	*secs.*		
9	27	54	....		N. 56½ W.	....
	28	24	1	30	N. 54 W.	2½
	28	54	0	30	N. 49 W.	5
			0	30	N. 38 W.	11
			0	30	N. 28, W.	10
			0	30	N. 18 W.	10
			0	30	N. 5 W.	13
			0	30	N. 6 E.	11
			0	30	N. 19 E.	13
			0	30	N. 30 E.	11
			0	30	N. 43½ E.	13½
			0	30	N. 58 E.	14½
			0	30	N. 74 E.	16
			0	30	N. 89 E.	15
			0	30	S. 75 E.	16

Time.			Interval.		Ship's head by compass.	Arc turned.
h.	*min.*	*secs.*	*m.*	*secs.*		
			0	30	S. 61 E.	14
			0	30	S. 46½ E.	14½
			0	30	S. 33 E.	13½
			0	30	S. 20 E.	13
			0	30	S. 7½ E.	12½
			0	30	S. 4½ W.	12
			0	30	S. 16½ W.	12
			0	30	S. 30 W.	13½
			0	30	S. 45½ W.	15½
			0	30	S. 61 W.	15½
			0	30	S. 78½ W.	17½
9	40	54	0	30	N. 84 W.	17½
9	41	24	0	30	N. 67 W.	17
9	41	40	0	16	N. 57 W.	10
0	13	46	13	46	....	Mean angular velocity, 27′ per second.

Ship came outside barrel about 150 feet, when it was abreast taffrail, *i. e.*, it was on our starboard side at conclusion.

VI.

Among the methods suggested to find the qualities of the turning circle is one by Lieut. A. B. Wyckoff, U. S. N., for determining the drift angle and final diameter, which is as follows:

Have two cross-battens erected on the topgallant forecastle, and two observers—one at the cross-battens and the other at the after end of base-line on the poop-deck. At instant of putting helm over drop a buoy abreast cross-battens and note the time. (See Plate V, Fig. 6.) When the vessel has turned through 90° drop a second buoy abreast cross-battens, and take the angles *a* and *b* subtended by the first buoy and the opposite end of the base-line. Note the time when the second buoy comes abeam (position 3) by the cross-battens, take angle *z*, subtended by the second buoy and the forward end of base-line. Note time when ship has turned through 32 points.

$$l = \text{length of base line } P^1\,B$$

$$P\,P^1 = \frac{l \sin b}{\sin n}$$

$$P^1\,P^3 = l \text{ tang } z$$

$$T\,P^1 = P\,P^1 \cos a$$

$$T\,T^1 = \frac{P^1\,P^2}{2} + T\,P^3$$

$$\text{Tang } c = \frac{P^2\,H^1}{R} = \text{drift angle}$$

$$R = \frac{P^1\,P^3}{2} \text{ half final diameter.}$$

VII.

In regard to the evolutionary powers of a vessel fitted with a steering propeller we propose to look a little into a type of vessel possessed by our Navy—we mean the Alarm. Without discussing her construction or engining, we will merely say that she has much to recommend her *tactically:* for instance, her great facility of turning; but this quality, with any sort of steering propeller, must be at the expense of speed. The action of the screw can be referred to any radius of a circle, and therefore the vessel can be pushed or pulled in any direction. Her motion indeed may he compared to a man standing between the handles of a wheelbarrow, since her pivoting point is in the bow. She will be comparatively safe from ramming in a single combat, since she can keep her bow constantly on the enemy. She will be able to ram an antagonist of greater speed, if he be fitted with a single screw, as she can make the *chord* of the segment of a circle in turning, where her adversary must run on the circumference. On a straight course, however, a vessel of less speed can overtake the Alarm, from the fact that her speed is reduced by the *eagerness* with which she answers her propeller, and the consequent reduction in the length of her forward moment due to the screw not always acting in the direction of her keel.

CHAPTER V.

THE SHIP IN ACTION ON THE OPEN SEA.

I.

Most authorities agree that during an action the highest speed should be maintained by the ship; that speed is of even greater moment to a ram than handiness or turning power, and that a powerful stern fire is at least as important as a powerful bow fire.

It is a fundamental principle of warfare that in single combat a fast ship need never be rammed by a slower one; indeed, if the turning powers are equal, the faster ship can *always* ram the slower one; and, also, the enemy should always, if possible, be put in a position to leeward of the attacking ship, so that the smoke from the guns and funnels combined will blind him. It follows as a postulate that should a vessel unfortunately be placed in this position, befogged with smoke, she should stop firing, so as not to add to her difficulties. It may be observed, however, that some of the best tacticians do not see in this leewardly position all the disadvantages charged against it.

Lieut. G. R. Bethell, R. N., says, in regard to the speed to be maintained in action, that unquestionably vessels should be capable of the very highest speed. There are cases, though, where slow speed will be used; as, for instance, two vessels running side by side, each would naturally tend to slow and turn toward her adversary, as neither could advisedly permit the other to enter her wake close astern.

II.

The increase in speed of ships, and the rapidity with which they will move in future fights, obliges us to look to every means of increase in the quickness of fire, so that we may hit the enemy as many times as possible in a given time. Actually, a 27-centimeter gun can fire once in three minutes under favorable circumstances, but in battle it will only be fired probably once in four minutes. The limited amount of ammunition that can now be carried raises the question whether very quick fire will be resorted to and maintained. A sea-fight will probably last such a short time and be so decisive that we think there should be no limit to this rapidity. During a bombardment the vessels of a squadron will have to be supplied by a regular ammunition supply-service from ammunition vessels. Some vessels have guns of such size that only fifty rounds can be carried for each. A German authority believes that ships of this kind are not fitted for the line of battle, and it may be added, that the majority of professional writers agree with him on this point. The precision of fire is of no less importance than the rapidity, the necessity of seizing the instant, generally very short, when you can get your enemy in a position to strike him hard and with certainty must not be lost, as projectiles are provided too few in number and are too costly to be thrown away.

The probabilities in favor of striking the side of an ordinary armorclad of the first-class with a large calibered gun are about 95 in 100 for 2,200 yards; 40 in 100 for 4,400 yards, and 15 in 100 for 6,500 yards, supposing the pointing to be perfect and the only marring element to be the motion of the ship.

Captain Rivet, of the French Navy, says that the precision of fire depends upon the following:

1. Relative movements of the two ships.
2. The smoke from the guns and funnels of your own and the enemy's ships.
3. The pitching and rolling of the ship firing.
4. The uncertainty of the intervening distance.
5. The action of the wind.
6. The state of the nerves of the firer, from his knowing that the instant he discharges his battery the enemy will do the same.

The methods in use to measure distances are very imperfect, and the variations of distances are very rapid, owing to the high speed of the combatants. Rolling exercises its worst influence on covered-in guns. It is recommended, in effect, as a general rule, not to fire a gun when the ship is half way on a roll. Now, it may happen that the battery may be concentrated beforehand on a point on a certain bearing, and with a certain elevation, and when the enemy is at this spot the broadside should be fired; but if at this instant the ship was at such a part of her roll as to change the elevation the whole effect of the broadside would be lost.

According to Captain Rivet the use of artillery in a naval fight can be reduced to the following rules:

1. The fire of pieces from uncovered decks, or guns in barbette, should be independent. Guns on covered decks should be fired by broadside and concentrated fire used.
2. Barbette fire of the lighter guns should be directed by preference at the decks, and at the non-protected parts of the ship. The battery and heavy guns should be directed at the water line.
3. If the sea is heavy and the vessels are rolling deeply, the firing-officer should carefully watch the motion when the enemy is on the brink of arriving at the focus of concentration.

4. As soon as the gun is laid the crew should cover. As soon as the gun is fired it should be loaded, laid, and the crew should cover.

5. If the broadside battery has great power of penetration it is best to fire each gun in succession. If the wind is ahead, commence aft. If the wind is aft, commence forward. Keep, if possible, between the sun and your adversary.

6. Guns should only be used when there is a probability of their producing a serious effect on the enemy.

7. Machine guns and small-arms on deck and aloft should fire on those parts of the enemy where it is suspected the captain and controlling officers are located, at semaphore stations on the deck, and at the points where the electric lights are installed.

Besides heavy artillery, ships are furnished with lighter guns that at most weigh four tons. In a fight the larger of the lighter guns will aim at the non-protected parts of the ship and the screw. The smaller of the lighter guns and the machine guns will keep up a shower of projectiles, when near the enemy, on her decks; or, if there is an attack from the enemy's torpedo boats, these guns should drive them off. Machine guns and small-arms should be used from aloft. As a quantity of small-arm ammunition will be used, there must be a regular force of supply-men, who shall serve ammunition to the machine guns and small-arm men from the small-arm magazine.

It may be suggested that the expanding quality of seed when wet might be taken advantage of to stop shot-holes. A long canvas cylindrical bag might be made and used like a jackass, partially filled with seed or grain. Until the seed has swelled a safety mat must be kept over the aperture. It may here be mentioned that all vessels, at all times, should keep one or more small hogging lines rove.

III.

The ram is the most formidable of all the weapons of the ship, and its use requires severe and prolonged practical study. The time has come when a commanding officer must be as dexterous in the handling of his ship as is a fencing-master in the use of his foil.

Lord Nelson said that there was only five minutes difference in time between victory and defeat. Captain Rivet says with fast ships, such as are used nowadays, for "five minutes" read "five seconds."

A great variety of opinion exists on the question whether vessels will ram each other *head on*. Many good commanding officers say that they would not hesitate to meet their antagonists in this way; in fact their decision is supported by the latest writers. As far back as ten years, Captain Noel said:

> If an enemy is observed to be approaching from ahead it seems to me that the only chance of frustrating his attack is to keep your bow exactly on his, and so meet him.

There are, however, many others who say that such an action could only result in mutual disaster, and that it should never be resorted to.

In ramming, mechanical handling of the rudder, either by steam or hydraulic power, is an absolute necessity. The engines should be stopped before actual contact is made, and therefore the ship should be fitted with engines, boilers, and pipe connections properly stayed and arranged to ram an enemy, or to withstand a ramming, without giving way.

If your ship is a ram, and you are chasing an enemy, and you have superior speed, do not keep in his wake, as you might run on top of a torpedo which he has thrown overboard. Keep a little on his quarter, and as you draw *well up* on his broadside sheer in to him as normally as you can, trying to destroy his screw and rudder. This is a good maxim. (See Plate VI, Fig. 1.)

Since an engagement between two vessels is very likely to degenerate into an artillery duel, each moving in the same direction around the circumference of a common circle, each vessel should look out for torpedoes dropped in the wake by the other.

If two ships intend to ram, and collide broadside to broadside at *C* (see Plate VI, Fig. 2), and the A puts his helm hard aport and B his hard astarboard, the ships will meet again at C′ and again at C. If, however, B's turning circle is smaller than A's in diameter, at C′, B will be inside of A's circle and safe from ramming at C″. If the two vessels put their helms each the same way when they collide, they will each describe a circle and meet again at C.

If the two vessels are steering around the same circle the faster vessel may ram the slower in the stern. (See Plate VI, Fig. 3.) Or if one vessel has greater facility of maneuvering, as, for instance, a smaller turning circle, she can ram the other on the quarter by steering a course within the other's circle. (See Plate VI, Fig. 4.)

When one vessel is attacked by two she should never enter upon circling, as one of the vessels could enter the lists with her and the other could stand aloof and ram when an opportunity offered.

IV.

Automobile torpedoes can be installed so as to sweep from right ahead to right astern, according as they are put in the bow, broadside, or stern. A broadside installation, however, alone permits of any horizontal train. At present, in the French service, the torpedo is discharged above water. If they are discharged ahead, the pitching of the ship disturbs the depth of immersion for some time in their flight.

Discharged from the side in even a moderately heavy sea, if the bow of the torpedo strikes a wave, the torpedo will probably be altered in its flight laterally. Discharged from the stern, the torpedo is acted upon by the water stirred up by the screw. It is believed that an installation right ahead is the best for torpedoes, as it takes up less of the attention of the captain in using them. The captain already has too much to look out for in battle.

In discharging automobile torpedoes from the bow, we will consider the tube as being fixed in a fore-and-aft line. Launching in this direction can be considered as extending the ram of the vessel some hundred yards, as the torpedo during its flight can be counted upon to go in the direction of the ship's head. There are no doubt times during an engagement when a torpedo can be fired from this position with great success. It has this drawback, however, in a stern chase a slight error in the pointing of the head of the ship will make the torpedo miss the object fired at. Added to this there is the possibility of running over your own torpedo. This latter danger can of course be avoided by having the torpedo sink at the end of its flight.

The best way to show the relation that should exist between the attempt to use the torpedo and how to avoid it, is by tracing the movements of the two ships. The question will be considered in three categories.

1. The course of A crosses the course of B, who for some reason does not change it, but continues on.
2. The courses of the two ships are parallel and opposite. The attack is made by a rapid sheer of one of the ships towards the other.
3. The enemy strives to avoid the attack by turning with his helm hard over.

FIRST CASE. *When the two paths cross.* (See Plate VI, Fig. 5.)—A has the greatest speed and intends to attack. If A is at *A* and B at *B*, A should ram B at *A′* (B then being at *B′*). Since the torpedo is in the fore-and-aft line of the ship, A would have to turn towards *B* to discharge it. This A could not do and be certain to ram B at *B′*. The torpedo then could not be used except just before contact. It may be well to state here how A should steer with reference to B in order to ram him. A knowing both ship's speeds, should keep a bearing on B.'s stern *and not change* it. If A's speed is half again as great as B's, he should keep B four points on his bow; but as it is likely to be only one-tenth more, he should then keep B about a point or a point and a half forward of his (A's) beam. (See Plate VI, Fig. 5.)

Suppose, however, that A wishes to torpedo B. Since his torpedo travels at a speed of 20 knots, and is available within 350 yards, he can, when at a determinate point, *A′* (see Plate VII, Fig. 1), swing through the calculated angle and discharge his torpedo; then he could swing back again and head for the point where he knows that he can ram B, or if he fails in reaching B can pass under his stern and give him a broadside. In the figure, A at *A* gets a line of bearing *AB* on B at *B* At *A′* A swings through the proper arc and discharges his torpedo, B being at *B′*, the torpedo and B should meet at *x*. B, if he escapes the torpedo, might be rammed by A at *B″*, A being then at *A″*. If, however, B has arrived at *B‴*, A cannot ram him, but must pass under B's stern.

SECOND CASE. *Courses parallel and opposite.*—A and B are passing on parallel courses 350 yards apart. (See Plate VII, Fig. 2.) A, wishing to ram B, puts his helm hard a starboard and sheers to port. He will ram B at *x*, but A cannot use his torpedo. B at *B'*, however, bears slightly to port and can use his torpedo on A, who will be at *A'*, hitting *A* at *y*.

THIRD CASE. *Two vessels maneuver each to ram the other.*—A, having greater speed than B, could get within B's turning circle, and so have him at a disadvantage. (See Plate VII, Fig. 3.) A could use his torpedo at *A'*, B being at *B'*, which would strike B at *x*. A can continue on and ram B at *B''* or can pass astern of B, and give him a broadside. This case is an illustration of the maxim that, all else being equal, the advantage remains with the ship having the greatest speed.

In case the torpedo is installed astern the best time to use it is when the vessel, having missed ramming you, passes under your stern. Or should two vessels be passing on opposite courses, B turns across A's stern. A would stop and fire his torpedo with his head pointing in such a direction that it will reach B at *B'*. (See Plate VIII, Fig. 1.) Then shifting his helm in the same direction as B, he starts ahead at full speed and continues his circle. There is really no good reason why he should continue to turn beyond *a*, unless he has greater speed than B, as when he is at *a* B is at *b*, and any further turn brings A within B's turning circle and puts him at a disadvantage as regards B.

Should the torpedo be installed in the side, the instant of discharge will depend upon the speed of the two ships. It is of great importance to discharge your torpedo so as to strike your adversary before he can fire his concentrated broadside. The exact place of installation is really of great moment, especially for distances close aboard. Probably the best in broadside is as far aft as possible, as the great point is to have a torpedo ready to prevent the enemy ramming you, which he will try to do on the quarter. The discharging tube should admit of a train three points forward of the been.

As an example of when the broadside installation is of greatest use, we suppose two vessels to steer courses that intersect, the slower one can use his torpedoes on the faster at any time that the ships are within 350 yards of each other. In this case, also, the best point of installation would be as far aft as possible, as the slower vessel could always turn from the faster vessel and have him in range as regards his torpedo. (See Plate VII, Fig. 4.)

V.

SINGLE COMBAT.—The broadside fire is no longer the principal and only power of attack; still a fight will be opened by artillery, although the ultimate design will unquestionably be to ram. The whole point to strive for will be a commanding position—a position of advantage—using the guns to overcome the enemy, or torpedo if possible, and the ram to give the *coup de grâce*.

We will suppose two rams identical in qualifications are pitted against one another. There will be some evolutionary sparring, a feeling of one another, and then an arrival at one of the following positions referred to shortly.

Admiral Randolph, from whose work on Naval Tactics the following cases are taken, does not believe that rams will meet each other head on. He thinks that they will pass in opposite directions close aboard, exchanging broadsides. (See Plate VIII, Fig. 2.)

As they pass, A might turn with the utmost rapidity with his helm hard aport across B's stern. If B at the same instant puts his helm hard a-starboard, A at A_2 would have the power of passing ahead of B, who would then be at B_2. A might then *stop* inside of B's circle; or, if B continued to circle, A might ram B at x.

All else being equal, the one which uses her helm quickest would get to a *safety point* inside the other's turning circle. If B, however, after passing astern of A at A_2 (B_2) were to slow also, and they were to be in the position shown in Plate VIII, Fig. 3, then each could be said to be inside the circle of the other, and the one which can by means of fore-and-aft sails, drags, or sternway get its head pointed fair at its opponent, has the position of advantage and can ram. It follows then as a maxim that the ship which first passes into the circle of the other has the advantage.

Having examined the engagement from a ramming stand-point, we will now consider it from an artillery view.

Broadsides have been fired when the vessels were abreast one another on opposite parallel courses. At A_2, A fires his other broadside, B being at B_2, the ships being at close quarters. Instead of crossing B's bows, A might be able to go astern of B. He might or might not be able to give B a broadside, as that would depend upon whether he had had time to reload his battery.

If, after the exchange of the first broadsides, each ship turned across the other's stern the result would be separation for more than two diameters of their circles, and a renewed meeting end on.

If, instead of commencing the duel by exchanging broadsides, suppose one of the ships endeavors to obtain by maneuvering some opening advantage, and for this purpose when 1,000 yards off turns quickly in one direction in the hope that the enemy will turn towards him in the same direction, and instantly, after he has turned through 4 points, rights and shifts his helm, and, supposing his maneuver has induced the enemy to circle, runs astern of his opponent, giving him a broadside in passing, and immediately slows, he will then have the advantage of having made the enemy feel his metal and will be inside his enemy's circle, comparatively safe, and ready to ram. (See Plate VIII, Fig. 4.) A yaws, and straightens up at A_b. B, misled, turns and receives a broad side from A, when A is at A_2 and B is at B_2. Finally A, at A_3, is slowed and inside of B's turning circle.

If B does not change his course at *B*, but stands on, he will give A a broadside at B_b, A being then at A_b; then, if A turns astern of B, he can finally get inside of B's turning circle at A_n, but he will have received B's other broadside when he is at B_c and A at A_c, but the distance will be comparatively great. (See same plate and figure.) If the ships have strong bow-fire this must be taken into consideration.

Still other tactics. (See Plate IX, Fig. 1.)—B may wish to try his artillery first, and so alters course 5½ points to port. A steers toward him, and, if speeds were equal, there would be a collision at *x*. After exchanging fire for some time, one or the other wishing to continue to use artillery must keep away, which would finally end in a stern chase, either straight away or both ships steering around a circle If this is not the case, and they both steer to meet until their tactical circles intersect, and both put their helms over simultaneously so as to turn towards one another, they would meet bow and bow, without advantage being to either. Here the faster ship might by a sheer pass astern of the other, say A astern of B, and getting inside the other's circle have the advantage; or, again, if they were very near and both had the same speed one might slow for an instant and be able to ram the other. Say B to ram A. (See Plate IX, Fig. 2.)

Captain Colomb, R. N., in his work "On the attack and defense of fleets," says it is a mistake generally made that vessels desirous of ramming one another will head directly for one another. On the contrary, a vessel should keep the enemy on his bow, and put his helm over to ram when the opposing vessel is a little less than 4 points on his bow and 200 yards away. If he does so he will strike the other vessel at right angles to his course. This supposes a speed of about 10 knots.

Vice-Admiral Bourgois, M. F., says, in speaking of single combats between armored vessels, suppose two adversaries, steering straight courses that intersect, are led to fall foul of one another. The probabilities are that they will come together, scraping broadside to broadside, end for end. If they are equal in speed and tactical qualities each vessel should come around under the stern of the other. If they are unequal the vessel that has the *greater speed* should put her helm over the *same* way as her adversary. Again, the vessel that *turns in the smaller circle* should put her helm the *opposite* way from her adversary. To illustrate: If B has greater speed than A (see Plate IX, Fig. 3), when A is at *A′*, B will be at *B′*, and in a better position to ram than would A; or B can run inside of A's circle and be on a safety point at *B″*. But if A's turning circle is smaller than B's, by A putting his helm as directed he has the advantage at *A′* over B at *B′*. (See Plate IX, Fig. 4.)

Captain Fremantle, R. N., discussing the subject of single combat, supposes the antagonists to be equal in power and in all tactical qualities. He says: "Our tactics are ramming tactics, and the enemy is ready to meet us on our own ground." (See Plate IX, Fig. 6.)

A steers for the enemy B, keeping him a couple of points on the bow. They are 2,000 yards apart. A intends to ram from the first, while B's plan is not yet matured, but intends to use his guns and to ram A the first time he makes a broad sheer. B is willing to keep A on his bow for this reason. They near one another, steering opposite and parallel courses. Both going at full speed, they should meet in three minutes. Each keeps the other from 1½ to 2 points open on the bow. A intends to fire one round from his bow gun and then ram. The gun is kept on the enemy and laid for 900 yards. The instant B's masthead angle shows that the vessels are separated that distance, A fires and puts his helm hard aport. The smoke hides A for half a minute. If B stands on for that length of time A will ram B probably effectually. If, when A fires his gun, B shows for an instant and starts ahead again, B would probably ram A.

Captain Colomb says, very truly, that the difference between ramming and being rammed lies in "half a ship's length."

Should B be wary and keep always head on to A they would of course meet, but Captain Fremantle, although not believing that vessels will intentionally ram one another head on, thinks that vessels will go so close as to collide broadside to broadside, thus agreeing with Vice-Admiral Bourgois: "Here would be a chance for a skillful captain to injure the enemy's steering-gear and screw by a double movement of the helm."

Supposing A and B to be broadside and broadside, and each ship going at full speed, with A's helm hard astarboard and B's helm hard aport, each would describe a circle, with the chances in favor of A, since A would be inside of B's circle and would have another chance to ram.

If from the position of broadside to broadside each ship went ahead at full speed, with helms hard astarboard, then the conditions would be the same as when they bore down for each other at the first.

Should they agree to fight an artillery and torpedo duel after ineffectual ramming they would probably ultimately find themselves moving about each other around the circumference of a circle of 400 or 500 yards in diameter. Once in this position neither could use his ram except by stopping or going astern, which would be extremely dangerous. In these duels of the ram, gun, or torpedo, success should lie with the fastest ship, other things being equal.

Lieutenant Bethell, in his work on two vessels in action, discusses the most advantageous maneuvers that can take take place between two adversaries in single combat. He draws attention to the environment of one position, which he calls the "position of greatest danger," and gives rules to follow to avoid it, and he further shows the importance of turning power in a vessel. We propose now to take up the different cases which present themselves, and to examine into the position of greatest danger.

We consider two vessels, A and B, of equal tactical value, and it is to be shown that one of them can, to a greater degree or lesser degree, force the other to assume a disadvantageous position, and that this locality may be termed the "danger-field." To escape from this environment requires certain tactics, which if not adopted, put the threatened vessel in a constantly increasing position of danger, until she arrives at a point called the "position of greatest danger," where her destruction is imminent. (See Plate IX, Fig. 5.)

A is in this position as regards B: If A attempts to turn in order to put himself on equal terms with B, B will ram him. A can only use a weak stern fire on B. B can keep up a powerful bow fire on A. A has one advantage alone over B; he can use his torpedoes better.

The *danger field* is the forward half of A's turning circle on either side if A and B bear relatively as in the diagram. In order that A shall clear the danger field and meet B on equal terms, the time that it takes him to turn through the first two quadrants must be less than the time it would take for B to get to him. The necessary distance can be determined by A measuring B's masthead angle.

A can hardly escape, when having swung through, say, the first quadrant, he runs off at right angles to his first course, for his pursuer having only to move on the circumference of a larger circle has had his speed but little reduced, and therefore arrives in A's wake nearer to him than on the last course. In other words, unless A can shake B off by superior speed, he only *helps* him by turning. (See Plate X, Fig. 1.)

In a ramming duel, then, one vessel will try to force the other into the danger field, and to the position of greatest danger in that field; and the question arises how to avoid it for one, and how to force it on the other. If two vessels are maneuvering, and one is unable to approach the other, the one has the advantage if he can get in the wake of the other within 400 yards. The pursued is, of course, safe as long as he steers a direct course, but if he attempts to maneuver, he shortens the distance between himself and the pursuer. By the pursued having the advantage, is meant that the natural impulse of the pursued is to fight, and the instant he turns he comes in the danger field. (See Plate X, Fig. 2.)

Another phase of this example: Suppose A wishes to close with B. If he can force B into his wake at a distance that would take B longer to traverse than it would A to turn her bow to B, then A could effect his object, or if B continued to stand on and not turn A would have B in her danger field. (See Plate X, Fig. 3.)

We will now consider an engagement between two vessels equal in all respects, and steaming at a rate of 12 knots. Each vessel has a diameter of turning circle of 500 yards which she executes in five minutes.

The following formula seems to express what is incontrovertibly a fact:

> If one vessel is turning, and another enters his circle, then, if the latter vessel enters on an opposite course to that of the turning vessel at the moment of entry, or is permitted to come to an opposite course while inside the circle, the turning vessel is momentarily on equal terms with the other, and has the power of retaining that equality by a proper use of the helm.

CASE I.—A and B are passing 150 yards apart, steering opposite and parallel courses. Each puts its helm over the same way, at the same instant, so as to cross the other's wake. Result: They will come around and be on equal terms. (See Plate X, Fig. 4.)

CASE II.—But if the helms are put different ways, say, A's to port, and B's to starboard (see Plate X, Fig. 5), B will enter A's circle at B′ while A is at A′. B will have the advantage, being inside of A's circle, and safe from A's ram, while B can use his. A should not attempt to turn this way unless the perpendicular distance *A B*, was so great as to permit A to turn more than 16 points before B can enter his circle. In this case he would be on equal terms with B.

CASE III.—Suppose A, instead of putting his helm either way, when B began his circle, continued to stand on for one minute, and then put his helm over, he would find that no matter which way he turned, he could turn through more than 16 points, and could therefore meet B on equal terms; for when he arrived at y or y' B would be at x or x'. (See Plate XI, Fig. 1.)

It follows from these considerations that if two equal vessels are passing one another close to, and maintaining the same speed it is immaterial, so far as gaining tactical advantage is concerned, *when* they elect to turn, with the exception of Case II, already discussed.

Now, as regards artillery, the two vessels will exchange broadsides in passing, but if A stands on, B has the advantage, as he can give A a broadside at b or b', when A can only reply with a weak stern fire, being then at A' or A'' or A'''.

Taking everything into consideration, however, we may lay down the rule that two vessels passing, apart from unforeseen circumstances, it is best for them not to delay turning.

If two vessels are separated in passing the diameter of a turning circle no tactical advantage can be gained by either turning. This is equally true if either stand on and elect to turn at a later time. It will be seen, then, that although it is better to turn immediately on passing your opponent, so as to get the advantage of fire, it is not vitally bad tactics to delay doing so.

We come now to consider two vessels that are *unequal* either in *speed* or *turning power*.

I. If two vessels engage, and instead of being equal in all respects, have unequal speeds, then the slower of the two could not delay her turn, after her adversary had begun to turn, without losing her position of equality. Conversely the faster of the two can turn when she wishes without sacrificing her advantage.

II. If two vessels engage, and instead of being equal in all respects one has greater facility of turning than the other, the one which has the smaller diameter of circle should turn immediately, as in one minute, with a speed even of 12 knots, her advantage has disappeared, if we suppose that her adversary had turned when she did and across her stern.

III. But if this latter vessel, with the larger turning circle, does not turn until later, and the one with the smaller circle turns immediately, there will be no advantage of position for either vessel.

IV. If two vessels engage, and one turns quicker than the other, then the one with the smaller circle increases her advantage for every increase of distance from her adversary, when abreast one another, until such distance is equal to the diameter of the smaller turning circle, when the quicker turning ship is at the position of greatest advantage, *provided* that her adversary crosses her wake in turning. If, however, her opponent turns from her she loses *part* of her advantage of position. (See Plate XI, Fig. 2.)

Therefore, not knowing which way the adversary will turn, the quicker turning vessel should seek to pass close to the other, so as not to risk losing any advantage. To illustrate: Let A in the diagram be the vessel with the smaller circle. If A and B cross each other's wake, A will enter B's circle at about *a*, and have the advantage, B being then at *b*. If we suppose A and B to be apart a distance equal to A's diameter of circle, that is, for A to be at A', we will see that the position is still more advantageous for A, since when B is at *b* A will be at a'. If, however, B turns the other way he will be at b' when A is at a'' or a''', and A will therefore have less advantage if he started from A' than if he started from *A*. It will be noticed that the quicker turning vessel has the advantage, from an artillery stand-point, all through.

We come now to consider *slower speed* balanced by *greater turning power*.

A has 12 knots speed; large turning circle, taking five minutes to complete.

B has 10 knots speed; small turning circle, taking three minutes to complete. (See Plate XI, Fig. 3.)

I. If both ships are in the usual position of passing close to on opposite and parallel courses, and both turn with the helm the same way and at the same instant, B will be able to get A in the danger-field; but probably before B can traverse the distance between them A will have turned through enough points to be on an equality with B as regards tactical position. B, however, will give A two broadsides for one that he receives.

II. If B stands on, even for one minute, he loses any possible advantage he might have reaped by an immediate turn. Conversely, if A stands on for one minute or longer he will be clear of any possible danger from B's ram. Here, if B turns at *B* he will be at *b* when A is at *a*, but A, being faster, ***might*** put himself on an equality before B traverses the intervening distance.

If B stands on to *B′* before he turns, he will be at *b′*, when A is at *a*.

If A stands on to *A′* before turning, neither will have an advantage.

III. If B is pursued on a straight line by A, A having the speed can in time overtake him. B turns to put himself on an equality with A. If A can traverse the distance before B can turn through 16 points, he can ram B, so that B notwithstanding his turning power must succumb to A, or turn before A gets within 600 yards of him.

IV. B must at all times endeavor to turn with his helm the opposite way from A, when both turn on passing; for the reason, by so doing he gets inside of A's turning circle, where the poor quality of his speed is least felt.

V. Should A pass B going in the same direction, B should try and force him to turn, by feinting a ramming attack, and thereby put A in the danger-field by entering his turning circle. (See Plate XI, Fig. 4.)

For an actual fact, it would be very bad tactics for A. to take any position forward of four points on B's quarter. His best position would be astern of B, and out of B's wake.

Slow ships therefore should have heavy stern fire.

With *twin screws* the turning circle becomes smaller, and therefore the advantage for B greater. A, the faster, should avoid turning until two or three minutes after B, and should always put his helm the ***same way*** that B has his.

Lieutenant Bethell is of the opinion, since rank turning with twin screws represents a position of almost absolute rest, vessels should avoid the excessive use of the maneuvering quality of their screws, as the destruction of momentum is an advantage thrown away..

Lieutenant de Vaisseau Besson, of the French Navy, in discussing the subject of an engagement between two vessels, equal in all tactical respects, formulates the conditions in thirteen theorems. Some of these have already been considered and some are sufficiently evident from an inspection of the diagrams. Others will be explained.

THEOREM 1. When two rams are in action, the first that enters the turning circle of the other has the advantage. He can ram the other or force him to run. (See Plate XI, Fig. 5.) A entering B's circle can ram B. B cannot ram A at any point, as A is always in B's circle. B to avoid being rammed must run.

THEOREM 2. When a vessel enters the turning circle of another, in order to ram, it is necessary that the assailant shall head within an angle formed by a line which joins the two ships, and a tangent to the turning circle of the adversary at the point of entrance. (See Plate XII, Fig. 1)

It will be seen that B enters A's circle at B. The distance OB is equal AC, and from the fact that the figure $oCo'B$ is a lozenge, the angles o and o' are equal; more than that, oC being parallel to $o'B$, is perpendicular to AB, tangent to B for the circle o'. From these facts we conclude that the arcs AC and CnB are each equal to arc CmB, and are consequently equal to each other. The two ships describing routes of equal length, the collision will take place at C, to the advantage of B, he slightly diminishing his speed to let A reach A slightly ahead.

To the extent that B has his head to the right of the line AB, just so much smaller will be the arc that he will have to traverse to ram A; of course diminishing his speed to do this. He cannot be rammed by A, since he is in A's circle. The limit of B's advantage is when his head is in the line BD, when the two ships, turning in opposite directions on the same circle, and will meet head on at C. Should B's head lie to the left of the line $A\ B$, she will be inside A's turning circle and safe from A's ram, but he cannot ram A, as he will have to traverse a longer path than A to meet on A's turning circle, which he cannot do, since their speeds are taken as equal. If B's head lies to the right of the line $B\ D$ he will have A in his turning circle and the case is reversed.

THEOREM 3.—When a vessel, entering the turning circle of another, has her head towards her adversary, and succeeds in ramming him, the angle of contact is equal to the angle of the initial routes. (See Plate XII, Fig. 2.)

The initial route is the relative bearing of B from A, or the angle included between their courses, or the angle $B\ A\ E$ in the figure. To show that $B\ A\ E = H\ C\ K$.

$$\text{The initial route } B\ A\ E = 90^\circ - o\ A\ G$$
$$\text{The angle of contact } H\ C\ K = 90^\circ - o\ C\ H.$$

The triangles $o\ B\ G$, $o\ A\ G$, $o\ H\ C$, are equal; so also the angles $o\ A\ G$ and $o\ C\ H$, consequently $G\ A\ E = H\ C\ K$. The best way therefore to enter your adversary's circle is to have your bow on his middle point, and at the same time on the center of his circle. The adversary then is crossing your bows, and the angle of contact will be a right-angle.

THEOREM 4.—If two ships are too near to run directly at one another, and are steering convergent courses, the advantage, at any instant, is with the one which has the other bearing more on its bow. (See Plate XII, Fig. 3.)

In the figure, A having B bearing more on its bow, has the advantage from a ramming point of view. They are too near to suppose that B, having a shorter distance to traverse to reach the intersection, will attempt to run ahead of A.

THEOREM 5.—The advantage of bearing is greater, the nearer two vessels are together; it ceases when their distance is greater than five times the radius of their turning circles. (See Plate XII, Fig. 4.)

The demonstration of the part of this theorem is evident. B has the best chance to ram A at *B*, and less chance to ram A as he recedes towards *B'*, *B''*, since B has a longer distance to go over. It will be seen by Plate XII, Fig. 5, that A and B are six radii apart. B is in a position most favorable to ram, and A is in the most unfavorable position for being rammed. But A can turn through sixteen points and be in a position of equality with B before B can reach her.

THEOREM 6. (This theorem refers only to the rules of the road and has no war value.)

THEOREM 7.—When two rams pass broadside to broadside each should turn towards the other in describing their circles (*i. e.*, cross each other's wake) when they will meet again under the same circumstances. If they each turn with their helms the same way the one that is turned *towards* is at a disadvantage.

THEOREM 8.—In passing broadside to broadside the maneuver to turn under the stern of the other, should be commenced as soon as possible.

THEOREM 9.—When two ships are together broadside and broadside, if they have the same diameter of turning circle, the advantage will belong to the one who is the fastest, that is to say, to the one who describes his circle in the least time.

THEOREM 10.—Two vessels close to, and broadside to broadside, having turning-circles of different diameters, but whose circles are made in the same time, the advantage will belong to the one that has the smaller circle.

THEOREM 11.—When two rams are close to, and broadside to broadside, and on opposite courses; one turning quicker from greater speed, and the other having a smaller diameter of circle, the advantage will belong to the one with the greater speed, if each turns under the stern of the other, and to the one with the smaller circle if they turn with their helms different ways.

THEOREM 12.—Two ships passing broadside to broadside, on opposite and parallel courses, and close to, describing with helms in the same direction like turns, there exists a point which does not change, and which is the only point where they can meet. (This point is hard to determine, and the demonstration is not here entered into.)

THEOREM 13.—The quickest method of approaching another ship is to keep your bow pointed towards him.

VI.

In the action between the Esmeralda and the Huascar, and the Independencia and the Covadonga, in the Chile–Peruvian war, although nothing new in the way of naval tactics was developed, still the weaker vessels were handled with great *strategical* skill by their captains, who no doubt would have shown, had their commands been equal in any way to those of their antagonists, an intimate knowledge of the maneuvering of vessels, and the employment of their tactical qualities in an [illegible] of those officers [illegible] United States [illegible]

[illegible] the Huascar. [illegible] and the [illegible] the number of [illegible] on the [illegible]

[illegible] the Esmeralda: [illegible] great. [illegible] But [illegible] of saving it.

---

* [illegible] Huascar: length, [illegible] feet; beam, [illegible] feet [illegible] inches; length of [illegible] draught forward, [illegible] feet—aft, 16 feet; displacement, [illegible] indicated horse-power, [illegible] coal capacity, 300 tons; [illegible] maximum speed, [illegible] knots. Armament: [illegible] muzzle-loading Armstrong rifles, mounted in a revolving turret placed forward. The turret is on Captain Coles's plan, being supported on rollers and revolved by hand-gearing. The exterior diameter is 22 feet. [illegible] forward and the conning tower and a [illegible] gives command [illegible] of the horizon, that is, from [illegible] on either side of the [illegible] on either side of the stern line. Two 40-pounder muzzle-loading Armstrong rifles, one on the starboard quarter-deck and one on the port; one 12-pounder muzzle-loading Armstrong on the port quarter-deck. These [illegible] guns are mounted on wooden [illegible] carriages. Armor: The side armor, [illegible] below the water-line, has a thickness of 4½ inches abreast the turret, chambers, and engine rooms, diminishing to 2½ inches at the bow and stern. This is backed by [illegible] inches of teak and an inner iron skin ½-inch thick. The bow is strengthened and shaped for ramming. The decks are protected by 2-inch plates. The [illegible] forward in a small top-gallant forecastle, [illegible] in which the anchors are secured, and in an open poop aft.

[illegible] ram Independencia, built by Samuda at Poplar on Thames, England, [illegible] displacement, 2,004 tons; machinery by John Penn & Sons; [illegible] horse-power, 1,500; maximum speed on trial, April 27, [illegible] armament, two 150-pounder muzzle-loading Armstrong [illegible] twelve 70-pounder muzzle-loading Armstrong rifles [illegible] gun-deck. To this at the outbreak of the war, were [illegible] Vavasseur rifle on pivot in bows; one 150-pounder muzzle-loading Parrott rifle on pivot in stern. Armor, 4½ inches thick at water-line, and about central part of battery, backed by 10 inches of teak. Bow strengthened and shaped for ramming. Condition: hull good; boilers new. Rig, ship.

[illegible] The sloop of war Esmeralda, built in England in 1854. Hull, wood; length between perpendiculars, [illegible] feet; beam, 35 feet; draught, 14 feet; tonnage, old measurement, [illegible] tons; engines, simple, old type; nominal horse-power, 200; screw, single and lifting; speed, 3 knots; rig, ship; armament: original, eight 40-pounder muzzle-loading Armstrong rifles, in broadside, increased to fourteen 40-pounder muzzle-loading Armstrong rifles, broadside; crew, 160 men; condition of hull, old and rotten; boilers, very old and almost unserviceable.

Born April 3, 1848, he was still a very young commander. He had been a marked man in his service, having held positions of the greatest trust; by his conduct in the capture of the Covadonga and in quelling a serious mutiny on board the Peruvian corvette Union he had gained a reputation for gallantry; by being selected more than once as an instructor in gunnery at the naval school he had proved his theoretical proficiency in that all-important branch of study. Was this young senior officer fitted by his antecedents to surrender? The answer to this question is his conduct in the engagement which was about to take place—a fight that astonished the naval world; which established the precedent that, no matter what the odds be, vessels must be fought to the last, and which, on account of the intelligence and intrepidity that characterized it, and on account of the harm that was actually done to the powerful opponent, deserves a whole page in the records of fame.

It was a curious combination of circumstances that brought Grau and Prat together in deadly combat, both to die, sword in hand, in the heat of combat, within a few feet of the same spot on the deck of the Huascar, each being at the time of his death the senior officer of an immensely inferior force contending nobly against great odds.

At 8 a. m. the Huascar fired a shot that struck between the two Chilian vessels, and the action immediately became general; the Huascar singling out the Esmeralda, and the Independencia the Covadonga. The Chilian transport Lamar, which was also in port when the enemy was sighted, was sent off to the southward and took no part in the fight. After the firing had been going on for an hour, at distances varying from 2,000 yards to, perhaps, 1,000, the Covadonga steered to the south, the Independencia following her closely.

The Esmeralda remained in Iquiqui Harbor, fighting the Huascar. By this time the Peruvian soldiers had dragged a field battery to the beach, and opened fire at distances not exceeding 400 or 500 yards. Thus, with the 300-pounders of the Huascar on one side, and a field battery on the other, the Esmeralda was forced to abandon her position near the shore, which she had taken to avoid a ram attack from the enemy, and go farther out in the bay. The time when this occurred, and that at which the Huascar first rammed, has not been fixed satisfactorily; but it could not have been far from half past ten, two hours and a half after the beginning of the fight. It appears that Captain Grau was deterred from ramming by the fear of torpedoes, which he supposed were placed around the Esmeralda; and he rammed only when the latter vessel was driven from the place which she had first occupied, by the fire of the field battery on shore. The defense of the Chilian vessel would have lasted a much longer time if the fight had been decided entirely by the guns. The Huascar kept up a fire from all her guns for four hours, and during this time must have fired at least forty shots from her two 300-pounders; yet it is recorded that only one of these shots struck the enemy. This shot passed through the side, burst in the engine-room, and killed every one of the engineers, besides disabling the engine. The reply of the Esmeralda was most effective, as is testified by Captain Grau; but musketry and 40-pound shot are no match for 7-inch armor. Captain Grau is in error when he speaks of the mitrailleuse fire of the Chilians, in his report; neither the Esmeralda nor the Covadonga had machine guns of any kind. The Huascar had one long Gatling.

When the Esmeralda came out in the bay Captain Grau determined to ram her. In the first attempt, the Huascar, steaming about 8 knots and steering NE., struck the Esmeralda, nearly motionless and heading N., on the port quarter. The Huascar's engine was stopped when she was about one ship's length from her adversary. The blow was harmless. Captain Prat, followed by one man only, gallantly sprang on the forcastle, and, sword in hand, rushed aft on the port side of the deck, and was killed by a musket-ball at the foot of the turret. The command now devolved on Lieutenant Serrano. The Huascar backed off and made at the Esmeralda again, this time heading S.; the Chilian vessel presented her bow: the Huascar's engines were stopped too soon, and she struck the starboard bow of the enemy, doing little or no damage. Again a boarding party, headed by the commanding officer, Lieutenant Serrano, leaped on the Huascar's deck, but only to be shot down. The third attempt of the Huascar was better conducted. The head of the Chilian vessel had fallen off to W., and Captain Grau, steering S., going full speed, and stopping his engines when 20 feet from the Esmeralda, struck his adversary squarely on the starboard beam. The Esmeralda sank with her colors flying and guns firing.

The Covadonga,* meanwhile, was doing all that seamanship and courage could dictate to get away from her huge pursuer. She led along close to the shore, crossing shoal places, and actually, at times, almost in the breakers. The Independencia, with her raw, unskilled gunners, could not hit the little craft, though the vessels must have been within 200 yards of each other several times. Captain Moore, fearing that he could never end the affair with his guns, determined to ram; this he tried three times, and failed to accomplish. The third attempt was made at Punta Grueso, at a time when the Covadonga was not 100 yards from the beach and had actually touched on the reef. Steering about S.SE., the Independencia aimed an oblique blow at the Covadonga's starboard quarter, and, missing her enemy, struck a rock and stuck fast. It appears from the reports of both captains, Moore and Condell, that the helm of the Peruvian ship was not ported early enough to prevent her going ashore, because a shot from one of the Covadonga's 70-pounders killed her helmsman. The only steering-wheel of the Independencia was the ordinary one on deck.

It must have been 11.45 a. m. when the Independencia † struck. Captain Condell, seeing at once the state of affairs, turned his vessel, and, passing along the starboard side of the enemy, coolly took his position astern of him and began to fire. It has been asserted that the Independencia's ensign was hauled down and a flag of truce hoisted, on account of the deliberate fire of the enemy and her inability to return it, having fallen over on her starboard side, and her lower part having filled with water. To add to the discomfiture of those on board, a shell from the Covadonga, or an accident, set fire to the after part of the vessel.

Immediately after the surrender of the Independencia, and before she was taken possession of, the Huascar, which, having sunk the Esmeralda at 12.10 p. m., had remained to pick up the survivors of her crew, came around the western end of the island which forms the south side of Iquiqui Bay. She was about 10 miles off, and the Covadonga, having evidently disposed of the Independencia, was steaming rapidly away. The Huascar, after speaking her stranded consort to ascertain whether there was any immediate danger to the life of the crew, resumed her pursuit of the Covadonga. This pursuit lasted until dark, when Captain Grau, seeing that there were still 10 miles between him and the chase, and probably uneasy about the enemy's iron-clad's, whose position was unknown to him, gave up the pursuit and returned to the Independencia. This vessel it was clearly impossible to save, and she was set on fire and burned.

Nothing could have been better than Prat's plan of action. First remaining stationary in a corner between the island and the shore, he limited the field of his adversary's maneuvers to ram, conveying also the idea that he was protected by those terrors of modern naval warfare, torpedoes. This impression was rendered doubly certain in Captain Grau's mind by the report of the Peruvian captain of the port of Iquiqui, who managed to get aboard the Huascar in his boat. Again, by assuming this position, he reduced Grau to the painful necessity of sending his shell, at moderately short range, directly towards the town which was occupied by his own country-men. When forced by the fire of the shore guns, more dangerous, at that short range, against his wooden walls than the 300-pounders of the iron-clad, he hugged the shore as closely as possible, keeping up a heavy, well-directed fire from his guns of all kinds, how well directed the condition of the Huascar after the fight clearly showed. One shot entered the turret through one of its ports, and after balloting about considerably, came to rest without injuring any one. Had this been a shell it might have entailed considerable loss. Other shots cut the tripod foremast nearly away; so insecure did it become that Captain Grau feared that it would fall, in which case it would probably jam the turret. When the ramming began Prat called away his boarders, and, as already stated, actually succeeded, with one sergeant of marines, in reaching the enemy's deck. Had the contact been of longer duration he would have succeeded, probably, in transferring his crew to the decks of the Huascar with a very fair chance, according to Captain Grau himself, of capturing the vessel, as the crew was, with very few exceptions, very much demoralized. Serrano's attempt failed from the same cause. When the Huascar did finally succeed in sinking the Esmeralda, which was then little more than a stationary target, she injured her own bow so severely that extensive repairs were necessary. The musketry fire of the Esmeralda was so well sustained that it was thought that she was provided with machine guns.

---

* The gunboat Covadonga, captured from the Spaniards in 1866 by the Esmeralda. Tonnage, old measurement, 412; engines, old style, 140 horse-power; single screw; maximum speed, 5 knots; rig, three-masted topsail schooner; condition, hull poor; engines and boilers poor; armament, two 70-pounder muzzle-loading Armstrong rifles, on pivot carriages.

† See note on page 72.

Condell could not have done better with his little ship. That he followed the correct tactics in keeping close to the shore was proved by the results. His artillery fire, which was continued throughout the chase, was so excellent that he dismounted the heavy bow pivot of the Independencia before it had succeeded in sending more than one shot into him. What the effect would have been if this had not occurred may be imagined from the fact that this shot entered the starboard quarter, raked the whole length of the ship, and passed out on the port bow. The other two guns, being protected by iron plating, continued to fire, with but moderate results, owing to the want of training of the guns' crews. The small-arm fire of the Covadonga kept the enemy's crew below and killed the three helmsmen at the critical moment, according to Captain Moore, who, like Captain Grau, mistook it for machine-gun fire.

It was thus that Captain Prat's speech made to his officers and crew before the fight was carried out in its fullest details. Had the results of the action been different it might have passed for bombast; as it is, it becomes a fitting text for the naval students of the future:

"Children, the odds are against us. Our flag has never been lowered in the presence of the enemy; I hope that it will not be to-day. As long as I live that flag shall fly in its place, and if I die my officers will know how to do their duty."

Captain Moore was placed under arrest and kept a close prisoner on the Moro at Arica. The two 150-pounders of the Independencia were afterwards raised by the Peruvians and taken to Iquiqui.

This action, of course, raised the blockade of Iquiqui, and about 4,000 troops, Bolivians and Peruvians, were thrown into the place, which was visited also by General Prado.

The Huascar was considerably injured in the action, her tripod mast was so much damaged that it had to be removed on her return to Callao, her bow leaked from broken plates, and her turret was slightly out of line. She continued her cruise, however, to the southward. At Antofagasta she exchanged shots with the Covadonga, that lay inside of the reef, and was supported by three 150-pounders mounted in sand batteries along the face of the town.

VII.

TWO SHIPS AGAINST ONE.—It may seem strange at first sight to suppose that now-a-days one vessel would attempt to cope with two nearly her size, but in reality the two ships must work together, and be at all times alive to succor one another to compel victory to rest with them; for the single ship might steer down on one of the two advancing against her, close together and in line abreast, and when at the proper distance put her helm over and ram one, giving the other a broadside. Now, if the one first headed for and to whom she gave her first broadside was to attempt to ram her assailant the chances are that she would run foul of her consort.

Admiral Randolph says the proper course for the two ships to pursue when the enemy's single ship is bearing down on them is to form on a line abreast, with one ship's stern in a line with the other ship's bow and two cables apart. They should endeavor to keep the single ship between them. The idea of the line of bearing is, not only are the two ships' gun-fire more effectively arranged, but in case the single ship essays to ram one of the two ships the other ship can put her helm over to ram the rammer, without anything like the same danger there would be in an exact line abreast of running into her consort. At least this is Admiral Randolph's opinion.

There are several other ways that the consorts might arrange themselves, as in line ahead, or one might keep out of the fight until the other two were engaged, either in an artillery duel or in a ramming contest, and then could enter the fight and help her friend.

If circumstances should serve, that is, if there was plenty of smoke, which interfered more with the two than it did with the single ship, it would be good tactics for the single ship if she could keep outside of the two—outflank them in other words—to give one a broadside in passing and sweeping up under the stern of the other enter her turning circle.

We will consider A the single ship, and B_1 and B_2 the consorts.

Plate XIII, Fig. 1, shows how A should act.

Plate XIII, Fig. 2, shows how B_1 should run for A if he attempts to ram B_2, and, in case B_2 escapes ramming, how B_1 and B_2 must take care not to collide.

Plate XIII, Fig. 3, how B_1 and B_2 should act in case A acts as before. As soon as A's ramming maneuver is detected, B_2 should put his head on A and slow, B_1 should ram A, and B_2 should turn astern of the contestants after the collision had occurred.

Plate XIII, Fig. 4, shows the danger, according to Admiral Randolph, of line abreast and being close together. Either all three will meet at one point, or else B_1 and B_2 will collide.

Plate XIII, Fig. 5, shows how, in case A can outflank the consorts, he may force them into danger of collision.

Captain Fremantle says that the best way for one vessel to fight two, is to try and get them in line ahead, and that the best way for two vessels to engage one is to keep generally abreast and far enough separated to prevent the movements of one from interfering with the other. The two vessels should strive to keep the single vessel between them, and on their bows.

VIII.

To illustrate an engagement of one vessel with two others, we cite the combat between the Peruvian monitor Huascar and the Chilian iron-clads Blanco-Encalada and Almirante Cochrane. The account is taken from Lieut. T. B. M. Mason's work on the operations of the war between Chili and Peru:

The Chilian squadron at Mejillones having coaled, put to sea during the night of the 7th in two divisions; the first, under Commodore Riveros, consisted of the slower vessels, Blanco, Covadonga, and Mathias Cousiño, left at about 10 p. m., and steered down the coast towards Antofagasta; the second, under Commander Latorre, consisted of the Cochrane, O'Higgins,[*] and Loa, left at about 1 a. m. of the 8th, with orders to cruise 25 miles on and off Point Angamos. This was done in accordance with telegraphic instructions from the director of the war, and differed slightly from the original plan of the commodore, who intended to have moved south along the coast in similar divisions, the first division skirting the coast and looking in at the bays, while the second stood in the same direction but farther off shore, and about 40 miles on the starboard quarter of the first. Either of these plans would probably have entailed the same results. Thus it was that, at 3.30 on the morning of October 8, the weather being fine and clear, the lookout in the Blanco's top reported the smoke of two vessels approaching from under Point Tetas, distant about 6 miles. At daylight the enemies recognized each other. The Huascar ran for an hour to the southwest at full speed, making about 10¾ knots with sixty revolutions and an average pressure of 25.5 pounds of steam, the Blanco and Covadonga following, making about 7¼ knots. The Mathias Cousiño was sent in towards Antofagasta, but later turned to the northward and followed her consorts. Commodore Riveros saw immediately that the chase was hopeless; still, on the chance of an accident to the machinery of the Huascar or her consort, or of their turning to the northward and being cut off by the second division, he determined to continue it.

It has been asked, and with good reason, whether the results of the battle might not have been different had the Peruvian ships engaged the Chilians at this time. It is true that the Union was a much more powerful vessel than the Covadonga, and that both she and the Huascar had a great advantage in speed. When, however, we consider that the Admiral's orders were very explicit, and wisely so, that he should run no risks with his ships, as the loss of the Huascar would give the Chilians the command of the sea, it does not seem strange that he should have attempted to escape. Admiral Grau, finding that he was rapidly distancing his pursuers, turned to the northward at about 5.40, and eased his engines by reducing the revolutions to fifty-three. Having been on deck all night, he now lay down for some much needed rest. At about 7.15 smoke was seen, from the Huascar, on the horizon to the northwest, and at 7.30 she having stood slightly to the westward to reconnoiter, the Cochrane[†]

---

[*] The corvette O'Higgins, wooden hull, built in England in 1867. Length between perpendiculars, 217 feet; beam, 35 feet; mean draft, 15 feet 9 inches; displacement, 1,670 tons; engines, simple, old type; screw, single and lifting; speed, 8 to 10 knots; rig, ship; armament, three 7-ton muzzle-loading Armstrong rifles, on pivot carriages; two 70-pounder muzzle-loading Armstrong rifles, in broadside; four 40-pounder muzzle loading Armstrong rifles, broadside; number of crew, 160 men; condition, hull fair; boilers very old and poor.

[†] The armored, box-casemated, sea-going rams Almirante Cochrane and Blanco Encalada. Length between perpendiculars was 210 feet; beam, 45 feet 9 inches; draught, forward, 18 feet 8 inches—aft, 19 feet 8 inches; height of battery above water-line, 5 feet 6 inches; displacement, 3,560 tons; engines, two pair, compound, horizontal trunk; horse-power, 2,960; screw-propellers, 2; speed, measured mile, 12.8 knots.

The armament consists of six 9-inch 12-ton muzzle-loading Armstrong rifles, mounted and her consorts were recognized. The Huascar was seen at about the same time from the Cochrane's top, and the Loa was sent to reconnoiter. Admiral Grau, who had now come on deck, probably felt confident that he could elude the Cochrane, as her speed, according to the latest information in his possession, was only 8 knots, and stood for a short time towards the Loa. Finding, however, that the Cochrane was changing her bearings more rapidly than he had anticipated, he stood more to the east, and ordered full speed. The Union, which had remained on the Huascar's port quarter, now, at about 7.45, crossed her stern and passed to starboard of her at full speed. From this moment this vessel, it is alleged, by order of the Admiral, made the best of her way to Arica, followed until dark by the O'Higgins and Loa. The conduct of these three commanding officers has been much commented upon; the first for not engaging, the others for not continuing the pursuit. The three iron-clads were now about 8,000 yards distant from each other. Grau saw that his only chance of escape lay in his speed. At 9.10, as the Cochrane had approached to within less than 4,000 yards, and it was evident that she could cross his bows, he ordered the crew to quarters, and shortly afterward entered his conning-tower alone. In going to quarters an accident occurred in shifting the lead from the ordinary steering-wheel

---

on Scott muzzle-pivoting carriages, in a central-box battery, with double re-entering forward and after ports, this arrangement permitting the forward gun on each side to train from right ahead to abeam, the central gun from 70° forward of the beam to 35° abaft the beam, and the after one from abeam to right astern. Each ship carried, besides, one 20-pounder, one 9-pounder, and one 7-pounder. The Blanco Encalada carries two 1-inch ½-pounder Nordenfelt machine guns, one on each end of the bridge, and the Almirante Cochrane one mounted on the knight-heads forward. After the battle of Angamos several Hotchkiss revolving guns were added to the armaments for use against torpedoes.

In addition to these light guns 12 picked riflemen in action are stationed in the fore and main tops, protected from observation by screens. The battery is 7½ feet high, the armor is in two strakes, the lower of which is 8 inches and the upper 6 inches thick on the sides and forward part, while on the after part both have a uniform thickness of 4½ inches. The armor is backed by about 14 inches of teak, inside of which is a thin iron skin. The armored transverse bulkheads forming the forward and after ends of the casemate extend below the water-line. The iron double-bottomed hull is divided by seven water-tight transverse bulkheads, and is protected around the water line by an armor-belt 9 feet wide in three strakes. The middle strake is 9 inches thick amidships, while the other two are 6 inches, all of them tapering to a uniform thickness of 4½ inches at bow and stern. The teak backing behind the armor-belt has an average thickness of 10 inches, and the whole of the armor and backing is fastened to a double thickness of skin plating, supported by massive angle-iron frames on the inside and longitudinal angle-iron guides on the outside. The upper deck, which is flush with the upper edge of the armor-belt, is protected by 3 inches of armor near the casemate and 2 inches at the bow and stern. The casemate overhangs the side about 3 feet.

It is reported that these vessels when in good condition make 10 knots per hour on a coal consumption of from 30 to 35 tons per day. Their coal-bunker capacity is 254 tons. They are bark-rigged and have a complement of 300 men. They can fire their guns by electricity, and their steam launches, of ordinary type, are fitted to carry spar torpedoes. Beside its regular armament each carries a rocket tube and rockets. Neither is fitted for torpedoes.

The stem is a solid casting, ram-shaped, and strengthened by backing and bracing. The ram extends 7 feet 6 inches beyond the bow, and the point is 6 feet 9 inches below the water-line. Condition of the hulls, good; Blanco's bottom very foul; Cochrane's better, as she had been taken to England to be docked and cleaned. The Blanco's bottom is sheathed with wood and zinc.

under the poop to the fighting one in the turret-chamber under the conning-tower. This caused the Huascar to yaw considerably whilst a makeshift tackle was being rigged. At 9.25 the Cochrane, being about 3,000 yards distant, the Huascar opened fire with her turret-guns. The second shot, ricocheting ahead of the Cochrane, entered her unarmored bows, and after smashing the galley and causing some slight damage fell on deck without exploding. At this time the Blanco was about 6 miles astern. The Cochrane did not answer these shots, but stood on until within 2,000 yards, when she opened fire. One of her first shots penetrated the Huascar's armor on the port side and, exploding, entered the turret-chamber, where it set fire to the light wood-work, killed and wounded twelve men, some of whom were at the winches used to revolve the turret, and drove its own fragments and *débris* of all kinds under the turret-trucks, which it jammed for the time being. A 10-inch 300-pounder Palliser chilled shell from the Huascar, fired at a range of 600 yards, struck the Cochrane's starboard side-armor at an angle of 30°. The plate, which was 6 inches thick, was indented or scored out to a depth of 3 inches, the bolts were moved, and the backing was forced in; a beam was also broken. The shell probably broke up.

At 9.40 the Huascar stood a little to port with the intention of ramming the Cochrane, but the latter prevented this by turning an equal amount to port and steering a parallel course. At 9.45 the conning-tower was struck by a shell, which exploded in it, shattering it very much and blowing Admiral Grau to pieces—only one foot and a few fragments being found. Admiral Grau usually directed the movements of his vessel with his head and shoulders out of the top of the tower; the shell, therefore, must have hit him at about the waist. The concussion from this shot caused the death of Lieut. Diego Ferré, the admiral's aide, who was at the fighting-wheel, separated from the conning-tower by a light wooden grating only. This officer's body was mistaken for that of his commander, and caused the erroneous statements which appeared at the time of the combat. No wounds were found on Lieutenant Ferré's body. Part of this shot also disabled the fighting-wheel, and the vessel turned to starboard and ran to the eastward until, the damage having been repaired, she was again headed north. About this time a shell penetrated the armor of the turret (now trained on the port quarter) in its thickest part to the left of the port of the right gun, killing and disabling most of the guns' crews. Among the former were the two gun-captains, and among the latter Commander Meliton Carbajal, chief of staff, who had come to inform the second in command, Commander Elias Aguirre, that he was now in command. This shot furnishes the data for the killing effect of the projectile fired experimentally at the Glatton some years ago, which by a curious coincidence struck exactly the same part of the turret. Relief crews were sent to the guns, but the firing became very wild, as the men were comparatively inexperienced. The right gun had been disabled by the shot above mentioned, which bent the right compressor and cap-square. Lieutenant Rodriguez, while looking out of one of the gun-ports, had his head taken off. An eye-witness reports that the native part of the crew was much demoralized by the loss of their commander. The cabin and wardroom were full of men and officers, some wounded and many refugees from the upper deck, from which every one had been driven by the Nordenfelt and small-arm fire of the enemy.

The Cochrane now attempted to ram, coming at right angles to her adversary firing her starboard bow gun at 200 yards; the center gun missed fire. She missed the Huascar and passed about five yards astern of her. A shot from one of the Cochrane's port guns pierced the armor of her opponent on the starboard quarter, exploding and doing much damage, including carrying away the iron tiller-block, which served as a lead for both ordinary and fighting wheel ropes. The Huascar now again headed to the eastward. A shell pierced the armor abreast the engine-room, covering the engines with *débris*, and killing and wounding several persons in the engine-room gallery. Among the latter were Surgeon Tavara and Mr. Griffiths, the master of the schooner Coquimbo, captured a few days before, and whose crew were forced to render service during the action. The relieving-tackles, which had a very bad lead behind the transoms in the admiral's cabin, were now manned. The steering was very uncertain, as Commander Aguirre had to conn the vessel from one of the lookout hoods of the turret, and the word had to be passed clear aft on the lower deck to the men at the relieving tackles. The Cochrane again attempted to ram the Huascar, firing her starboard bow gun as before at 200 yards, and coming on at right angles with the center guns trained abeam with three degrees depression. She again missed her blow, and passed astern. The center gun was being loaded at this time.

It was now about 10.10, and the Blanco arrived on the scene of action, passing between the Huascar and the Cochrane just as the latter was preparing to ram a third time. The Cochrane, to avoid the imminent danger in which she was placed by her consort's ram, was forced to turn to port and then to the northward, increasing her distance to 1,200 yards. The Huascar turned to starboard and headed for the Blanco with the intention of ramming her, at the same time firing some ineffectual shots in her direction. The Blanco sheered to starboard also, and passing at about 25 yards' distance, poured a broadside into her stern, which killed or wounded all of the men at the relieving-tackles, and also many of the wounded and others assembled in the officers' quarters. The wounded were now removed to the coal-bunkers and store-rooms. The Huascar now stood to the westward.

On account of the number of shots which had traversed the smokestack, driving down soot, *débris*, and smoke into the fire-room, it was impossible to see the gauges. The water fell too low in one of the boilers, which allowed the tubes to be burned through, and caused a great escape of steam. This led the Chilians to believe that they had struck one of the boilers. The small-arm fire at some previous time killed and disabled three out of the four men stationed at the Gatling gun in the Huascar's top, although protected by a boiler-iron screen. The fourth man went below. This must have been done by the small-arm men in the Chilian tops; the latter were higher than that of the Huascar, which had no top covering or hood. The breast-high shield bore no evidence of having been penetrated from below. At 10.25 the Huascar's colors were shot away at the flag-staff, and for some moments she was supposed to have surrendered, and all firing ceased. A loader at one of the guns went aft and hoisted another flag at the gaff. A shot about this time penetrated the turret of the Huascar, killing or mortally wounding every man in it, including Commander Aguirre. Some idea of the terrible effects of this shot may be drawn from the fact that when this officer's body was found and identified, all the upper part of the head was gone, the lower jaw only remaining, four wounds on the right leg, a cut across the stomach, and six body wounds; the right shoulder and arm had disappeared entirely. He was standing at the time to the left and rear of the left gun, with his head in the sighting-hood. Lieutenant Palacios was terribly wounded by this shot. At Commander Latorre's urgent request Palacios was sent on board the next northern-bound mail steamer, but died before reaching Lima.

The command had devolved upon the fourth officer, Lieutenant Pedro Garezon. The vessel was almost unmanageable and on fire in several places; still the engines were kept going, and the left turret gun was fired occasionally. The Cochrane now returned and again tried to ram; she was only prevented from doing so by the chance movements of the Huascar. Both Chilian ships now followed the Huascar, using the bow and center guns, accompanied by an unceasing shower of small-arm and machine-gun projectiles. The Cochrane was struck during the action, probably when she turned off to give place to the Blanco, by a shell which entered her unarmored stern and caused considerable damage, wounding ten men, of whom two afterwards died. The Covadonga now came up and succeeded in putting herself on record by firing one gun. Lieutenant Garezon, after calling a council of surviving officers, sent Sub-Lieutenant Ricardo Herrera to the chief engineer with orders to attempt to sink the vessel by opening her valves. Chief Engineer MacMahon and his assistants succeeded in partially accomplishing this by opening the circulating-valves of the condensers, to do which they had to stop the engines. They were at work on the bonnet of the main injection-valve when Lieutenant Simpson of the Cochrane interfered, revolver in hand. While this was going on below some of the men forward crawled up through the fore-hatch and waved towels and handkerchiefs, seeing which the Chilians ceased firing. The flag was then hauled down. As the Huascar's engines did not stop at first, they were going to reopen fire when she became motionless, probably for the reason already stated. She was immediately boarded by boats from the Cochrane, under Lieutenant Simpson, and from the Blanco, under Lieutenant-Commander Castillo, chief of staff to the commodore; with them came surgeons and engineers.

It has been asked, of what use would the Whitehead system of torpedoes have been in such an action? The answer would seem to be that the Whitehead or any of the diverging systems would have proved to be dangerous and suicidal. The spar type alone might have been used. It is worthy of note that, while the Chilian vessels could always bring some of their guns to bear on the Huascar, the Huascar found herself in many positions where only sheering would bring her guns to bear on them. In fact, this action tends to prove that an all-round fire, even inferior in single guns, will have a great advantage over a preponderance of fire within only given limits.

IX.

TWO VESSELS AGAINST TWO.—In two vessels against two we cannot follow the tactics of two against one. The ships must work together or there is danger of two combining on one. The two vessels should keep within one cable of one another, and, according to Captain Fremantle, in line abreast, and according to Admiral Randolph in his modification of line abreast. Both authorities agree that they must act together and try to isolate one of the enemy and combine on him.

It may be laid down as a maxim that vessels engaging two and two, the advantage is with that side whose ships are close together.

Plate XIII, Fig. 6, exemplifies this, the ships being in Admiral Randolph's formation. A_1 and A_2 are nearest together. B_1 in order to ram A_1 at x must put his helm down the *same instant* that A_1 does, and therefore must have anticipated A_1's move, which is not likely.

Plate XIII, Fig. 7, shows when B_1 and B_2 choose to attack. A_1 and A_2 are in closer formation. A_2 can see B_2's move to ram A_1 well marked before he need put his helm down to ram B_2 at x.

THREE SHIPS AGAINST TWO.—The general rule is for each side to strive and ram the enemy's ships furthest off. The two ships, keeping well together, should try and ram the two ships furthest off of the line. Other than this rule there is no special tactics for the two ships to use. The point to strive for is to use both of your ships on one of the enemy if you can.

For the three ships, a formation is best where two of the ships are in line abreast, or in a modification of it, and the third ship is kept in the rear, ready to assist either of her consorts which may be attacked.

CHAPTER VI.

THE ADMIRAL AND HIS FLEET.

I.

The commander-in-chief of a fleet in time of war has from the outset a very complex duty to perform, viewed from a tactical standpoint. Not only must he be able to exercise his fleet in the various evolutions, and to classify and to arrange his ships in line-of-battle according to their values as regards speed, armament, and turning qualities, but he must know just what types of vessels are suited to compose his squadrons, in order that he may undertake the work cut out for him.

To discuss only that part of the Admiral's duty which relates to fighting his fleet on the open sea or on the enemy's coasts, or to defending his home ports, comes more within the province of these pages.

He must have an intimate acquaintance with the signal-book, and in it should be laid down his plans of battle and the lines of action that will be followed in an engagement. These, in common with all other tactical maneuvers, should be thoroughly discovered to his captains.

The Admiral must be versed in naval strategy, and there are certain rules governing its general principles which he must ever keep in mind. Captain Fremantle formulates them as follows:

> 1st. In any fleet intended for action on the open sea the ships must be so far alike as to be able to act together against the enemy in any tactical evolution which the Admiral may require to be performed.
>
> 2d. If special ships, such as rams, gunboats, or torpedo vessels, are attached to a fleet, they must act independently of other ships, according to a prearranged plan, in which all their peculiar qualities may be best developed.

Since the problem to be solved is how one squadron is to gain an advantage over another of equal force, we think that the solution may be summed up in the following maxims:

1st. Surprise an enemy and attack him when he is unprepared.

2d. Overwhelm a portion of his force with the whole of yours.

There are certain main objects to be clearly borne in mind which follow from these maxims. These are, primarily, so to form the fleet that it may not offer any isolated portion to the enemy's attack, and that the whole fleet may readily be brought into action to repel attack; secondly, so to maneuver as to be able to concentrate your force on a point of the enemy's formation.

To carry out these objects certain tactical action must be resorted to; for instance, disguising to the last moment from the enemy your plan of action, so that it may come to him in an unexpected way or from an unexpected quarter, such as getting him between two fires or massing on one of his flanks. To do this will require thorough drill, the most perfect discipline, and a complete knowledge of naval tactics.

According to Captain Rivet, certain strategical considerations will influence the determination of the commander-in-chief as to whether he should force an action or avoid it if he can. Among them will be found the following:

Are the nearest coast ports friendly, neutral, or inimical?

What are their distances, and how do they bear?

Can re-enforcements be depended upon during the action?

In what direction can it be reasonably hoped that these re-enforcements will appear?

It may be set down as a maxim that a fleet, in *any* formation, if it discovers the enemy near at at hand, as, for instance, through the lighting up of a fog or coming around a point of land, and this enemy in the midst of performing an evolution, it is the duty of the commander-in-chief of the formed fleet to charge the other, even if the formation then in is not a good one for attack, and the formation the maneuvering fleet is striving for is better than his own.

In modern warfare, with great clouds of smoke and rapidly moving vessels, it will be with great difficulty that friend can be distinguished in action from foe. To prevent accident, it is possible that nations will assume some color or some distinguishing mark for their fleets, as they have color and cut for their army and navy uniforms. We can conceive of a weak fleet, as a piece of strategy, assuming the enemy's livery, and adopting some other means of distinction, for the time being, which will permit them to be recognized by their friends.

Lieutenant Campbell says:

> I look upon the system of communication between the Admiral and his fleet as vitally important to the success of an action in the present time and in the future, even more than in days gone by.

Referring to his own Navy, Mr. Campbell says:

> With soft coal, as now carried, it is literally impossible to make out the Admiral's signals, and this is still more palpable when topgallant masts are down and the ship is clear for action.

Coal, therefore, for purposes of fighting at sea, must be smokeless. Since we, in our Navy, burn generally anthracite coal, we are to a great degree spared the annoyance of smoke, but whether we can develop the same high engine-power with this fuel which can be done with the softer coals we leave to others to decide. In a pitched battle, though, the enemy's smoke puts us all in the same category.

As this will be the case, battle signals must be very simple. There should never be a hoist of more than three flags, and shapes should be substituted for colors, if possible, such as is used in *Distant Signaling*, according to the International Code. Still better, signals made up of cones, double cones, cylinders, and balls should be employed.

Most authorities agree that in action, on account of smoke, the weather-gauge is almost as necessary now as it was considered to be in the days of Rodney and Nelson. There are tacticians, however, who believe that this position does not possess the merit claimed for it, and prefer to have the wind set in a direction that will bring it abeam for each vessel when attacking. Lieutenant-Commander Goodrich, U. S. N., says that the weather-gauge prevents you from seeing where your missiles strike, a very necessary point to be sure of. Under all circumstances, we believe that the Admiral should so maneuver his command as to be on the weather end of his line.

Ships, in all probability, will have to coal on the open sea, as, for instance, when maintaining a blockade or in long voyages, especially if sail power is still further reduced. Probably no nation has had greater experience in this respect than our own, and in the event of war now, unquestionably our experience will be still further enlarged, as we have no colonies upon which we can rely, and coal undoubtedly will be considered contraband of war. Several methods for coaling on the open sea have been proposed, and one suggested by Lieut. R. S. Lowry, of the British Navy, seems to possess, at least, the claim of novelty. His plan is substantially as follows:

In coaling at sea the coals should be taken on board with the vessel steaming ahead, especially if there is any sea on, as will likely be the case nine days out of ten. A steamer should be fitted to carry a cargo of coal already put up in "carriers," which resemble somewhat the life-cars now used on sea-coasts to save life. Each carrier holds one ton or less. The collier is towed on the quarter of the ship, and, besides the towing hawser, there is a jack-stay from the quarter of the collier to the bow of the ship. The carrier is hauled along this last line in the water, and taken on board the ship by a yard-and-stay, if coaling over all, or by yard-arm purchase and gurnet if coaled through a port. The empty carriers are sent back the way they came.

The strategic value of coaling points is apparent. Nations with navies must make sure in time of peace that their vessels will not be rendered useless in time of war through a lack of fuel-supply. This supply may be divided into two classes, *fixed*, or coal stations, and *movable*, or by steamers using a temporary base. Probably the carrying on of a war will exact both systems being in a degree maintained. Each has its advantages, but undoubtedly the last category presents the greatest number.

We have said that a necessity for coal supply must be met in a time of peace; that is, either the coaling station must be protected by diplomatic methods, or else by regular fortifications and marine defenses. In most cases this last condition would necessitate purchase of the territory, and the coal station immediately partakes, more or less, of the nature of a colony. In time of war this station will have to be guarded by vessels, which could be otherwise employed, and therefore develops at once a disadvantageous aspect. Again, it may be a long distance from the theater of war, in which case no small percentage of fuel will be burned by a vessel going to this station and returning to her duties with the fleet. Another point: the enemy will do his best to capture it, and since ships will probably have to keep up the supply at this depot, he will try to seize the colliers *en route*. One of the few advantages of this means of coal supply is that at the outbreak of hostilities coal can be obtained whereas otherwise the necessity would have to be foreseen, and vessels with fuel-cargoes be dispatched in time to supply the fleet.

To insure a coal supply under the second category, in time of peace, the Government must encourage a large proportion of the fast merchant steamers to be so built that they can carry cargoes of this commodity to such rendezvous as the nature of the war shall decide. These rendezvous, from a strategic point of view, should be as varied as possible in location, so as to mislead the enemy. The advantages of a movable coal supply here become apparent. The location of the depots not being known to the enemy, the capture of the supply vessels is much less likely. Then, the points of supply being near the base of operations, little or no coal will be consumed uselessly. The drawbacks to this method of supply are that a rendezvous where the fleet could coal, having a hostile environment, would be harder to establish, and, if established, would be more likely to be attacked in force. Then, again, steamers at the outbreak of a war may be hard to obtain, the distances that they have to be sent may be very great, and the fleet might suffer in consequence.

II.

Admiral Aube remarks, "A fleet superior in numbers will be, from the commencement of a naval war, the mistress of the seas, other things being equal."

According to Captain Noel, there are two fundamental principles to be observed in preparing a fleet to operate in time of war:

1st. In selecting weapons for service with a fleet, choose those that are capable of inflicting the greatest possible injury on the enemy with the least possible danger to yourself.

2d. In the organization, maneuvering, and formations of a fleet, and in the use of signals, study the utmost simplicity, arranging everything with a view to efficiency combined with the fewest prospects of damaging friendly ships.

Ships may be classified under the following heads, and may be combined to compose a fleet of armor-clad line-of-battle ships: A reserve of armor-clads, observation squadrons, cruisers (preferably of steel), commerce destroyers, and dispatch vessels. Ships from these classes, either combined or single, will operate especially on the high seas. Coastwise squadrons will be composed of armor-clads, gun-vessels, tenders, harbor flotillas of gunboats, torpedo-vessels, torpedo-boats, and their tenders. There are other vessels that must be used *with* the fleet which may not be considered *of* the fleet, and which are only furnished when required to fulfill some special duty.

Captain Noel, for warlike purposes, would have his navy divided as follows:

1st. A fleet of heavy ships of the line. These vessels, by reducing their top-hamper, and having only topsails, courses, and fore-and-aft sails bent, would save enough weight to permit stowage of extra coal. They should be provided with heavy towing hawsers.

2d. A squadron of cruisers attached to this fleet, all of great speed and fully rigged. Their duty is to reconnoiter, make prizes of hostile cruisers, and to obtain information from shipping.

3d. Dispatch vessels.

4th. Torpedo-boats of a size large enough to keep the sea on their own account. In cruising they should keep with the ships whose tenders they are.

Captain Harris says:

> As the speed of the slowest ship is the speed of the fleet, no vessel should be assigned to the line of battle of less speed than 12 knots. With the swiftest fleet lies the option of giving or declining battle, and also whether or not the battle will be limited to artillery alone.

Lieutenant Besson, M. F., asks the following question concerning a reserve squadron: Should the fleet be divided and fight with a certain number of ships, letting the others keep out of the battle until the formations are broken up, or ought the fleet to be kept together and should there be no reserve? This query he answers by saying that every fighting formation presents two feeble points. These are the ships furthest off; that is, the outside or flank vessels. Divide your fleet into detached squadrons and you increase these feeble positions, and therefore diminish its power. If your fleet is much larger than that of the enemy it might be done; otherwise not. Is it not more rational to put the reserve on the field of battle to strengthen some part of your line?

There are three places to put the reserve; they can either be put between the line-of-battle ships, in line abreast, so as to diminish the distances without adding to the length of the line, or they can be put behind the center or wings of this same line abreast.

In the first case they interfere with the free movements of the ships, which is a bad feature, but there seems to be no fault to find with the other two positions in which we consider they can be placed.

The latest authorities combine in the opinion that there should be no regular reserve squadron, believing that all vessels of any size and strength should be in the line-of-battle.

We would call attention to the necessity of having an efficient squadron of "lookout" vessels. Two squadrons bearing down on one another, and steaming at the rate of 10 knots, pass over three cables' length in one minute. Hence the necessity of great speed in these vidette vessels.

These vessels will probably be unarmored cruisers, but there are many tacticians who are of the opinion that, besides their lookout work, they should be placed in the line of battle. Admiral Penhoat says, decidedly:

> Large cruisers of great speed and few guns, or of feeble battery power, should be fitted with torpedoes and be put in the line of battle. Such vessels will increase their value if to these qualifications is added turning power.

A fleet should have its videttes stretched over a distance of 20 miles ahead and 10 miles on each flank.

It must be remembered that this vidette or lookout squadron is a regularly organized body, and differs entirely from single vessels sent out from any squadron of the fleet to observe the enemy or to draw his fire. These last may be termed skirmishers.

In that part of the fleet termed "the convoy" must be vessels fitted to carry ammunition. As they will have to supply the fleet under all conditions of environment, their fittings as regards protection from projectiles of the enemy, defense from any attack, and ability to supply their cargo becomes a serious war problem. They should be supported by rams and torpedo-vessels (these last they should carry), and by one or two powerful corvettes. These corvettes should be furnished with good towing hawsers. The armament of the ammunition ship should be a large number of machine guns. The enemy will do their utmost to destroy or capture such a vessel.

Large, clumsy ships, with inferior speed and large evolutionary circles, should never be permitted to cruise alone, no matter if they have heavy batteries and are well protected by armor.

III.

The Admiral should supply to each captain commanding a vessel under him, copies of the "helm table" and speed table" of each vessel of his fleet, so that it can readily be found, on the commander-in-chief signaling the number of revolutions of the screw of his flagship, how many revolutions are necessary for each ship to make in order to preserve the formation. Then, again, each captain, knowing which ship has the largest turning circle can, when this vessel signals her evolutionary helm angle, judge what amount of helm to give his ship. Mast-head angle tables, for open and closed order, must be prepared for each ship both when in cruising and in fighting trim. Each captain must have these *data*.

All professional writers call attention to the necessity of the captain being thoroughly informed as to the Admiral's plans, and agree that they should be strictly conformed with, especially in respect to the speed of the ship and the intervals and distances to be maintained. If the commanding officers of ships are not thoroughly imbued with the spirit of the commander-in-chief, and are not conversant with his tactical plan of action, there can not only be no success, but only disaster and defeat can be looked for.

IV.

A great diversity of opinion exists as to the post the Admiral should occupy in an engagement. No doubt he should be in a position where he can see and where he can be seen of all, so that the simple signals with which he must content himself can be easily observed. Personal example, however, will weigh more in the scale of victory than signals, and therefore we find that since all actions now are based on the ram, the Admiral's post is in the place of danger; he must lead into battle. Admiral Penhoat says: "He should lead in in line ahead. He can then change direction of the fleet without using signals."

By some authorities the Admiral is placed in the center of the line; this is an excellent post should he elect to fight in two lines ahead or even in line abreast. The only point to be made against this position in this latter formation, is that the commander-in-chief's movements and signals will be more obscured with smoke than if he was in some vessel large enough to lead into action, but which, not having been given a number in the line, can shift to the weather flank. As the flanks will be the points most likely to be attacked, we conceive it to be the place of the Admiral to make his presence felt on either one or the other of them.

There are writers who believe that the post of the Admiral should be with the reserve, either in a special ship or in one of the armor-clads We hardly see the philosophy of this in a pitched battle, as the flagship would probably be inferior to the armor-clads of the line-of-battle in one or more respects.

A German writer has the following remark on the post of the commander-in-chief during an engagement:

> The Admiral's flag belongs on the largest and most powerful vessel, which should outshine all others as a brilliant example in the heat of battle. History shows that the Admiral must himself be in the midst of the fight. If he wishes to be the vital element in his ship, and to make the best use of all the components of his command, then he must put himself in a position to see everything and to be seen of all.

CHAPTER VII.

FORMATIONS.

I.

There are tactical precepts which are common to armies fighting on shore and to fleets engaging at sea. Napoleon says: "Concentrate your forces; do not have a weak point. To move *en masse* and with rapidity on the enemy, and to attack him where he is weakest, is the secret of victory."

The principle which answers to this is *concentration*. This precept of war, which is universally admitted to be excellent, is especially applicable to fighting with rams. To weaken or to destroy by greater numbers a part of the enemy's fleet, then to be able to bear down afresh on some other part of his formation with a superior force, is the special object of all attacking maneuvers.

A fleet is in order of battle when all the vessels composing it can use perfectly all the means of offense and defense that they are provided with, without interfering with one another or detracting from their mutual support. The offensive weapons of the line of battle are guns, rams, and torpedoes.

The principal conditions which a formation of a fleet for attack should fulfill are:

1st. The largest amount of liberty of evolution for each vessel, and at the same time the best employment of the peculiar fittings of each ship for attack.

2d. It should permit the execution of every maneuver in the least time, with the greatest speed.

3d. It should be simple, flexible, and easy to keep, under all conditions of sea and weather, without exposing the ships to collision.

4th. Unity of direction of each vessel's course must be preserved. The vessels must maintain their stations, and they must be able to change rapidly to the direction of the enemy's attack.

5th. It should be such as to permit the fleet to be able to cope with any particular necessity for preservation imposed on them by the enemy.

6th. Between vessels of the fleet there must be mutual support either for attack or defense.

7th. It should permit the fleet to be kept well together under the eye of the Admiral, so that each vessel can see his signals.

In dividing the fleet, should the basis of division be either the group or section, attention should be paid to the equality of the ships which are to act together, more especially to their maneuvering capabilities. These vessels should exercise together, should learn to move as one, and should only be changed under circumstances of necessity.

In old days the signal-book was shut when the fleet bore down upon the enemy. Now it may be required to maneuver as a fleet until actually engaged. For this reason Captain Fremantle thinks that a long line of ships, either ahead or abreast, will be impracticable.

Any attacking formation will finally disappear during an engagement. and the fight will, in all probability, settle down to actions between vessels. The Admiral must be careful to designate certain vessels to act as rallying points, or as *nuclei* for the re formation of his fleet, either for purposes of concentrating for renewed attack, or to combine for mutual support to fight in retreat.

II.

A fleet or squadron can be formed as follows:

1. In line ahead.
2. In line abreast.
3. In bow and quarter lines.
4. In triangles or quadrilaterals of different shapes.

The first three formations which are simple, can be made *compound* or *complex* by doubling or repeating the formation in some peculiar manner, as, for instance, forming in two lines ahead, alternate line abreast, in naval square, in double echelon, &c. The fourth formation is always *compound*

The basis of fleet division is either the ship, section, or group. The most modern idea is probably that each line-of-battle ship is a unit in itself, and in order that it may be thoroughly effective it must not be hampered in the use of any of its weapons by having to act as part of a formation with any other vessel or vessels. Mr Besson says, although the tactical unit *is* the single ship, and while her first duty is to act for herself, still a designated vessel next to her in line should be combined with her to develop the best results to be obtained with the ram for each vessel.

Captain Courbet, M. F., in 1872, in order to apply in the best manner the principle of concentration of a larger portion of his force on a smaller portion of the enemy, took as the tactical unit *two* vessels, which he called a *section.* One of the vessels was termed the leader, and had the other vessel under his control. These two vessels, in English, may be designated as the " leader" and his "mate." They must combine their energies in attack and give mutual support.

Admiral Penhoat also favors the interdependence of two ships, and in all the formations and movements discussed by him and by the writers who assume this tactical unit the two vessels act together. As a general thing it was contemplated that the best position for the subordinate vessel was on the quarter of the leader, so that all lines ahead were alternate lines ahead, and all lines abreast were alternate lines abreast. We have said that Mr. Besson believes in the necessity of two vessels acting together, but he differs from all other tacticians as regards the relative position of the two in attack. Believing that the plan of attack should be based upon the use of the ram, he shows that the ships should be *abreast of one another* in order to develop this weapon to its fullest extent, and that therefore the line of battle should be a line abreast. He also goes on to show that any other relative bearing between the two vessels puts one or the other of them at some disadvantage as regards helping its consort.

Admiral Penhoat, in common with most writers now, believes that the fleet should be made up as follows: Two vessels should compose a section; two sections a division; two divisions should form a squadron, and two squadrons a fleet. This would make the fleet composed of sixteen vessels. If there is a less number than sixteen, the squadron must still be composed of eight, and the rest must be over, and be exercised as another division or squadron.

We now come to the consideration of the *group* as a tactical unit. During many years the students of this science were struck with the necessity of so dividing the fleet that the particular qualities of each ship could be given its proper value, and the divisions of the fleet into groups found numerous defenders. Until lately this has been a favorite system, since it was considered to develop in the greatest degree the following points:

1. Each ship's battery was clear.
2. Each ship was considered to be entirely unhampered in its movements as regards ramming.
3. There was the greatest mutual support between ships.

Although the pèloton or group was originally intended as a formation to cruise in solely, and ships moving in this order were without any arrangement, save that one was designated as the leader, still it soon came into prominence as a fighting formation, and was especially favored by the English. In 1868 Captain Semetchkin, of the Russian Navy, was entirely impressed with its usefulness, and in his work on "Naval Tactics" divided the squadron into two divisions, and each division into two groups, composed of three ships each. These groups were either equilateral-triangular or rectangular-triangular, with equal sides, the hypothenuse forming the rear face of the group.

Captain Lewal, of the French Navy, divided the squadron into three groups, each group containing three ships, one being designated as "group leader." Mr. Laughton's plan is nearly identical with this. He makes the basis of fleet division a *squadron* of three vessels, each squadron to have its admiral. He gives as a reason, that each vessel is alongside of his admiral, and therefore in the handiest position to send or receive signals. Besides this the admiral is immediately supported by the ships of his command.

Lieutenant de Penfentenyo, of the French Navy, in his work on "Rams in Battle," says that the tactical unit is a group of three or four armorclads arranged in a triangle or square. He further says that a squadron should contain at least two divisions, and a fleet two squadrons and at least twelve armored ships.

Lieutenant Campbell, speaking upon this point, says that the "evolutionary unit" seems to rest between a group composed of two, three, or four ships. With two ships, one ship should be four points on the quarter of the other, and two cables from it; with three ships, the third ship should be three cables from the second ship and four points on *her* quarter. (See Plate XIII, Fig. 8.) With four ships, the fourth is placed as in the figure.

According to Captain Fremantle, the subordinate vessels of a group should be the handiest and fastest.

Mr. Campbell says, that in a fleet actually organized for war, a group should consist (if the fleet be sufficiently large) of three line-of-battle ships, three tenders, and six torpedo quarter-boats.

Commander Noel also divides the squadron into groups. He adopts the triangular group, which he forms in different ways. (See Plate XIV, Figs. 1, 2, 3 & 4.) He says: "Since, nowadays, fleets are and must be made up of vessels of different powers, and whose parts to play in a fight are essentially different, the group-leader can, being the staunchest, call his consorts under cover." Furthermore, he takes issue with Captain Colomb on the point of the latter's condemnation of the group system for either attack or defense, and gives cases to show that groups can maneuver to pass down the line of an enemy with a narrow front if required, and that they are most mobile for change of formation to ram, and, that in case of collision with the enemy, they will not pile upon one another as they would do if they were in line ahead; also, that if the line *was* broken, re-formation is more feasible with this system.

We may observe right here what may be set down as a maxim : The victory will probably lie with that fleet whose formation will permit it to keep its integrity the longest.

In regard to the number of vessels comprising a group, Captain Fremantle says, "There is no special virtue in the number *three*, and there is no extraordinary strength of formation in the scalene triangle." This most favored grouping in the English service consisted, perhaps consists, of one vessel leading, termed as, by Captain Lewal, the group-leader; a second vessel two points abaft the beam of the first and one cable off, and a third vessel on the other quarter of the first and two cables off. We believe that the English signal-book now permits of great latitude in the use of this system.

Lieutenant Campbell is one of the greatest champions for the group formation, and does not hesitate to say, "I believe that no formation is better adapted to the development of the torpedo, the ram, and the heavy artillery of the present and the future."

Lieutenant Cattori, of the Italian Navy, believes in equilateral-triangular groups, with the groups revolved through 30° about the center of figure. Several of these groups in line abreast have the advantage of the group system and that of line abreast in three lines. (See Plate XIV, Fig. 5.)

We can hardly look upon this formation as anything but *pretty* theoretically, as the formation being so hard to keep would be certain to degenerate either into isolated groups or into a formation in three lines. It is unquestionably clumsy to maneuver in.

Lieutenant Besson says that the result of the drill in the French squadron of evolutions was such as to condemn the group system *in toto*. In speaking of a formation for attack, he remarks that all orders on *lines* of bearing, and particularly the group formation, must be abandoned. "The group formation is the worst of all" are his words. He goes on to say that in the group formation the vessels do not give each other such efficient support as to make up for the clumsiness of their arrangement. Line ahead in groups is a bad cruising order, as the slightest movement of the helm or change of speed may cause a collision. In every case it is difficult to imagine a fleet going into action formed in this way.

At first glance it is very different with line abreast in groups. We see here, in each group vessels can easily change speed; the wing vessels especially can do so without danger of collision. Although the formation may be said to possess all the merits of supplementary lines, still the difficulty is that changes of direction, maintaining the group formation, are well-nigh impossible. This, and from the fact that this arrangement exacts an unanimity of action between ships which is hardly to be brought about, would seem to call for an absolute rejection of the system.

Lieutenant Rivet, M. F., calls attention to the following defects in this system. He says:

> At first glance, the three triangles that can be formed from a group of three vessels seem to fulfill all the requirements of a perfect formation, but when we come to analyze it, we find the length of time that it will take these ships to change the form of their triangles or direction is too long to recommend the group system as a fighting formation.

The most competent authorities are unanimous in condemning it. Each group presents two weak points, one on each flank, where two of the enemy can easily concentrate, as shown in Plate XIV, Fig. 6.

In regard to the fundamental organization and numbering of the fleet in line-of-battle, we lean towards the method given by Admiral Penhoat. The fleet should be considered to be in line abreast, arranged as in Plate XV. The first guide on the right of the line, the second on the left. These act as general guides. There is also a right and left guide to each squadron. These guides will be most particular in regard to speed, course, and mutual bearing. It will be seen that the guides keep half a ship's length ahead of the line; Admiral Penhoat and Admiral Randolph both say that this is as easily done as to keep exactly abreast. When the fleet is in line, the Admiral should signal the direction of the dress.

We favor this method of assigning numbers to the fleet, since it will cover any system of tactical division. (See Plate XV.)

The numbers for the line-of-battle are sixteen, or as many more as needed, up to thirty-six. If the group or division system was used with four to the group, the numbers would run as in the figure. If there were three vessels to the group the numbers would be in the following order: 1, 12, 13, 2, 22, 23, etc. If the section system or combination of two vessels is used, the numbers would run: 1, 12, 2, 22, 3, 32, etc. If the tactical unit was the single vessel, we would still have to use the method of numbering used in the section system, so as to have numbers enough for 16 vessels. It will be seen that the *leader* has always a single number, and that the subordinate vessels have a two-figure number; the *tens* figure telling the number of its section or group, and its *units* figure the number in the section or group. The line-of-battle should first be furnished with numbers, then the reserve, then the look-out squadron, and finally the convoy.

The probabilities are that this system does not furnish numbers enough for all the squadrons of a large fleet unless the group system of assigning numbers is used. The only point to be looked out for is, to have each distinctive squadron numbered on some system. These numbers need not necessarily run from right to left; in fact, the left group or section, most likely, will have the *leader* on the flank, and it is this vessel which should receive the single number.

Formations may be either natural or inverted. They are *natural* when the numbers run in order from an assumed right towards the left (the fleet or squadron being in line abreast), and *inverted* when the squadron has changed course simultaneously sixteen points. The natural order should always be maintained except when forced by circumstances to form in an inverted formation, which should be only as temporary as possible.

It will be understood that each ship has an *invariable* or *distinguishing number*, as explained above, and a *number in line*, which is her number from the ship on the right, the squadrons being in natural order. The ship on the right should be No. 1.

The Admiral should assign himself a number in the line, leaving a tender or some small vessel to take his place, should he see fit not to occupy his billet.

In regard to open and close order, Captain Fremantle says:

> We may remark on the much greater difficulty of keeping anything like a good station when in "open" than in "close order"; and now that "close order" is specially ordered in a fog, it is abundantly clear that it might and should be maintained under all circumstances by night and by day, except in very bad weather.

Mr. Laughton defines "close order" as 150 yards and "very close order" as 100 yards. The general rule, however, in tactics is, that no interval or distance should be made small enough to admit of two vessels fouling in any manner. Admiral Penhoat is of the opinion that the distances and intervals should not be arbitrary, but be laid down with great rigor, and Captain Rivet says that the distances between ships should be two cables, or two-thirds of the diameter of the evolutionary circle.

The distances between vessels in double line abreast should be a little more than in simple line abreast, but should not exceed four cables, or once and one-third the diameter of the evolutionary circle.

The intervals between two lines should be about six cables for a speed of ten knots. Supposing each fleet charges at ten knot's speed, the two will come together at a rate of twenty knots. This rate makes the second line engage the enemy two minutes after the first. This interval ought not to be made smaller.

III.

It is hardly necessary, we take it, to go over the thousand and one modifications of the three or at most four simple formations in which a fleet can be arranged. Nearly every tactician has his favorite methods, differing somewhat from those of other tacticians, to which formations he gives special names, and special rules are laid down to preserve their integrity.

It will perhaps be well, however, to look back twenty years, when broadside fire was the basis of attack, and ships had only moderate speed, and see the multiplicity of formations that were considered to be necessary, then glance at the situation to-day, and observe what simplicity of order is forced upon us by the ram, and by the enormous engine power of ships.

In 1866 there were fifteen simple and compound formations. These were drilled in, and undoubtedly were found to be not only satisfactory but imperatively necessary. To-day, according to Lieutenant Besson, only two simple formations are retained, line ahead and line abreast; and two compound formations, two lines ahead and two lines abreast.

Formations are either simple or compound. Simple formations are line ahead, line abreast, and line of bearing. This last is sometimes termed *échelon*, and when ships are in this formation they bear from one another all the way from two points forward and abaft the beam, relatively, to four points.

Compound formations (see Plates II & III) are those where the simple formation is repeated, as two or more lines ahead, two or more lines abreast. On two lines of bearing making different angles with each other, and known as *chase* and *retreat* formations; squares, which are either lines ahead, lines abreast, or lines of bearing of unequal length, but where the distances and intervals are equal in size and number;

modifications of the square, and the numerous group forms. By some writers, compound formations are confined to designate the group; by others, the group formation is called "special." All this is a mere question in terminology, and we prefer to class as compound all those formations which are not single lines ahead, single lines abreast, and single lines of bearing.

According to some authors, line ahead is too extended for an attacking formation, but it is very useful in going through a narrow channel. The line abreast and the line of bearing take up too much sea in width, and they necessitate changes of direction that are very difficult to make when the enemy is sighted.

These writers either depend on compound formations for combat, or else believe in no regular attacking formation at all.

According to Lieutenant Cattori, of the Italian Navy, the line ahead is only useful in tortuous channels, but in other cruising it is of little or no account. As a fighting formation at sea he says it has no place. Compound lines ahead may answer in cruising in special cases, and it is useful in time of war to force a passage and to enter a harbor under fire. In effect, it is sufficiently concentrated, yet simple to permit change of direction without change of formation. The nature of the defense from the shore would have to determine whether the ships would have to be lashed together or whether the compound lines ahead would be two lines ahead or alternate line ahead. The commander-in-chief, in this case, most authorities agree, should not be in the line. A French tactician says:

> Line ahead is probably the best formation for entering a harbor, even where mines are suspected. If the torpedoes are in a line perpendicular to the line ahead, only one ship would be blown up. If they were more scattered, going in this formation will increase the chances of some of the vessels getting through. Of course a suspected locality should be thoroughly countermined.

Leading into a fight or bearing down on an enemy's position in line ahead has its advantage; it does away in a great measure with the necessity of signaling. Then, it is easier for the captains of the vessels, as they have no dress to keep, but only to maintain their position in the wake of the next ahead. According to Admiral Penhoat, with a small fleet, say of six or eight vessels, the best arrangement is in line ahead in single column, with a distance of two cables between ships. If a vessel must slow for some cause, she should steer out of line. The line-of-battle is most easily formed from this formation by changing direction eight points and then coming into line abreast. (See Plate XVI, Fig. 1.) If the fleet is large, the Admiral recommends bearing down in two parallel lines, which is double line ahead, for the reason that if all the vessels were in one line they could not see the Admiral's signals, and also they would take too long to get into line abreast, which seems to be the favorite formation for attack. Double line ahead can be formed in two ways: the even number may form the second line by falling out to starboard or to port when formed in one single line ahead, or it can be formed from the last half of the fleet. (See Plate XVI, Figs. 2 & 3.)

When the lines are formed in the first manner, and the odd number are in the right-hand line, and the two lines have an interval of about five cables, the formation is an order of battle in two lines abreast, moving by the flank. It is easy to see that a fleet established in this formation can come quickly into the order of battle in two lines perpendicular to the bearing of the enemy.

Admiral Penhoat's advice, then, is that, as a general rule, it is better to have one line even if it is a little long than to have two or more, especially when in the same waters with an enemy. The limit of one line is eight vessels. If there are more than eight, two lines ahead *must* be formed. Change of direction is made without difficulty. In each line ships can drop off on the off side without interfering with each other. The smallest interval between the lines should be greater than the diameter of the evolutionary circle, so that in case a vessel had to drop out on the side nearest the other line, she could turn without danger of collision. This interval should be from four to six cables. The maximum interval between the lines need only be sufficient to let the fleet form line abreast on a line of bearing eight points from the old course.

It is difficult to bear down on the enemy in any spread-out formation, and preserve the stations of the vessels. If in bearing down, the enemy shifted his bearing to the right or left, he can often be kept in front by changing the course without changing the formation or the absolute bearing of the lines. In steaming in line abreast, the captains of each ship must preserve for their vessels—

1. The course.
2. The bearing.
3. Their station in the line.

Each ship's compass should be perfectly adjusted, or its errors must be exactly known. This is most important. Chiefs of divisions are guides for their divisions, and they should keep themselves just a little ahead of the alignment when the fleet is in line abreast.

From Lieutenant Farret we learn that simple line abreast only answers as a cruising formation for a limited number of ships; as an attacking formation in the opinion of some it is too extended even with a fleet of ten ships, and the flanks are without protection. This bad quality does not apply, however, to line abreast in two or more lines, and although this is not properly a good cruising order, it is, according to Lieutenant Cattori, an excellent formation when advancing upon or when feeling an enemy. It also answers in many cases as a fighting formation.

Captain Rivet has the following to say about simple line abreast:

> As a cruising formation it is not good; especially is it bad at night. As a formation for attack with rams it is good; for artillery fire it is bad. Any compound line abreast is better than the simple formation. Alternate line abreast, with the distance and intervals as small as possible, is the best arrangement of this formation.

Admiral Randolph has the following remarks to make on the bow and quater-line, or a formation in the ordinary *échelon*. "It is," he says, "hard to preserve; the opportunities, however, for using the battery are very good. It is not the most efficient for mutual protection from ramming, as the sternmost of two ships receives none from her bow neighbor, and the leader of two not the utmost possible from her quarter neighbor. Furthermore, it is not a good formation for ordinary steaming as it is hard to maintain your station, and is difficult to change direction in, although it permits great liberty of movement of the vessels themselves."

We now present the views of Mr. Laughton in regard to fleet formation for attack. He is of the opinion that the fleet could best be formed on a modification of the "naval square" (*carré naval*) of Admiral Count Bouet-Willaumez. The French formation is limited to nine vessels. If this number is maintained, it will be seen that the formation is not only strong, but presents the same shape, no matter how the vessels head. Of his special formation (see Plate XVI, Fig. 4) he says he believes that there would be all the necessary advantages of the square in the formation he suggests, and that every movement could be performed under one general signal, "change front (so many) points to starboard (or port)."

Groups are not necessarily triangular. Some writers believe that each group should be exercised as a squadron, but that the leaders should always be in one of the simple formations; the distance to be sufficiently great between the leaders as to prevent any interfering between the groups. Although this system certainly aims at keeping up a squadron integrity for a longer time than any other, still the maneuvering of even two groups together will be found to be very awkward, take up too much time, and the vessels, during the evolutions, could not give one another sufficient support if attacked at this time.

In Plate XVII, Fig. 1, we give several forms in which groups can be, and the tactician, who recommends them, explains their uses as follows:

1. The equilateral triangle, for ramming or as a cruising formation.
2. The group on a line of bearing. For flanking an enemy; for defense against an attack by ramming, and sometimes as a formation for attack.
3. The group for evolution or for using the battery.
4. Group in line ahead.
5. Group in line abreast.

In regard to special formations, Admiral Randolph favors a line of bearing in which the ships are in *échelon* of not more than a point forward and abaft the beam. (See Plate XVII, Fig. 2.) Such a formation, he says, is as easy to maintain as line abreast. In this formation Admiral Randolph claims:

1. The fire is left clear.
2. The closest order is maintained.
3. It gives the maximum of mutual protection.
4. It is a rapidly formed formation and can be deferred to the last moment, and thus mask the intention from the enemy.

The distance between the ships is set down as one and one-half to one and three-quarter cables.

Some tacticians divide formations for cruising into those to be followed in time of peace and to those applicable to a period of hostilities. Captain Attylmayr, of the Austrian Navy, believes that in time of war the best cruising formation is in line ahead in groups, and in time of peace line ahead, either single or double, chase formation, or the square. Mr. Besson, however, is of the opinion that for all purposes of cruising, line ahead in divisions is the very best for squadrons; that is, the squadron is in two lines ahead. From it the line-of-battle can be most easily formed. The Admiral can see all his ships and be seen of all; the squadron is compact, and the tenders on the wings can easily keep it advised of the approach of the enemy. When cruising the place of the Admiral is leading one of the lines.

Cruising in route formation consists in dividing the fleet into sections of two vessels, or groups of three vessels, and each section or group governing itself as a little squadron, all steering the same course, set by the commander-in-chief, and each section or group maintaining proper signal distance with him. This system is excellent for a long run, as, for instance, crossing the Atlantic. The Admiral should furnish his captains with a list of several rendezvous, and assign certain dates when these rendezvous would expire.

Lieutenant Farret says that the groups first used in the French Navy were in the form of an equilateral triangle.. This formation was:

> Not for fighting purposes, but as an habitual order of navigation, so as to take the place of lines of ships in each other's wake; an order compromising for steamships, especially at night.

The equilateral-triangular group became usual later as a "*peloton de combat.*" For a strange fact, Commander Noel puts *his* groups in such a position during the night that the squadron is virtually in line ahead.

It would seem that a good night formation would be line ahead in two columns or lines. Each column should not contain more than six vessels, better still if there were only four. In time of peace, or away from the enemy, the leader of each line should use the forward electric light to illuminate the fore part of the leader of the other line, and the after electric light to illuminate the fore part of the rear ship in the other line. (See Plate XVII, Fig. 3.) If the officer of the deck of either of the leaders, or of the rear ships, draws into the glare of the lights of the leader of the other line, he will know that he is drawing ahead of his station.

When convoying, the convoy squadron should be so distributed that the heavier ships during the day should cruise in chase formation with the lighter vessels, acting as "whippers-in," keeping the convoy well within the angle. There should be tenders to act as skirmishers ahead, on the flanks, and a swift one to cruise astern. During the night the convoy squadron should separate and cruise on the flanks. If the convoy is large it should be divided.

Although massed or in square is not in good formation for fighting it is a most excellent one for reconnaissance; probably the very best for a small number of ships.

Fighting formations all come within one of the four following categories:

1. Narrow front—great depth.
2. Extended front—slight depth.
3. Front and depth equal.
4. Groups.

The first category is represented by line ahead; the second, by lines abreast, chase and retreat formations; the third, by the square, and the fourth, by every formation that may be included in the group system.

A good order of combat demands the arrival of all the vessels as near together as possible on that point of the enemy's formation where the attack is made. It also must possess the following qualities:

1. It must be easy to keep.
2. It must be easy to re-form in.
3. It must lend itself, by its flexibility, to all the combinations required by the Admiral.
4. The vessels composing it must be so disposed as to give one another the maximum of mutual support.
5. The vessels must be able to use all their warlike outfit, which includes helm and speed power; the use of their rams, guns, and torpedoes.

Some authors do not believe in a fundamental formation for battle, but think that any formation in which the fleet presents the bow to the enemy may be taken as an order of attack.

Admiral Penhoat says that vessels composing the line-of-battle must steer the same course, or they will run the risk of collision. In his opinion, if the plan of action is based upon artillery, the best formation is simple line ahead, steering a course as nearly as possible a right angles to the direction in which the enemy bears; otherwise the broadside guns could not be used.

Even with the ram as a basis of attack, some authors prefer a line ahead on a course perpendicular to the line of formation of the enemy. Their reasons being: first, that each ship in line ahead can as it cuts the enemy's line use both broadsides; and, secondly, the rear vessel of the line can, without interfering with the other vessels, take advantage of the *mêlée* by the time it reaches the enemy's line, and use its ram to advantage. They consider, in making this departure from rather well-established ideas, that vessels nowadays have such great speed, and that artillery, from its size, must be so slowly served, the leader of the line ahead will not be punished so badly as formerly. Another advantage of this formation for attack is, that the rear vessels are protected, the strongest and most formidable ships leading into action.

Mr. Besson says that line ahead is the easiest to keep or to reassemble in. It is perfectly flexible, and can in a few minutes change to any direction. Each vessel is flanked by the next astern which can come up on either side. The vessels being in the wake of one another must maintain the same speed, it is true, but by sheering to either side any vessel can take up any speed, or use its turning power in any way. The artillery fire, for the broadside, is entirely unobstructed, but the ram, the bow and stern fire, and the torpedoes are certainly put out of action, but by a slight sheer out of the line any or all of these weapons are called into play.

This formation fulfills all the requirements of a good fighting order.

In line ahead, in close order, the vessels flanking each other mutually, and their broadsides protected by auto-mobile torpedoes, the formation should be nearly impenetrable. The last ship in the line is the only exposed one, and she should be endowed with excellent turning qualities.

The line ahead presents, according to circumstances, either the bow or the broadside to the enemy. At a distance, using artillery, this formation is most efficient with a broadside presentation. It would be foolish to engage the enemy broadside to, near at hand, as the fleet would be too much exposed to the enemy's rams and torpedoes.

Captain Grillo, of the Italian Navy, adopts, as an order of battle, the line ahead steaming at right angles to the enemy's front. The formation should be kept up as long as possible. He re-enforces the head of the line with the reserve division, and the rear of his line with rams or ram-bowed cruisers. (See Plate XVII, Fig. 4.)

On the other hand, Admiral Randolph expresses the opinion that the line ahead is a bad attacking formation, for the reason that only the leader can ram, all the guns of the fleet are not used, and because the ships do not mutually support one another to any degree. He says, "It is fraught with the maximum of danger."

Mr. Laughton remarks, "The best professional opinion refuses to admit the line ahead as an attacking formation."

The formation in alternate lines ahead, according to this writer, is free from the defects of the single line, but it is still too extended. A concentrated attack on the rear might inflict fatal damage on one or two ships, before the van could come round to their assistance, supposing that the enemy's formation had been penetrated by a portion of your line.

The alternate line ahead, however, has certain advantages. It is powerful as regards fighting the battery, and permits vessels of the second line to ram vessels of the enemy penetrating the first. Another author says that a formation in alternate line ahead permits a squadron to preserve a good battery front. It is a formation hard to break through and has little to fear from rams. It has the drawback of not being flexible.

The majority of tacticians are of the opinion that the most reliable formation for attack based upon the ram is founded on the line abreast; still it has several alleged disadvantages, which are as follows:

1. It is hard to preserve the dress of the vessels.

2. It is so extended as to favor concentrated attacks of the enemy anywhere on the line.

3. The Admiral's signals will be hard to make out by vessels on the flank.

4. The flanks are unprotected.

5. It precludes broadside fire, except from the wing ships, which are unsupported.

6. It is not flexible. Changes of direction require long and difficult conversions.

7. It is the easiest formation to break through and to break up, if the enemy, in one or two columns, concentrates every effort on one point.

These disadvantages are discussed by Mr. Besson, and some disappear under the light he throws upon them; for instance, it will be shown later, in discussing the "Fleet in action on the open sea," that the broadside fire *can* be used, without endangering the other vessels of the fleet, at least at any period subsequent to the first charge.

In regard to this formation not being flexible, it is thought that if this order was formed just a little while before it was needed this inconvenience would disappear.

Mr. Besson calls into question some of the charges made against it, and says that if there are no more than eight ships in line, the formation, being simple, is consequently easy to maintain and to retake, and, furthermore, in it, the vessels mutually give one another the maximum of support. It is considered at the present day the best attacking formation for rams by the French writers, and by many foreign ones.

In regard to exercising in this formation, the rule is laid down that the vessels should be the radius of a turning cricle apart. Each vessel then has control of its engine and helm, and may be said to be unobstructed in its movements. The torpedo and ram can be perfectly used, likewise the bow and stern fire.

Vice-Admiral Bourgois and Lieutenant de Penfentenyo believe that the attack should be made in line abreast, but that after the first charge the formation will disappear; Admiral Bourgois believing after that instant each vessel will act for itself, while Mr. de Penfentenyo advances the opinion that the fleet should form groups, and lays down rules for so doing.

Mr. Besson says that two lines abreast, either double or alternate line abreast, is preferable to single line abreast. It has the merit of concentration and mutual support. The heaviest ships should be placed in the front line, although they may be hampered in the use of their rams and torpedoes, to some extent. In this formation there is this drawback, that it is hard to change the vessel's course sixteen points, which must be done after passing through the enemy's line, to charge him again on account of possible collisions with vessels in the second line.

Admiral Penhoat acknowledges that this is a hard formation to keep in, but he says that its disadvantages are few, and that any error in dress is easily rectified, agreeing, as we see, with Mr. Besson on this point.

Captain Fremantle is of the opinion that if there are many ships, the fleet should be divided into independent squadrons, but preserving for each squadron the formation of alternate line abreast. On the other hand, when your fleet is so small as to allow the enemy's line to overlap your flanks, when formed in this manner, Mr. Besson says that you must not fight in this formation, but in *single* line abreast.

Captain Attylmayr does not believe in the double or alternate lines abreast, and says that it should be entirely discarded as an attacking formation.

According to Captain Grillo, in attacking this formation with a fleet formed in line ahead, the rear vessels of your line ahead should be ordered to reserve their fire for the rear line of the enemy's two lines abreast.

The great drawback to the formation in square is that stations cannot be maintained at good speed.

Formations *in échelon* present to the enemy a line of rams and a line of fire. Yet it is a dangerously bad formation if it is attacked in direction of its line of bearing, as it is not flexible. An angular formation, such as a chase formation, permits the use of only one broadside on the enemy; moreover, it is a hard formation to maintain, and an attack from rams is liable to get it into confusion. Although a formation in chase-angle gained for the Austrians the battle of Lissa, its disadvantage is in changing direction. The point of the angle must be kept towards the enemy, otherwise the enemy will concentrate on one of the flanks. Owing to its unhandiness as a general formation for attack, it is not to be recommended. In fact the most modern tacticians condemn it entirely as too clumsy. Unless the enemy, in some simple formation, was very badly managed he could turn so that he could always avoid the point, and could thereby flank the fleet.

Captain Werner, of the German Navy, in 1873 said, that "all modern systems must look to the ram as the main weapon, and all formations should have this end in view, and should try and combine as many rams as possible on the enemy at the point attacked. To do this the fighting formation should be such a one as to remain intact and be compact as long as possible, and at the same time to permit of great mobility. The group system of three vessels is the only one which satisfies these conditions. It is easily managed and can be rapidly formed again on dispersion." Captain Werner believes in the right-angled triangular group, hypothenuse to the rear. Other friends of this system argue for the scalene triangle, since the rear vessel has an excellent chance to ram. They all believe that after the fight commences every group should be under the sole control of its leader.

Lieutenant Campbell arranges his groups in a manner that has the advantages of the unity of the group system, and the defense and support accredited to the double or treble line abreast. (See Plate XVII, Fig. 5.)

Line ahead by groups, in one or two lines, appears to Lieutenant Algranati to fill all the conditions of an excellent order of attack. The first or second charge will break up any elaborate formation, and the groups will probably hold on longer to their identity than ships in any other formation. The leading groups should be formed with the most formidable armor-clads. The rear group, which has the best chance to ram, should be composed of those vessels best qualified for this work.

Vice-Admiral Randolph examines, in his work on tactics, the different formations that a squadron can take to attack, and he proposes an order in *échelon* on a line of bearing not greater than one and a half points forward or abaft the beam. He applies this formation to eight armor-clads divided into divisions, and he places them on two lines of bearing, but one line is the inverse of the bearing of the other. They are formed something like a retreat formation. (See Plate XVII, Fig. 6.) After the first penetration of the enemy's line, the order of cohesion ought to be kept up until the squadron has executed the plan of battle of the admiral. After this the greatest liberty of action is left to the captains.

An authority who favors this system of Admiral Randolph says—

> We think that it will be always wiser and more advantageous to keep together all the forces in a compact mass than to divide them into isolated groups. If the aim of strategy is to deceive the enemy to the last moment, to hide from him the method of attack, we believe that this result can only be brought about by rapidly moving the squadron *en masse*. We conceive this can best be done by using some flexible preparatory formation, and then moving in some preconcerted manner, as contemplated by Admiral Randolph.

The retreat formation as a formation for retreat or otherwise has few friends, and may now be considered obsolete. Any spread-out formation, such as this is, is bad. In retreating the best formation is probably in lines ahead, with the least-injured ships nearest the enemy. Authors who recommend spread-out formations to serve this purpose forget the following considerations: A spread-out order supposes that all the vessels can steam without assistance, and are still in a condition to fight. This hypothesis is not tenable, for a fleet would retreat fighting, and only after a reverse or failure. On its face a spread-out order permits an enemy with superior speed to concentrate its force on some point of the fleet in retreat, and destroy it.

In alternate lines ahead the formation is more concentrated and cohesive. Every gun is capable of being used against the enemy. Stations are easily kept, and the towed vessels are well protected. Finally, there are no complicated maneuvers. So this formation is the best for disabled vessels in retreat, as they can be taken in under the guns of their own fortifications, or can enter their ports without any evolution, save changing direction.

Possibly there is one condition where retreat formation may be available; that is, when fighting in a comparatively narrow channel, there is danger of being attacked by the enemy's fleet.

CHAPTER VIII.

EVOLUTIONS OF THE FLEET.

I.

Evolutions in naval tactics have for their object the assembling of formations and the passing from one formation to another. They must satisfy the following requirements:

1. They should be done in the least possible time.
2. They should be spread out as little as possible.

There are three methods of evolution; those controlled by—

1. Simultaneous movements.
2. Successive movements.
3. Direct or oblique movements.

It will be seen further on that some tacticians draw a line between *direct* and *oblique* movements; others consider this extreme delicacy of division to be unnecessary.

The tactician should study these fundamental movements thoroughly, so as to decide *without hesitation* which method fits the case best. It will be seen that some evolutions require a combination of all three of these methods.

Evolutions are not tactics, although they form the basis on which tactics are founded. Captain Fremantle says, "they are simply fleet drill, and the signal-book is the drill-book."

In all evolutions performed by a fleet at sea in the presence of an enemy, the one important point is that they should be quickly understood by the commanding officers of the ships composing the fleet. To attain this very desirable result, it is necessary, according to Lieutenant Campbell—

1. That the signals should be as few in number as possible.
2. That the explanation attached to each signal should be as explicit and concise as possible.
3. That the officers of the Navy should be instructed in the manner of performing the maneuvers as early in their career as possible.

Since changes in naval warfare are constantly rendering changes in ships necessary, changes in ships bring about changes in evolutions and also in the manner of performing them. These changes necessitate changes in the signal-book.

The knowledge of the helm, the speed of the ship, and the elements of the turning circle, certainly furnish the basis for all evolutions. There will be some difficulty in maneuvering a fleet composed of vessels varying greatly in speed, turning power, and armament, so as to develop the special qualities of each ship; therefore it may be set down as a maxim that the actual capabilities of the worst of the vessels comprising a fleet must be taken as the representative capability of such fleet. So that the maximum speed of the slowest ship is effectively the maximum speed of the fleet, and the circle of the ship which describes the largest, is, effectively, the circle on which every vessel in the fleet has to maneuver.

It seems, therefore, to follow that the power of a fleet as a fighting unit may be improved by the rejection of those vessels whose power of maneuvering is bad. Mr. Laughton says: "Ships so ejected might form a reserve to act in time of battle, independent of the formation of the main body."

It must be borne in mind that a surprise to a fleet by an enemy has ever been dangerous; but with our modern means of warfare it will certainly prove disastrous. This being the case, it will require great foresight on the part of a commander-in-chief to have his fleet in such a condition, as regards formation, that it will not be necessary to perform any evolution of moment in the presence of the enemy. Should it become necessary, however, under these circumstances, to maneuver the fleet in order to form to resist attack, such an evolution must be performed by ***ships***, according to Admiral Penhoat, and not by ***groups***; as by this latter system the fleet will be spread out, and a concentration on a portion of it by the enemy will be easier. The Admiral goes on to say that—

> If the form and organization of the line-of-battle are well determined, it will be easy to deduce the proper formation for steaming and to establish in some way a proper system of evolutions. These evolutions, above all, must be simple.

It may be laid down as a general principle that no evolution is of merit which employs such a method, to pass from one formation to another, as breaks up the mutual support which should exist, in all good tactics, between the ships of the fleet.

After preparatory exercise, so as to permit the captains to familiarize themselves with the handling of their ships, the fleet should be formed in line and exercises should begin. We have before discussed the principles by which the speed and position are maintained, and have given forms of the tables to be used.

The fleet must drill at making together two turns of 90° each; one turn with the helm one way, and the other with the helm over the other way. The turns to be made at full speed and to be continuous. (See Plate XVIII, Fig. 1.)

Drill in change of speed can be done as follows: The fleet being on a line of bearing four points on the Admiral's quarter, for example, and on the same course as the flagship, will, at the signal, come into line abreast, dressing on the flagship. Then the moving flank will be changed, and the same movements will be repeated, pivoting on the ship on the other extremity of the line. The ships always steering parallel courses.

Night drill is simplified by the improved methods of electric lighting. It certainly takes more nerve to drill in darkness, but it is most necessary, and the Admiral should constantly exercise his fleet at this time.

In regard to intervals, the general rule is to close them when the formation is accomplished, and to open them out before beginning to form a new one.

Owing to the reduction in speed caused by turning, vessels changing direction in line ahead in close order will be likely to collide with the next ahead. Distances then must be great enough to permit vessels to turn without being run into.

The following instructions taken from the "Manuel du Matelot Timonier (Paris, 1882)" are extracted from the first volume of the Naval Tactics of the French Navy:

GENERAL PRINCIPLES FOR SQUADRON STEAMING.

Every vessel which increases or diminishes its speed must communicate the fact to the next ahead and the next astern.

This rule not only applies to formations and to evolutions, but to every circumstance where vessels maneuver in proximity to any others. It is shown by hoisting the speed pendant higher when the speed is increased, and lowering it when the speed is diminished. At night a lantern is waved over the bow, to be answered by the next ahead, when the speed is increased, and if the speed is diminished, the lantern is waved over the stern, to be answered by the next astern.

The only circumstances under which a vessel is authorized to stop, when steaming in squadron, are the following:

1. To save a man overboard.
2. In case of an accident to the engine, screw, or rudder.
3. To avoid a collision.

In almost every case the vessel which stops should drop out of line, by sheering to that side which interferes with the other vessels the least.

II.

In any movement made by a fleet in performing an evolution, there are the following requirements to be fulfilled:

1. To lose as little distance as possible in passing from one point to another.
2. To avoid any possibility of collision between two or more ships of the fleet.
3. To keep the fleet in such a condition as to form order-of-battle easily and quickly.

We may also state that the nature of all movements of a line-of-battle presents three phases:

1. To approach the enemy—bow towards him.
2. To keep at a certain distance from the enemy—broadside towards him.

3. To retreat, or increase the distance from the enemy—stern towards him.

We have said in the first part of this chapter that movements may be classed under the head of simultaneous, successive, and direct.

SIMULTANEOUS MOVEMENTS are those performed by all the ships of the fleet, which are steering the same course, coming together on some other common course.

SUCCESSIVE MOVEMENTS are those which are performed by means of the *countermarch*. This method consists in putting the fleet into line ahead. The leader steams in the new direction, followed by the other vessels. The advantage is that it requires no signals, the quickest speed is maintained, and there is little or no danger of collision. Furthermore, a countermarch is applicable to any number of vessels, whereas, a *wheel in a concentric circle*, which is intended to accomplish the same object as a countermarch, can be undertaken by only a very small number of ships. since the greater the radius of turn for the fleet or squadron in line abreast, the greater the speed to be made by the moving flank ship. With more than five ships in line, the flank ship would have to make greater speed than vessels are generally capable of doing. There is a method called by the French *conversion*, which is intended to accomplish the same object as the wheel or countermarch, and which is a combination of the simultaneous movement and the direct movement. This method will be further discussed at another point in this chapter.

When the movements refer to changes of direction of eight points by means of a successive movement, they are termed "rectangular movements," and evolutions performed by this method furnish the basis of a regular school of tactics. There is another method of performing rectangular movements, now practiced in the French evolutionary squadron, we believe, which resembles the *isodromic* method of Captain Lewal, which will be touched upon later.

Without discussing *all* the plans, methods, and means of evolution suggested in the last twenty years, we will say the great speed that ships are now capable of, and at which all evolutions must be performed, entail upon these evolutions the greatest possible simplicity. Therefore it may be laid down as a general rule, that where direction is to be changed without changing the formation, if the angular difference between the new and old line of bearing is less than four points, and if the fleet is in line abreast and not very large as regards numbers, then wheeling in concentric circle or conversion should be resorted to. If, however, the change is greater than four points, then the evolution will be performed either by a simultaneous movement into line ahead, followed by a countermarch, and then again swinging simultaneously to some common course, or the evolution will be performed by a DIRECT MOVEMENT. A direct movement is where each vessel proceeds from her place in the old formation to her place in the new, at the quickest speed, by the shortest route, without reference to the other vessels of the fleet. Since one of the vessels of the fleet is formed upon in all direct movements, and since vessels arrive in their new positions at different times, changes of speed are necessitated. Simultaneous and successive movements, then, have this advantage over direct movements: full speed can be maintained at all times.

Although at first glance the direct method may seem to be the easiest to maneuver in, it is not so. Unless the fleet is very well drilled, there is great danger of collision; and, moreover, the vessels in passing from one point to the other are in no formation and are therefore at a disadvantage in case of attack.

Captain Fremantle thinks that it is "wise to prescribe as closely as possible to each captain the course to be followed." He also thinks that there will never be an attempt made to change a formation when in action, since such change will act too disadvantageously for the fleet in the manner we have spoken of. Furthermore, he says: "Rectangular movements, which allow changes of formation to be made without variation of speed, are correct."

Many authors, however, do not believe that rectangular movements are applicable to a fleet of armored vessels, into which fighting by means of the ram enters. They believe in direct movements, which, as we have before said, contemplate a vessel proceeding from one position in a formation to some other position in some other formation by any route her captain may chose, observing the usual rules of the road.

Some writers favor the use of both systems, the admiral to be governed by the environment as to which method he will use. Each of them, however, have their drawbacks. With rectangular movements, if we are maneuvering in the presence of the enemy, our broadsides are exposed to his line of rams; with direct movements collisions are liable to occur, and the fleet is without order until the new formation is complete.

An advantage with rectangular movements is that it takes less time to perform the evolution, and the location of the new formation is exactly known; that is to say, the commander-in-chief, supposing him to be in the leading ship, passes exactly over the spot of the new line of bearing; whereas with direct movements it is not so. For instance, the fleet are in line ahead, and they wish to form line abreast on the leader, on a line of bearing eight points from their present line. As the leader must keep up his steerage way, although at a reduced speed, say four knots, the consequence is that by the time the fleet are in line abreast the formation is accomplished two or three miles ahead of where the leader was when the evolution commenced.

With the great speed that vessels will maneuver at nowadays, it may be set down as a maxim, that, if an enemy's fleet should be discovered less than four miles off, and your formation was in line ahead in direction of the enemy's bearing, and you wished to form line abreast, or some modification of it, you must use a rectangular, and not a direct movement; otherwise the enemy will be upon you before your formation is complete.

A point in favor of direct movements is, that ships performing this evolution always present their bows to the enemy, which, in this age of ram warfare, is of great moment.

III.

It is our intention now to consider several systems proposed by tacticians for the performance of evolutions. Many of the methods presented are perhaps antiquated, still they are so often referred to by later writers that it will be as well for us to make some little examination into them.

We have seen that Mr. Laughton divides his fleet into groups of three; each group he terms a squadron, and each leader is the flagship of a rear-admiral. His method of evolutions consists in putting his squadron into line ahead, and using a successive movement, or in putting each squadron into line abreast, and making a wheel in a "concentric circle" through eight or sixteen points. To these are added simultaneous movements, which may be considered as entering into the scheme of evolutions of every tactican. Mr. Laughton also bases his evolutions upon a time element so that a ship, for instance, in a formation in line ahead in close order puts over her helm at a certain time-interval after she has received a signal from her next ahead. When this last ship puts over her helm she signals the fact to her next astern, &c.

The author describes his method of performing concentric circles, as follows:

> At a reduced speed of three knots, the pivot ship describes the arc of her circle through the required change of bearing; the center ship describes the same arc with a double radius, at a speed of six knots, and the third ship with a treble radius, and a speed of nine knots, thus "wheeling" into line on the required bearing.

We have here a simultaneous-direct movement, but with two new elements; helm angle different for each ship and different speeds.

Commander Noel adopts groups, as units, performing rectangular movements. That is to say, all movements made by groups are to be considered, when maneuvering in fleet formation, as if the groups were each a single vessel. Among the vessels of the groups themselves the movements are *not rectangular*, and are made at different speeds. The speed of the group-leader, however, is never changed; always being the highest adopted speed of the fleet. The movements of the fleet are, nevertheless, rectangular when passing from one distinct formation to another.

Captain Fremantle remarks substantially as follows, on this point: The difficulty of evolutions in groups consists in this: The ships of a group must maintain both their relative and absolute bearings—that is, when the course is changed, the whole group have to swing into their new positions as ships forming on their group leaders in order to keep up the formation. This involves so many difficulties, as change of speed, &c., that all advantage of the group of three ships is lost by its unhandiness.

Vice-Admiral Jurien de la Gravière, who commanded the French fleet of evolutions in 1868–'70, chose the division as the tactical unit, and had the following ideas upon some tactical questions. He did not believe in any fundamental formation for attack. The battle having once begun, the captains must fight the ships without any special direction from the Admiral. Furthermore he did not believe that rectangular movements were suitable for armor-clads, and therefore he substituted those which were direct. Every vessel proceeded to her station as we have before described, and for which maneuver an expression was invented, or at least a phrase was applied, namely, that each vessel should "*chasser son poste.*"

Admiral Boutakov takes as a point of departure for his evolutionary system, the idea that every evolution of a vessel is formulated upon two geometrical lines: the circle, and a line tangent to it. Considering the vessel to be moving, if the helm is put over she describes a curve, which may be taken as a circle, and if the helm is righted she describes a line which is tangent to this circle.

The radius of the turning circle used by the squadron is the basis of all measurements, and everything is laid down with the greatest precision. He contrived a series of co-ordinates, so that the ship at any movement of its evolution could be plotted mathematically. Probably it is more theoretical than practical, for although each captain is furnished with minute *data* as regards engine and helm, still the author supplements these instructions by advising the commanding officers that they must be governed also by surrounding circumstances, and that they should preserve their stations by viewing the situation rather than by a blind following of theory.

The Admiral indicates several methods of changing the direction of a line ahead. Some are made by countermarching and some are made by conversion. This last evolution is made in three movements.

Wishing to change direction eight points, being in line ahead—

1. All the ships together put over their helms and swing to a line-of-bearing parallel to the course in line ahead. The angle which the head of each ship swings through is always once and a half, the change of direction of the lines of bearing. (See A, Plate XVIII, Fig. 2.) In this case the ship's head has changed course through twelve points.

2. Each vessel proceeds at different speeds, the pivot vessel just turning over, the flank vessel moving at full speed, dressing on the pivot ship, until the line of bearing is changed eight points. (See B, same plate and figure), when;

3. Each vessel puts its helm over simultaneously, and swings into line ahead. (See C, same plate and figure.)

Of course, the new direction MC may make any other angle than a right angle with the old line ahead NM. It will be noticed that by this method the rear ship is formed upon.

To change direction in line abreast (see Plate XVIII, Fig. 3), either pass to the formation of line ahead by simultaneously putting over the helm, then letting the leader steam in the new direction, the rest of the fleet following, the one in the wake of the other, and when the last ship has gained the new direction, having the fleet swing into line abreast simultaneously; or else, the fleet can proceed as follows (see Plate XVIII, Fig. 4): The vessels together swing through half the angle between the old direction and the new, the pivot vessel barely turning over, the flank vessel at full speed. When the line-of-bearing at right angles to new direction is reached, the fleet comes simultaneously to the new course and renews the normal speed. This second method is only to be used when the change of direction is less than five points.

When the fleet is in bow and quarter line and wishes to change direction it must first come into line abreast or into line ahead, and then proceed by the rules given above.

The author has a method of opening order and increasing distance by means of *sheering*. This plan is hardly feasible at night, and has given way to other and simpler methods.

Captain Colomb's method of evolutions as set forth in his work in 1865, resembles somewhat that of Admiral Boutakov. He assumes that the vessel describes a circle in turning and a tangent to this circle when the helm is righted. He calls "simple evolutions" those performed by *either* change of speed or use of helm; and, "compound evolutions" those in which *both* change of speed and use of helm enter. He only allows change of speed when he prescribes the direct method of movement. A compound movement is a combination of several simple ones. At the end of each simple movement, the alignment is rectified. The author discusses several methods of changing the direction of a line ahead, one of which is by *wheeling in concentric circles.* All the vessels swing through eight points together, coming into line abreast. The pivot vessel then puts its helm at such an angle as to describe the arc of a circle with a radius of two cables; the vessel next to the pivot puts its helm at such an angle as to make the radius of the arc of its circle four cables and so on, increasing the diameter of the turning circles two cables for each ship towards the moving flank. The pivot barely keeps steerage way. The wing ship goes at full speed, the fleet keep their alignment. When they come into line abreast on the new line of bearing, the vessels' helms are put over the same way together, and the fleet comes into line ahead, resuming full speed when the helms are put over. (See Plate XIX, Fig. 3.)

The two methods by which the bearing of a line can be changed, but where the course still remains the same, are formulated by the author as follows:

1. By using the system of co-ordinates proposed by Admiral Boutakov, or—

2. By using the method of wheeling in concentric circles, or the countermarch to get on to the new line-of-training, and then coming to the old course by a simultaneous movement.

We will now consider a last example to show Captain Colomb's methods. Being in double line ahead, by divisions and wishing to change both course and line-of-bearing (see Plate XIX, Fig. 1), he proceeds as follows: If the change is less than eight points, the outside division continues its course, and keeps its speed. The inside division (the pivot division) continues its course and diminishes its speed. The file leader of this pivot division lets the file leader of the other division pass him by a bearing equal to half the angle of the change of direction. At this instant both leaders come on the new line of bearing, followed by the ships of their line. The pivot division continuing at reduced speed until the other division bears perpendicular to the course steered. If the change is greater than eight points, then the division towards which the turn is made (see Plate XIX, Fig. 2) stands on the same course at full speed; the other division stands on the same course with reduced speed, until the file leader of the quick steaming division bears from the leader of the slow steaming division, half the angular difference between the old and new directions, when each leader maneuvers, as in the former case, followed by the ships of their lines. It will be observed that the left division has become the right one and *vice versa.*

We make our next note upon a system of evolutions proposed by Captain Lewal. It consists in moving the fleet from one formation to another by means of *isodromy*, or "paths of equal length." The method is easy to be seen by reference to Plate XX, Fig. 1. It has the disadvantage of there being practically a great liability of collisions occurring. It will be observed that each ship has passed over a course of the same length, and that the same speed is maintained by each ship. This evolutionary system, or something nearly akin to it, is recommended by Mr. Besson. We are led to infer that this method is now being used, or has been used until lately, by the French squadron of evolutions.

M. de Penfentenyo discusses the movements between the vessels composing groups, so that the leaders can maneuver either by rectangular or direct methods, whilst the duration of the evolution is shortened by the vessels of each group moving among themselves. This author used a line abreast as the basis of formation, the group of three being the unit of division. When the fleet maneuvers, the groups arrange themselves in scalene-triangular form; but the leaders of the groups are always in some simple formation. He maneuvers the vessels of his groups as follows; in changing direction two methods are used:

1. When the change is less than 60°.

2. When the change is greater than 60°.

In the first category the positions of the ships do not change; the leader remains ahead. The vessels on his quarters move in such a manner that each ship brings itself to bear half the angular change with the new course, the ship on the starboard quarter slacking speed if changing course to starboard, the vessel on the port quarter increasing hers. (See Plate XX, Fig. 2.)

If the change of direction is more than 60°, the three vessels come together on the new course at the same time. The vessel that finds itself *leading* in the new direction becomes *the leader;* the two other ships so use their speed and helm as to group themselves as shown in Plate XX, Figs. 3 & 4.

When a change of 16 points is made, the triangle is reversed by the method shown in Plate XX, Fig. 5.

We now come to consider the evolutionary system of Admiral Penhoat. He is very minute in his discussion of evolutionary points, and it is to be regretted that his most interesting instruction cannot be more fully entered into in these pages. Both the successive and direct systems are used by him. As regards simultaneous movements, he says:

> Theoretically, in these movements every ship puts its helm over in the same direction at the same time; practically, the ship that has no vessel on the side towards which she turns should commence—as, for instance, the rear ship in line ahead; as soon as the maneuver is marked, then the next ship to her, and so on.

The signal for the execution of any evolution may be given by the steam-whistle of the flagship, as well as by hauling down the hoist of flags.

Simultaneous movement is the only method which can be used in action.

Successive movements relate to the maneuvers of a line ahead, when one vessel keeps its station at all times in the wake of another, its next ahead, no matter what change of direction is made. In changing direction, which in successive movement is for each ship only a change of course, each ship moves her helm over easily. (See Plate XX, Fig. 6.)

In regard to direct movements, this expression designates, as we have said, a maneuver of a line which passes from one formation to another by each vessel steering directly for its new position; for example, being in line ahead, to form line abreast. (See Plate XXI, Fig. 1.) The pivot vessel reduces speed to steerage way and continues on its course. The other vessels steer sufficiently to port to gain their stations at full speed first; then, moderating their speeds and keeping their dress, on bringing the pivot guide on a proper bearing, they will steer his course. Suppose the pivot's speed is five knots, and that the rear vessel gains its position at the rate of 11 knots, it would take a fleet of eight ships twenty minutes to perform this evolution, and the formation would be completed 2 miles from where the evolution commenced.

If two opposing fleets have each a tactical speed of 11 knots, it will be necessary to begin the formation for attack 6 miles about from where the enemy is, in order that it may be accomplished by the time you must engage.

We will compare this with an example of an evolution composed of a successive movement succeeded by a simultaneous movement, being in line ahead, to form line abreast, changing direction eight points to starboard. A successive movement is made eight points to starboard, and when the new line of bearing is reached by all the vessels of the fleet, a simultaneous movement is performed eight points to port. It will take eight vessels, 300 yards apart, steaming at a rate of 11 knots, ten to thirteen minutes to perform this evolution. Advance, say, 200 yards.

In the first part of this chapter we said that some tacticians discriminate between *direct* and *oblique* movements. Admiral Penhoat, as we will see, makes an oblique maneuver a subordinate division of direct movements. He says, "That category of direct movements which is the most unfavorable is where the line abreast to be formed is at right angles to the line ahead you are in, and which we have discussed. If this line abreast is *oblique* to the line ahead, the consequences of the movement are not the same." Let us suppose a line ahead of eight ships, distance 2 cables, speed 10 knots, are maneuvering to form by a direct movement a line abreast, where the line of bearing is at an angle of 45° with the old line. This is termed an *oblique movement.* (See Plate XXI, Fig. 2.) It is done as follows: Simultaneous movement to starboard from line ahead, through the angle which is the complement of the angle which the new line of bearing makes with the old. Each ship then steers for its new station in line, regulating speed as in former cases. If we suppose the speed to be the same as in the example of direct movements, it will take fifteen minutes to complete the evolution, and the fleet will have run 2,000 yards on its course. It would take a little less time to make this same evolution by countermarch. The rule is, if the change of the new line of bearing is more than an angle of 45°, use successive movement; if the angle is less than 45°, use direct movement.

Direct movements, when the fleet is formed in double line ahead, with an interval equal to a divisional front *plus* one distance (see Plate XXI, Fig. 3), present some advantages over successive movements, if the fleet wish to form line abreast. With eight vessels steaming 10 knots, and preserving the usual distance, the duration of the evolution will be eight minutes and the gain ahead three-quarters of a mile. With a successive movement the duration would be nine minutes. If the line abreast to be formed is not at right angles to the double line ahead, the movement is not so simple, but it can be done in two ways.

The first method (see Plate XXII, Fig. 1) is to form line abreast by a direct movement, then change course eight points, coming into line ahead. Enter on the new line of bearing by a successive movement, and then, when the fleet is on this line, all come into line abreast.

The second method (see Plate XXII, Fig. 2) is to form the fleet into line ahead by a successive movement on a line eight points from the old direction, then steer in the new direction, and when the fleet is on this bearing come into line abreast simultaneously.

We now come to consider change of direction of vessels in line abreast or on a line of bearing by certain direct movements generally called *conversions*. *Circular conversions*, or *wheeling in concentric circles*, is, as we have seen, impracticable for a large fleet, on account of the speed demanded from the vessel on the moving flank. The author explains the following system as an efficient substitute or modification. A conversion becomes constantly necessary as the bearing of the enemy changes You desire to keep your line parallel with and opposed to his. (See Plate XXII, Fig. 3.) The fleet is on line A, and you must change to line B, as the enemy has changed his position from C to D. To do this the vessels come simultaneously to a course perpendicular to the new line. The pivot stands on with barely steerage way; the flank ship stands on with the fastest speed. The rest of the vessels vary their speed to keep their dress. When they arrive on the new line B, speed is resumed. This is not strictly a good method, since it brings the ships closer together on the new line. It, however, answers very well for small changes of direction, as it takes the least possible time to perform such change. If time offers after this evolution has been performed, the fleet should open out to their proper distances.

In order that ships should be at a proper distance from one another when they arrive on the new line, they should steer such a course from the old line A (see Plate XXII, Fig. 4) as to be perpendicular to a line bisecting the angle between the old and the new lines of bearing.

The Admiral has the following to say on formations, and the peculiarities of naval war that are now forced upon us by the enormous speed made by ships. Even with a small number of vessels, no movement can be made with the enemy bearing down upon you, inside of four miles separation. If an evolution *must* be performed, it would be better to charge through the enemy's line, in the formation in which you happen to be, and form on the other side. You have been caught at a disadvantage, and you must make a run for it, and this is the safest way to gain time to perfect a formation.

We have now presented about all the principles involved in the evolutionary systems of the last twenty years; only those in future will remain which fulfill the following conditions:

1. The ships must cover the least space at full speed without danger of collision.

2. The evolution must be feasible at night as well as by day.

3. During the evolution the ships must be formed, and be able to give each other mutual support.

4. If possible, the broadside must not be presented to the enemy's line of rams.

It may be judged from our previous remarks on formations that only lines ahead and lines abreast have survived the necessities exacted of tactics by the modern ship. The only question, then, is, what evolutions permit these formations to be accomplished under circumstances of ordinary steaming or in the face of the enemy? The fulfillment of the first three of these conditions imposes simultaneous and successive movements; the fourth category renders, under some, we may say most, circumstances, direct movements necessary.

The ideal system of evolution has yet to be perfected, but we are inclined to believe that it will be founded upon the *isodromic* method. It may be said for this system that when a fleet is maneuvering in the presence of the enemy, each vessel is pretty well covered by the remaining ships from any onset of the enemy for purposes of ramming.

CHAPTER IX.

THE FLEET IN ACTION ON THE OPEN SEA.

I.

In the opinion of a German tactician, the naval battle of the future will bear some resemblance to a combat on shore. In the army long lines of skirmishers are pushed forward, followed in quick succession by other lines, until the whole force is deployed, when the whole body advances, and in a few minutes the battle is decided. His idea is that the torpedo vessels represent the lines of skirmishers, and the line-of-battle ships the columns.

Captain Rivet says:

> The following tactical directions may be considered fundamental:
>
> 1st. During the execution of a maneuver determined on beforehand or ordered by signal, and which has for its object the bringing of the fleet into action, no vessel must change course except to avoid being rammed.
>
> 2d. From the moment that the fighting formation is broken up the combined action of the vessels as a fleet will cease. Each ship must act by herself, and she should try and avail herself of every chance of ramming the enemy which presents itself, and should assist any friendly vessel in need.
>
> 3d. Mutual support would point out the necessity of not separating. The grand object will be to keep together, and prevent the enemy from concentrating on any point.
>
> 4th. When once the ranks are broken it is imperative to keep a lookout on the flagship for signals, although the fighting of each ship as an individual must not be relaxed.

Captain Bridge, R. N., remarks as follows:

> Fleets will approach one another at a greater or less speed; that of about 8 knots, I am inclined to believe, will be the most usual. As they approach, every gun will be, most likely, fired. As they arrive in close proximity, the bow-gun fire will become at length ineffectual, and the respective captains will be disinclined to keep the fore parts of their vessels enveloped in clouds of smoke; so it will cease. Now will come the doubly-anxious moment of seeking to ram one's antagonist and to avoid being rammed by her, to steer clear of towed torpedoes and to plant one's own torpedo conveniently under her water-line. In the early stage of an action I venture to think no great damage will be done on either side. The two, I expect, will pass through one another to a great extent intact, till there shall arrive the time which shall be the crucial test of the value of the evolutionary practice in peaceful times. The two fleets will have to re-form! Picture to yourself the effect, moral as well as material, of a well-ordered column of fresh ships bearing down at superior speed upon a group of vessels endeavoring to re-form. This strictly tactical movement (that of bringing an overwhelming force upon some portion of the enemy's fleet) should not be left to chance or signal.

Mr. Laughton, in his "Essay on Naval Tactics," expresses the opinion that firing between vessels and fleets on the open sea should only be at very close quarters, and says:

> Men at all times are too ready to throw away their ammunition at extreme ranges. In naval action premature firing can have no other effect than to raise a cloud of dense smoke, through which signals cannot be seen, to put an early end to all precise maneuvering, and to let the ensuing fight become a mere scrambling rally, decided, as at Lissa, by individual dash, backed up by good luck.

Although individual dash is not only a valuable but a necessary quality for an officer to possess, still method is of more moment. An eminent tactician says:

> A squadron moving on an enemy must do so in some order; an advance as a mob means defeat. Individual dash is inferior to system, even should that system not be the best.

The following conclusions may be drawn from the expressions of opinion of many writers on this science:

Plans of battles should be prearranged, so that when the enemy heaves in sight he can be attacked without numerous signals being made.

The enemy should be attacked, if possible, if he attempts to pass from one formation to another.

Guns should be fought trained nearly abeam and concentrated fire used. The guns should be fired generally by broadsides, and at a range of about 500 yards.

The ram should be freely made use of. It should be considered the principal weapon of the ship.

Torpedoes should be used preferably by special steamers, but all vessels must be fitted to use some type of this weapon.

We have seen it is the intention of the writers upon this science, whom we have quoted, to use the torpedo-launch or the torpedo-boat, which may be carried by the ships of the line on the high seas, to do their torpedo work during an engagement. It occurs to us that tacticians may well pause and consider the possibilities which surround the plans which they advocate. Will not the lowering of torpedo-boats just previous to an engagement be fraught with danger, by giving the enemy a chance to concentrate and ram you? To get the boats into the water, speed must be reduced, your line will get out of dress, your attention will be distracted from the main object—the attack—and the probability will be that *all* the torpedo-boats will not have sufficient steam, cannot organize, and will fall an easy prey to an alert enemy. Perhaps, to gain your stations and to make your attack in a proper formation, you will have to leave your boats bobbing about a mile astern—of less than no use. If the enemy is sighted, and you have your boats on board and you intend to use them, it would be better to form in retreat, take your time to get your boats overboard, and when all is ready, and your boats have formed between you and the enemy, change course sixteen points upon signal and stand into action.

II.

Regarding the most useful formation for fleet combat, circumstances can alone decide whether it is better to form the fleet in one body with detachments acting by themselves, or whether it is best to divide the fleet into two main divisions acting independently, and attacking the enemy in two different directions at once. It will depend upon the relative numerical strength of the two fleets, as well as on the nature and the power of the vessels comprising them.

The following remarks are made by Captain Rivet in his discussion of attack formations:

It would be well for the most numerous fleet to divide into two main bodies, and one should act to cut off the retreat of the enemy, This portion should be strong enough to stand the brunt of an attack from the hostile fleet should the enemy succeed in outmaneuvering the other portion of the fleet. If the two fleets are numerically equal, the fleet should act together as a unit.

Rear-Admiral Aube, in his essay, further says:

> It seems to be admitted that an action will commence by a primary general attack, a collision between opponents, ship to ship; the fleet being formed in an order for which can be laid down no absolute rule.

Each vessel must keep its bow to the enemy to prevent ramming. The formation will be then one of two classes—great width with little depth, or narrow front with great depth. In other words, the only formations for modern fighting are the line ahead and the line abreast, and their derivatives.

In regard to concentration, we draw the following ideas from Admiral Penhoat's work:

The mode of concentration differs for whichever arm of warfare is put into action. There are three methods for concentrating in artillery engagements the batteries of a certain number of your vessels on a smaller number of the enemy:

1. By oblique pointing.
2. By the passing of the fleet before the one point assailed in the enemy's line in line ahead.
3. By catching any ship or ships of the enemy between two fires.

This last method of concentration consists in penetrating the enemy's line, to take between two fires each of the vessels of that portion attacked. The fight should take place at close quarters. This system of warfare leaves a portion of the enemy's fleet out of the fight, which will seek to enter the *mêlée;* but if the concentrating movement has been quickly executed before the unattacked portion of the enemy has had time to get into action, a decisive result should have been attained.

Considering the question of concentration in regard to rams, two rams cannot well attack the same vessel at the same instant; still, the two can act in concert, either on the same broadside of the enemy's ship or one on each side. In each case the attacked ship should endeavor to bring about a collision between its assailants.

The attacking vessels should ram the enemy's ship one after the other; therefore, any number of vessels can be concentrated for ramming on one of the enemy. In artillery concentration, however, only two, or at most three, ships can be used against one of the enemy.

Concentration for torpedo attack resembles somewhat the method used for ramming. If the torpedo is carried ahead on a spar or installed to act right ahead (if of the auto-mobile type), the methods are identical.

Mr. Campbell has to say, in regard to this most important factor of success—concentration:

> Had I a fleet of twelve ships in action against a fleet of twelve ships of the enemy, I would do my best to maneuver so as to fight them one at a time, or "twelve to one," and failing this, two together, and so on; last of all would I fight the twelve at the same time—that indeed would be a *dernier résort.*

III.

The following remarks and general rules applicable to actions between fleets are drawn from various sources, and may be considered as conclusions formed by the best tactical writers.

An attack upon one fleet by another, in fact the whole combat, will consist of a series of rapid penetrations of the enemy's line. Each side will be equally an attacking party. After the first charge all fleet combination will cease, and vessels must act for themselves. The ship then becomes the tactical unit. In all charges, having once passed through the enemy's line, it must be well understood beforehand how the vessels are to turn, whether to starboard or to port. This should be governed by an inflexible rule. If it was arbitrary, confusion and disaster would certainly follow.

In opposition to those who think it better for a fleet approaching an enemy to have the wind aft, so as to drive the smoke in the enemy's faces, by which the approaching fleet's movements are masked, Mr. Campbell says:

> As far as my experience teaches me, I have always found it as hard or harder to see through smoke driving before you as it is to see through it coming towards you; and I believe the ships coming up against the wind would be the first to see what formation the others were in.

For a fact, at Alexandria the English suffered from obscuration of their target by smoke, and since they were to windward Mr. Campbell's idea would seem to be borne out.

Captain Noel says:

> As it will be impossible to understand complicated signals in action, the only signals made should be very simple, need hardly be more than compass signals, and may be termed "action signals."

If possible, a semaphore should be used, worked from some protected tower, in place of the Army Code signal flag.

Captain Rivet is of the opinion that after an engagement has once commenced only those signals should be used which would give an order for retreat, or which would be needed to arrange the fleet in such a manner as to consummate the ruin and rout of the enemy.

IV.

We will now consider the sphere of the several weapons of a ship in a fight between fleets. Most authorities are of the opinion that the fire of the artillery should be by broadsides, and concentrated either abeam or slightly forward of the beam. Short range, say 500 yards, will be the ordinary fighting distance of ships. Commander Noel, in his work on the "Gun, Ram, and Torpedo," summarizes the duty of the artillery in action in the following words:

> Speaking generally of the use of guns in a fleet action, I am much of Captain Colomb's opinion, viz, that they should be previously laid right abeam and horizontal and then fired at the instant of passing an enemy's ship. I would lay down six rules for the use of guns in a general action :
>
> 1. Guns are on no account to be fired unless there is every probability of their taking effect.
> 2. The broadside guns will always be trained on some prearranged bearing, from abeam to 15° before the beam, so that the captain shall at all times, and without giving a second thought, be certain of the exact direction in which his guns are pointing.
> 3. Guns as a rule will be fired by broadsides.
> 4. A disabled ship, with rudder or engines broken down, will use her guns to the utmost of her power.
> 5. A ship pairing off with an enemy to 'single combat,' moving around on the same circle, or finding herself on the same course as the enemy, will use independent firing.
> 6. As far as possible the aim is to be directed at the weakest points of the enemy.

The armor-clads of every nation should be a study, so that their vital points and weaknesses may be known. Large diagrams showing these should be accessible to all officers and gun-captains. Captain Noel further remarks that a turret ship, with all-round fire, should, when in line-of-battle, have her arc of fire curtailed so as to be available only between abeam and 15° before it, the same as any other vessel.

Mr. Besson says :

> The ram is the hardest weapon to employ, but it is the most terrible. Ramming, so difficult in a duel between ships, becomes more practicable in an action between fleets, as during a *mêlée* vessels, from the fact of being befogged by smoke, or through some accident, may find themselves in unexpected positions either of advantage or disadvantage.

Commander Noel is of the opinion that ships of the line maneuvering as a fleet cannot alter course and turn in any direction with the sole intention of ramming an antagonist. Whenever *ramming* is resorted to, it should, in his opinion, be done in this wise : Should the enemy be off his guard, his vessels should be attacked by the rams on their beam. These should maneuver to strike the enemy's vessels amidships when on a course making an acute angle with that on which the enemy is steering, instead of a right angle. By thus turning slightly towards the enemy's course, the rams would come in contact with less although sufficient force, and would by ranging up into the enemy's course avoid the ram bows of the next astern, instead of running through the lines and exposing their broadsides to the ships coming up.

Captain Rivet says that all armor-clads must carry torpedo-boats of great speed, which can be lowered during an engagement, with steam up, and ready for immediate action. A rapid merchant steamer can be fitted to carry four large-size boats. She should accompany the fleet. Vessels must carry torpedo-boats to satisfy the following conditions:

1. She must be able to lower and hoist them with facility.
2. The torpedo-boats must be of the largest size possible, considering the size of the ship.
3. The torpedo-boats should have the highest speed attainable.
4. These torpedo-boats should be possessed of the best nautical qualities. Especially should they have excellent turning power.
5. The torpedo-boats, boilers, and engines should be noiseless, and their coals should be as smokeless as possible.
6. The torpedo-boats' armament should combine efficacy and handiness.
7. The torpedo-boats should be able to obtain their steam pressure very easily.

This steam pressure may either come by temporarily connecting the boiler of the torpedo-boat with the ship's boilers, or by having the boat fitted with a boiler especially constructed for rapid steam-making.

In the first part of this chapter we said that lowering torpedo-boats preparatory to an action presents more difficulties than appear at first sight, and we propose to discuss the subject further. Two fleets make out one another 10 miles apart. If we give each fleet a speed of 10 knots, they will be together in half an hour. Nine times in ten, when the mutual sighting takes place, neither will be in formation for attack. By the time they have gotten into this order, which will take fifteen minutes, say, they will have lessened the distance between them to about 5 miles. Now, if at this stage either fleet attempts to get the torpedo-boats into the water, the other fleet would have a great advantage if they bore down upon them at full speed and engaged them. This separating sea could be covered in twenty minutes, and it is doubtful if this length of time will suffice to organize their torpedo flotilla and straighten up the line for battle.

It would seem, then, that the principal dependence for carrying the torpedo boat must be upon those vessels specially fitted for the purpose. Too much distraction to the line-of-battle will take place, as a general thing, if they are carried for sea use by those vessels composing this force.

Torpedo-boats are of course most necessary and must be provided, but it will be remembered we are discussing actions on the open sea. We can see most easily the advantage of a torpedo flotilla steaming in groups among the ships of the line of battle, moving in and out among the enemy, the boats picking up their work as it comes to them. We are rather of the opinion, though, that instead of forming an advance line and entering the action before the field of operations is obscured by smoke, and when they can be the more easily driven off by machine-gun fire, their time for gathering the best fruits of the contest will be *later*, during the *mêlée*. Indeed, it would seem to be a maxim that victory will lie with that fleet whose torpedo flotilla is first in action *after* the first charge, the state of the sea permitting torpedo-boats to be used.

Admiral Penhoat says that in battle all fires will be started; therefore, there must be two speeds taken as necessary during an engagement:

1. The maximum maneuvering speed, which is about 3 knots slower than the maximum fighting speed.

2. The maximum fighting speed, which is, when the formation is intact, the fastest speed of the slowest ship, and when the formation is broken up the fastest speed of the individual ship.

Captain Rivet is of the opinion that no faster speed than 8 or 10 knots will be maintained during an action. He says:

> To exceed this would make the firing very wild, and ramming dangerous for the attacking vessel. The engine, though, should at all times be ready to go ahead at full speed.

V.

It is not probable that a fleet will charge more than twice without losing its formation. The commanding officer of a section of two should strive, for mutual safety, to keep up the fleet organization as long as possible, but if it *is* broken, the section should act as a unit independently of the fleet, keeping a lookout for signals from the commander-in-chief. Sections of two ships should keep together as long as possible, the junior being under the immediate control of the senior captain, whose vessel will be in the leader. There is one exception to this general rule; the junior when he encounters an enemy's ship in his path should immediately ram her.

Commander Noel says that the secret of success in an action lies in the re-forming of the fleet after the order of attack has been broken up. The chance of victory lies with that fleet which can re-form first. If, in the midst of an engagement, the Admiral considers it necessary to re-form the line of battle, he should signal his fleet to draw out of action and to form on *him*, either in the formation in which the attack was made or in some other as signaled.

In regard to the question of maintaining a regular reserve squadron, there are two absolutely different opinions; for instance, Captain Harris not only believes in a reserve, but says that the arrival of the reserve on either side will decide the battle in favor of the side to which the reserve belongs. His idea, further expressed, is that the reserve should be composed of those armor-clads which make less than twelve knots. Other tacticians believe that there should be no reserve, and that every fighting vessel should be in the line of battle to engage the enemy.

Probably the most advanced idea is that certain vessels of widely different qualities from the majority of vessels employed should not be associated with them in the line of battle. These may form what may be termed a reserve division. They may be used to re-enforce the head or rear of the line of battle, or they may be employed to prevent a flank attack.

During a fight the duty of the squadron of cruisers, if it is seen fit not to employ them in the line of battle, would be to keep well clear of the ships-of-the-line, and be ready to assist damaged ships, cut off torpedo-boats, and to harass the enemy's smaller vessels.

To attack a fleet at anchor use the ram ; each vessel choosing a ship of the enemy to attack. A fleet at anchor must depend for its defense on torpedoes and booms, together with its flotilla of torpedo-boats. A fleet surprised at anchor is a contingency of war hard to realize. A fleet, however, caught in this manner would undoubtedly be destroyed.

During an engagement, if the Admiral wishes to retreat, the line-of-battle, by a simultaneous movement or otherwise, as soon as possible should come into some retreat formation. Strong stern fire now becomes a necessity. The wake of each ship should be thickly strewn with torpedoes. Most Admirals will prefer to retreat in lines ahead; if this is the case, the best ships should be kept in the rear nearest the enemy, the lighter vessels towing the disabled ones.

Should a fleet be surprised by an enemy when it is in no formation, each ship's bow should be turned towards the enemy, and a charge made through the enemy's line. When the other side is reached, they should form in the chosen way for retreat and fight the now turned and attacking enemy, or, if the occasion presented itself, they should turn simultaneously and attack their pursuers.

Two fleets meeting at night, how will they fight? The two fleets will probably not discover one another until they have approached each other to within three miles. Each fleet will probably be cruising in an irregular group formation, or else in two lines ahead. The electric light cannot be used indiscriminately, as you may blind your friend and perhaps have him into you. Your torpedo-boats cannot be gotten into the water, and no elaborate formation can be attempted. We will consider each fleet to have been well exercised by her Admiral in night drill, and that they stand on an equality here. It is thought that the fleet which is formed in line ahead in two columns will have the advantage over the fleet formed in any other way. In this case the leaders of the lines alone should use their electric lights. The leader of the column nearest the enemy should charge the enemy's line, followed by all the ships of his column, maintaining their formation in line ahead. As soon as the last ship in this column has her new direction, the leader of the second column, followed by his command in the line ahead, should charge some other point of the enemy's line. Each column should strive during the action to preserve the formation, and should pass and repass through the enemy's line, using artillery alone with concentrated fire. Small arms and machine guns should be rapidly fired at the moment of passing and at no other time. The leaders of the columns must understand that they must turn the one and the same way in reversing their direction to charge the enemy again. All movements made should be successive. Although some tacticians, as is stated somewhere in this work. say that the ram is the weapon of the night, it is believed that the most modern thinkers are of the other opinion. From these last we gather that ramming should only be incidental to the attack, and then only when the formation gets opened out, as it will. Should the smoke grow so dense as to obscure the field of battle, each ship in each column should sound its fog distinguishing signal, slow to quick speed, and the column leader should draw his column out of action in the direction then steered, and when the smoke lifts should charge the enemy's line again, with his column always following.

VI.

Different tacticians have different ideas as to the probable conduct of battles on the open sea between fleets. Captain Colomb believes that an engagement will be opened by a charge on both sides, followed by ramming and a breaking up of the formation. He is partial to a formation for attack of great depth and narrow front; that is, a line ahead, or some modification of it, standing down on the enemy in a direction perpendicular to his line of battle. His idea being to concentrate by piling his ships on some point of the enemy's line.

We have before observed that Captain Colomb is not partial to the group. We will now consider the plan of action of an author who is.

Commander Noel would have the enemy attacked in this manner: (See Plate XXIII, Fig. 1.) Approaching in column of two divisions, the enemy's fleet exposing a narrow front, the object will be to make it pass outside your nearest line; that division exchanging broadsides and moving directly ahead, keeping all the enemy's ships enveloped in smoke, and doing all the damage it can with its guns. In the meantime (or directly the leading ships meet), the other division, having been previously instructed. will turn eight points towards the first division, and, in a line abreast in groups, will pass astern of the first division and will charge the enemy along its line.

Admiral Randolph, in discussing an engagement between two squadrons, assumes that the enemy's plan of attack will be a charge in simple line abreast. He assumes also that the enemy's line will contain eight ships. Before unfolding his scheme for his special method of forming, he says that the Admiral should draw up several plans of battle, and they should be rehearsed before any chance of meeting the enemy occurs, so that when signal is made on sighting the enemy, "Use plan A (or B, or C)," each captain will know what to do.

For fighting the enemy in the formation stated above, the author places his fleet of eight ships on two of his lines of bearing, *A* and *B* (see Plate XXIII, Fig. 2), the Admiral on the left of the first division, the second in command on the right of the second division. These two commanders are separated, and therefore the two divisions, so that the wings of the fleet outflank the wings of the enemy a distance, say, of 1,200 yards. The second in command drops back his division, say, 600 yards, so that the fleets are formed as shown in the figure. The Admiral puts himself opposite to the third ship of the enemy, counting from the wing nearest to him. The second in command opposite the third ship of the enemy from the wing nearest him. The author chooses eight knots as the best fighting speed.

The fleets steer for one another, the ships of the author's fleet carefully keeping their stations. The Admiral and second in command, acting as guides, steer for the vessels opposite to which they have formed. When the Admiral gets at the point *X*, he dips his signal and each ship circles simultaneously, and tries to ram the ship toward which he turns. If they miss ramming their opponents, then the first division steer over to assist the second, No. 4 going to assist No. [illegible] and No. 3 to No. 7, &c.

About this time each captain must take care of himself, but it will be seen that each division can steer down separately and attack the rear of the enemy.

If the enemy, instead of being in line abreast, were also in an echelon formation, the port division should not drop astern so much from the beam line of the starboard division.

Suppose, now, the squadron find themselves in the presence of each other under different circumstances, either somewhat suddenly, or one of them, standing in for the land in the morning, observes the other coming out of the port they have been watching.

The outside squadron (*A*) are in two lines (see Plate XXIV, Fig. 1); the other (*B*) has also been enabled to form in two lines, but has not had room enough to form abreast. *A* may be supposed to have what room he wants, and forms line abreast on a line of bearing by divisions, one division dropped to the rear, as shown in the figure.

As *B* will not have time and room to form, he will probably elect to cut through *A* in the 1,200 yards interval. With *A* formed as he is, *B* will run the risk of being pretty well used up by *A's* rams and bow fire, although *B* can get in a good broadside fire on *A*. As *B* goes through, each division of *A* turns towards the two columns of *B*. *A* can strengthen his formation by stationing 4 and 8 nearer the scene of the *mêlée*, say on the outer quarter of the Admiral and of the second in command.

Admiral Penhoat gives the following advice concerning the different formations for fighting with rams in squadron:

> If we should elect to attack the enemy in line abreast, we should charge him as normally as possible at good speed, and as we approach him each ship should try and pick out its opposite in the enemy's formation. To do this, each ship may have to maneuver either to one side or the other. This change of direction would be dangerous to make at a less distance than six cables from the enemy.

The Admiral thinks in the majority of cases that ramming will not be undertaken at the outset, but only after the guns have inflicted sufficient damage to prevent an enemy's maneuvering to evade an attack with the ram. If, however, at the outset, ramming the enemy is engaged in, the enemy may probably evade the shock; each ship, then, will pass close aboard the other, and they will exchange broadsides at close quarters, which should be very destructive. After the fleet have charged through the enemy's line, they should turn through 16 points, with helms all the same way, and return to the attack. The same general directions apply to the attack when formed in double line abreast.

This author has the following to say about concentration, and gives an example of a ramming attack: In regard to concentration it will be of little or no use between equal forces, except in the case where the fleets are very large. A concentration may be either *total* or *partial.* If a fleet is arranged for a ramming encounter, and its number of rams is double the number possessed by the enemy, the formation for attack in two lines abreast of equal length is naturally indicated. This is a total concentration. If the number of rams of the two fleets are equal, this method will not do, and a partial concentration must be made on some weak point in the enemy's line. In a concentrated attack the first line should be composed of the heaviest armored vessels, the second line preferably of rams. The first line is to use its artillery only. Ramming attacks on the broadside of a vessel, the rammer describing a quarter of a circle, are based upon an appreciation of the speed, essentially variable, of the adversary. This maneuver presents only a very few chances of success, if we reflect that with a speed of ten knots a vessel passes over her length in fifteen seconds.

In lines abreast, the flanks should be protected by other vessels, not belonging to the formation, but which act as a re-enforcement.

According to Mr. de Penfentenyo, the following plan of battle is the best to follow out. The proper formation for attack is the simple line abreast. After the first charge, vessels ought always to immediately reverse their courses, all heaving over their helms in a preordered direction, and form groups without further signal. (See Plate XXV, Fig. 1.) The group-leaders should become commanders-in-chief of their groups, and should maneuver them independently.

Should charging through the enemy's line be the scheme of attack, as nine times out of ten it will be, it may be laid down as a rule, that after having passed through the enemy's formation, vessels should return to the charge. If the formation is a line or lines ahead, the leader returns to the attack followed in succession by his line. The rearmost vessel alone may try ramming tactics, the others *must not* except for self preservation.

A German tactician in answer to the question as to how the fleet should engage the enemy, says, that if it advances in a formation of line abreast, it can use its rams better, but that its artillery is of nearly no avail, as it could hardly be used lest the fleet should fire into one another. The author suggests that, with the Admiral leading, the fleet should advance in line ahead steering for the nearest ship of the enemy. When within two miles, change course four points with the enemy's front by a successive movement, and when on this line, swing together on a course heading for the enemy. This brings your fleet into a bow and quarter line. (See Plate XXIV, Fig. 2.)

Mr. Besson says:

> The enemy being signaled, the squadron should form in line ahead and then steer for the enemy at full speed. If the enemy is in line abreast, it should try and isolate one of his wings and destroy it.

Or, to discuss the subject further, let us suppose one squadron to be in line ahead and the enemy in line abreast as has just been stated. Our squadron we will call *A*, the enemy *B*. (See Plate XXV, Fig. 2.) The leading ship of the *A* squadron receives the fire from all the ships of the *B* squadron as he approaches. If he is not stopped dead, which is unlikely, he will pierce the *B* squadron between B_1 and B_4, giving the enemy both broadsides. All the *A* squadron follows in line, and it is easy to see that B_1 and B_4 receives it hot and heavy. If it is supposed that the two squadrons steam at the rate of 11 knots, and are composed of six ships each, *A* squadron will pass through *B's* line in two and a half minutes. Consequently, the wing ships of *B* will not have time probably to give A_6 the benefit of their fire. The advantage belongs to *A* squadron all through from an artillery point of view. This advantage is as great, if not greater, from the standpoint of the auto-mobile torpedo, since B_1 and B_4 alone can use theirs, and yet they will receive the whole outfit of the *A* squadron.

If divergent torpedoes are used by the *B* squadron, A_1 and perhaps A_2 will be sunk by B_4 and B_1. But if both squadrons use them, they are on an equal footing, and B_4 and B_1 will have the same chances against them as A_1 and A_2.

From the standpoint of the ram, all the vessels of *A* except A_6 are flanked by their next astern, whilst as regards *B* squadron, B_1 and B_4 are not as well protected by their neighbors B_2 and B_5, placed on either side of them. B_2 and B_5 can both be rammed by any vessel in *A* squadron, but they in return can only ram one, and the next astern, as A_4, A_5, or A_6 will certainly sink B_2 and B_5 if they attempt to ram A_2 or A_3. From every point of view, then, the advantage remains with the *A* squadron.

The wing ships of *B* squadron not being able to use either guns or torpedoes, will seek to enter the fight by falling in rear of B_4 and B_1, and the formation of *B* will then be in two columns formed on the center, one column on each side of the *A* squadron. (See Plate XXV, Fig. 3.)

Even then *A* squadron will have the advantage in gun-fire, since it can use both broadsides; still, since the leading ships of *A* catch it so hotly they may be so injured as to throw their line into confusion. The advantage, on the whole, if *B*'s wing ships act as indicated in this last category, will belong to the *B* squadron, and *A* should never suffer itself to be entrapped into any such position. It would follow then as a *maxim*, that since a squadron in line ahead can change direction more easily than a squadron in line abreast, it should never attack a squadron in this last formation in the center, but nearer one of the flanks, preferably the weather one. To make this movement, *A* squadron should, when at some short distance from the enemy, change course eight points (see Plate XXVI, Fig. 2) by a simultaneous movement, and when abreast one of *B*'s flanks form line ahead and change.

Suppose that each fleet were in line ahead. The two lines pass close to one another, concentrating their fire on the head vessel of the opposing force. Each leader will probably succumb, and be rendered *hors du combat*. The only precaution against this which can be taken is to lead in with the vessel furnished with the heaviest protection. Whether we admit that the damage done to the leaders will be grave or light, the two lines will finally find themselves abreast one another. Each fleet will turn to ram the other and will collide or go through. The formation after this turn will be a line abreast for each fleet. After a mutual penetration of the formations, the fleets will turn about and again charge. (See Plate XXIII, Fig. 3.)

It will be seen from the figure, that vessels charging past the enemy do not do so, at the instant of passing, on a line abreast, but on a bow-and-quarter-line. This being the case, it will be observed that the gun fire is unobstructed, and that therefore charging and recharging in this formation is good tactics, since there is little or no likelihood of firing into your friends.

Two fleets are in line abreast and have charged, and each fleet has turned, all the vessels with their helms the same way. It is apparent that each fleet has gained a diameter on the flank of the other, and that the next charge will be with vessels in *échelon*. (See Plate XXVI, Fig. 1.) This figure, by following out two or more charges, would go to prove that the formation would soon disappear as the flanks would be thrown out of action.

We have now examined into most of the theories of engagements between fleets which have been set forth and discussed by various tacticians. All of them are more or less unsatisfactory, from the fact that the premises of the authors are more or less biased in favor of their methods, and the enemy's fleet is generally considered to do the most unlikely thing. There is, however, much to be gained by studying these systems, but until the modern fleet meets its match on the high seas, we will have to content ourselves by dealing with hypotheses.

CHAPTER X.

OTHER DUTIES OF THE FLEET IN TIME OF WAR.

I.

In answer to the question "What is the chief object of war?" Admiral Aube discourses as follows:

> To inflict the greatest possible harm upon the enemy! We must expect then to see the iron-clad fleets, mistresses of the sea, turn their powers of attack and destruction, in default of adversaries, against all coast towns, fortified or not, pacific or warlike, burn, ruin, and at least raze them to the ground without mercy. This has been done at other times; it is done now; it will be done in future.

Captain Maubenge, of the Belgian artillery, in his paper on "The use of Artillery in Coast Defense," expresses the following opinion as to the motive in war, bearing out the views of the distinguished writer above quoted, but in language rather more mild:

> In war, the main object of ships is not to destroy the elements of defense, but rather to approach naval and military establishments so as to carry disorder and devastation into the ports, dock-yards, and arsenals, and to diminish the morale of the garrison and inhabitants. Often the fate of an invested place will be decided by the presence alone of one or two armored ships in its roadstead.
>
> Seamen can operate offensively in three ways:
>
> 1st. By remaining outside of the effective range of the coast guns and at a distance from the place equal to or less than the longest range of their own artillery. In such a position, by correct firing—which would be facilitated by the great size of the target—they would throw their projectiles into the place, whilst the defensive artillery, having a much smaller object to aim at, would have less chance of hitting it; and even successful shots, striking an armored vessel with a great angle of fall and with little remaining velocity, would produce very small results.
>
> In winding rivers, with high banks, floating batteries, or ships not heavily armored, will conceal themselves behind the banks, and only the smoke of their guns will indicate their position.
>
> 2d. The second method consists in forcing a passage without engaging the guns on shore. This plan will certainly be adopted by seamen, if the means of defense appear insufficient or badly utilized, or if they have some chance of succeeding by strategy. It will be resorted to if, after having crossed the dangerous belt, the ships can bring their broadsides to bear on the place, especially so if they have to fear only the fire of 12_{cm} or 15_{cm} guns. The intelligent seaman will not fail to attempt a measure, the success of which would be attended with such great results. This method would be used sometimes even when the roadstead was commanded by guns of great caliber, if the river or channel above the place was navigable and was not protected by coast artillery. After having passed the enemy's defenses, the ships would ascend the river until beyond his effective range, stopping at a good distance for bombarding.
>
> 3d. In the third place, ships can engage coast artillery. It is the middle course; seamen will resort to it only when the first two are impracticable, or are too danger-

ous. They will, perhaps, be led to attempt it when they have discovered defects in the defense, and have confidence in the impenetrability of their ship's sides, or in the great superiority of their ordnance.

If navigable rivers give access to the seaport on all sides, the mission of the attacking seaman is easier. If he be exposed only to the fire of fixed batteries, he can, by constant change of position, avoid their shots while bombarding at a good range. Naval establishments thus exposed can only be defended effectively with the co-operation of a fleet of coast-guard ships, and of floating batteries.

II.

Admiral Aube in his essay says further:

> The depreciation of the power of artillery against a movable iron-clad target has been verified by experience. It sensibly lessens the risks which an iron-clad fleet runs, covered with smoke and defiling at high speed before the most powerfully armed coast batteries.

This remark is borne out by facts. The experience being still more derogatory to artillery for the reason that the ships in the case in point were nearly if not quite stationary. At the bombardment of Alexandria some of the guns in the forts, constructed to penetrate armor of a certain thickness, although fired with approved charges and proper projectiles, failed to more than dent the comparatively light sides of the attacking vessels.

Some tacticians, in fact most of them, set it down as a *maxim*, that in attacking fortifications, fleets should engage at close quarters and fight under way. If the environment prevents this, then the fleet should fight bows on if possible. This, however, was not the tactics pursued by the English in the bombardment of Alexandria. The result of their experience was that there existed no greater danger in being anchored, and that their artillery practice was much more accurate when the ships were stationary. It must be remembered, though, that the fleet was not opposed by its equal in the art of war. During our own late war both methods were tried, and both satisfied the requirements of the circumstances of the occasion.

There were certain tactical experiences undergone by the combatants at Alexandria concerning which Lieutenant-Commander C. F. Goodrich, United States Navy, has come to the following conclusions:

1. Although vessels engaging forts will never be able to fight on equal terms with them, still forts will offer but little resistance to vessels attempting to run by them.

2. Under all circumstances the fleet should keep away from forts whose guns are mounted high above the sea-level on account of the danger to be incurred from a plunging fire.

3. Any projection appearing above the crest of the parapet of a fort furnishes an excellent target for the attacking fleet. It is a means by which the position of the guns is readily indicated and located, and which advantage the ships should be quick to seize.

4. Recent high-powered guns are not adapted to bombarding earthworks. Ships for general service should have a composite battery.

5. Ships should engage forts at moderate distances. With close range and a stable platform great damage can be done by shrapnel and machine-gun fire.

6. In all bombardments the target for the fleet should be:

(*a*.) The guns of the enemy actually firing.

(*b*.) Any building believed to be a store-house or magazine.

7. An advantage possessed by a vessel with a heavy fore and aft fire lies in its ability to anchor head to sea and engage a fort either ahead or astern from a comparatively steady platform.

7. If the ships and forts are about equal as regards artillery, the ships had better anchor. If the forts are the heavier the fleet should fight under way.

Every fleet surprised at anchor is a fleet destroyed; the ram, which the assailant alone should avail himself of, then becomes an arm as safe to him as it is destructive to his victim.

Every fleet at anchor, if the access to the anchorage is possible, can be surprised by night, or even attacked by day, by a fleet of torpedo-boats.

With the present defenseless state of our coasts, it becomes of vital interest to know that the range of guns of 27^{cm} is 12,500 yards, and that of a 14^{cm} gun is 10,000 yards, with an elevation of 35°. It is, in fact, even greater with the enormous muzzle-speeds now obtained, so that these guns can bombard every town, every settlement occupying a large extent of ground, and which any ship thus armed can approach within these distances. These towns will not only be bombarded, but they will be burnt or laid under contribution without the assailants running any serious risks from the coast batteries, or other shore or submarine defenses. The attacking vessels can only be successfully opposed and their progress barred by a fleet designed for coastwise defense.

Admiral Penhoat says that an attack upon a harbor or position on the coast involves three distinct operations:

1. The penetration of the port, or getting into a commanding or dominating position.

2. The bombardment or landing.

3. The disembarkation of troops and the occupation of the position.

The speed of a fleet is now so great that it can appear off a harbor, without notice, with means for destroying a fleet at anchor not well defended. To defend these vessels the author believes in a fortified breakwater or mole with narrow entrances. He does not pin his faith on either mines or booms, as he believes such methods will prove as great obstructions to the defenders as to the assailants. Nets are only serviceable under circumstances which are not likely to occur. A net caught in the screw would be worse than a shot lodging there.

III.

The blockade of the whole coast of a country possessing a navy is impossible; even that of a single port is difficult. Under any circumstances it can only be rendered effective by the concentration of numerous squadrons écheloned, as it were, on several concentric circles whose center is the port to be blockaded.

It is not likely, in the opinion of Captain Harris, R. N., that armor-clads will be employed as blockaders, especially at night, in the vicinity of ports known to contain torpedo vessels. Blockade should be maintained by light and swifter vessels, which, being cognizant of the positions of the armor-clads, will repeatedly communicate with them. In some blockades an opportunity may be afforded the blockaders to establish themselves in an adjacent harbor, and to use it as a base for their operations.

A vessel occupying the position of a blockader will be exposed to an attack from:

1. Auto-mobile torpedoes from a gunboat or torpedo-boat.
2. A spar or divergent torpedo from a cruiser, gunboat, or torpedo-boat.

Gunboats and torpedo-boats of the most recent pattern are able to use their torpedoes right ahead without stopping or changing course; therefore, if a blockading vessel is exposed to an attack from vessels furnished in this way with these weapons she can defend herself by—

1. Running away.
2. Sinking the attacking vessel before she has time to use her torpedo.
3. Fighting the approaching vessel with guns and her own torpedo-launches.
4. Using nets, booms, &c.

The first method is hardly to be thought of. If it was used, the enemy could keep the fleet constantly driven off.

The second method is more practicable. The attacking vessel must, however, be destroyed before she can approach within 600 yards. A heavy fire of manageable guns should be kept upon her. The only drawback is, that if the guns do not sink her, they will give her the chance she wishes to have, that is, an abundance of smoke to work in.

The third method is not to be entirely depended upon, because the enemy may glide between your launches; injured perhaps by your attack but not disabled.

The fourth method is hardly satisfactory, but when combined with the second and third, it seems all that is left to us. The moving torpedo-boat is a small object and moves rapidly, and consequently is hard to hit, but on the other hand it is easy to sink if your shot strikes it.

The above views are taken from a paper analyzed by a French writer from an English work on torpedo defenses. To-day the bulk of professional opinion is against the use of nets, &c., except in the case of anchored vessels which are disabled. In any technical sense, the best method is to use torpedo-launches combined with mechanical gun fire from both ship and boats. In time perhaps torpedo warfare will become very much modified through the improved construction of war vessels.

Armored vessels built for coast and harbor defense, but which can be taken to sea, may be of great use in an enemy's harbor where torpedoes are feared, to be pushed forward in the van in place of the more valuable armor clads of the fleet, since they have, as a general thing, great artillery power and good resisting qualities for their size.

Among the most useful elements of the besieging fleet is the telegraph-cable vessel. The cable-laying flotilla should consist of the tank vessel, containing the cable, small vessels to be used as receiving stations, and tugs for the heavy weighing and handling of buoys. The tank vessel should be capable of laying out and picking up the cable and should in every way be fitted for electrical work. The tugs will be used to run lines on shore. The cable should be a compromise between the shore-end and deep-sea cables, so as to stand well in shoal water and to permit of its being picked up and laid down many times.

Speaking of instruments and methods for signaling messages, outside of the electric telegraph, probably the best system, for day work, is with the heliograph, in any country with a good bright sun and a moderately clear sky. The advantage, where this instrument is used, is that the enemy is absolutely unaware of your action, unless he be absolutely located in the path of the reflected ray; that is, in a line between your two stations. During the night the heliograph is acceptably used with artificial light.

IV.

Should a fleet regularly besiege a port, the nature of the work to be done will, in a great degree, decide the class and number of tactical elements which will enter into it. Besides the fleet of line-of-battle ships, and the squadron of vessels composed of cruisers, corvettes, gun-vessels, tenders, and torpedo-vessels, there will be heavy wrecking tugs, surveying vessels to establish lights and buoys, a flotilla of smaller tugs and funimobile launches (or those steered and governed through a cable, by the system contrived by Lieut. T. C. McLean, Uniited States Navy), a submarine brigade for mining and countermining, telegraph vessels for laying cables, search vessels furnished with a powerful electric lighting installation, coal and ammunition vessels, commissariat and naval stores vessels, hospital ships, and floating repair shops. All these various elements, with their multitude of experts and attachés, must be protected by a convoy guard, the whole to be under command of a flag officer, who will need a powerful and efficient staff under him. He must have these vessels ready at all times to perform their individual functions and ready to get under way and make passages without going adrift. If the convoy is very large it should be divided into squads of not more than six vessels, and the convoy guard for each squad should be a section of two vessels at least.

In entering an enemy's inclosed waters it will be necessary to have a countermining flotilla precede the fleet where planted mines are suspected.

V.

A German tactical writer, as recently as this year, remarks that a shot entering a torpedo-boat will probably place it *hors du combat*, but a moving ship makes it very uncertain as regards striking such a small and fleet target even with mechanical gun fire. This author says that there is only one certain means for driving off the enemy's torpedo-boats, and that is to fight them with your own. The question then immediately arises, how does this class of vessels fight? Not with auto-mobile torpedoes, because the target is too small and too changeable for a torpedo; besides, the boats are not deep enough in the water. Two torpedo-boats could not ram one another without both being used up. The way will probably be, each boat will attempt to destroy the other by means of small gun-cotton spar torpedoes, by mechanical gun fire, or by the use of hand grenades. It should be the aim of a combatant to try and kill the crew of its adversary, as it is to be supposed that it is composed of skillful and daring men, and that their loss will be felt.

VI.

The following notes upon landing parties and the naval brigade are by Lieut. T. B. M. Mason, United States Navy, published in "Hamersley's Naval Encyclopedia":

> When everything is ready for leaving the ship, line ahead is formed, the steam-launch towing the column. A few oars in each boat are kept going, and if the wind is favorable, sails are set. In moving up a river care is to be taken not to be ambushed. Scouting parties may be landed if favorable eminences are near at hand, from which the banks may be viewed ahead. If attacked in a narrow river, in force, a fight should be made, and the advance continued after the enemy is repulsed. In a broad river, it may be safe to run by the enemy, if he is unprovided with boats. Care must be taken to destroy all boats which may be discovered on the way, as they might be used to cut off retreat. If it is found necessary to land to make coffee, one boat only should be detailed for the work, the others lying off ready for a surprise.
>
> Having arrived within shelling distance of the place to be attacked, a well-directed slow fire should be opened upon it. The boats furnished with guns should take up a commanding position; the lighter boats, after the landing or beach has been cleared, should move in and land their men, with the exception of those detailed as boat-keepers; the steam launch with a machine-gun moving in to cover the landing. If possible, the work of destruction should be carried out by this party.

In regard to a naval brigade:

> The circumstances under which a landing has to be made are so variable that no general rule can be laid down. The question, however, can best be discussed from two standpoints:
>
> 1. Landing on the water-front of a town.
> 2. Landing on a beach (the enemy opposing the landing in each case).
>
> On approaching the town, the covering vessels will take up such a position that they can shell the landing, and at the same time cover the land approaches to prevent the enemy receiving re-enforcements. The artillery boats will then advance and

take up positions to clear the landing and command the principal streets and buildings likely to shelter the enemy's riflemen.

The sea-face having been well shelled, the first line of infantry will pull in to the best landing-places. Once ashore, the first line of buildings will be occupied and manned on the land side. The second line now land, then the artillery, then the reserve.

On approaching a beach, the covering vessels must take up a position so as to enfilade any work that the enemy has erected, and to command the approaches. The artillery boats must clear the sand-hills and bushes back of them. The first line now land and advance as skirmishers, and, under the fire of the boats, must throw up light protections and occupy the line. Once established, they must open fire, and the second line will land with the artillery. The second line on shore, they will occupy the position of the first line, which will advance. The artillery will occupy any little knoll, cover itself, and open fire. The reserves, in the mean time, will have landed, and the whole body will advance. The reserves must intrench themselves, and keep the communication with the boats open. As soon as their guard is left by the advancing troops, the boats should be gotten ready for the re-embarkation of the party. In all cases the boats must be hauled off a little way and anchored with a hauling line on shore from the stern, the cable being long enough to veer in.

The boat guard should intrench themselves as soon as they land. In case of retreat, the first troops at the landing will relieve the boat guard, which will proceed to its boats.

In case of disaster, boat-keepers must be ready to sink such boats as are not needed by the fugitives.

Sometimes the shallowness of the water will not permit boats to land, or the only regular point of debarkation may be covered by the enemy's artillery, and the landing must be made elsewhere under circumstances which necessitate the use of a stage or float. Such a condition of affairs existed in the French operations before Sfax in Tunis, where the stage was made out of the topsail-yards of the line-of-battle ships, which were gotten into the water alongside, constructed into rafts, then towed separately near the shore, assembled together, and taken in under the direction of Captain Juge, whose report of this well-executed, delicate piece of work is as follows:

On Board the Marengo,
At Anchor off Sfax, July 18, 1881.

Admiral: I have the honor, in obedience to your orders, to report to you concerning the duty which was assigned me relative to the assembling of the floating bridge made in sections by the iron-clads of the squadron, and taking it ashore to assist in landing our men.

At 3 a. m. Saturday, July 16, the steam-launch of the Intrépide shoved off from the Marengo, towing the whale-boats placed at my disposition, each boat having an officer in charge. We steered for the gun-boats to whose care the different rafts had been confided the evening before. As soon as we arrived, the steam-launch took in tow the raft of the Marengo, which was to be the head of the bridge, and the others conducted by the whale-boats followed on behind, end to end. Under the supervision of the officers the lashings were promptly and securely made. The bridge being thus completed the whale-boats made fast along each side, and the steam-launch steering by the alignment of the two towers took us in to about 400 meters from the mole. At that distance I stopped and dropped a grapnel from the rear end, so that the steam-launch had only to tauten the tow-line to keep us on a line perpendicular to the beach; we thus offered the smallest target to the enemy, and at the same time we were in the best position to work rapidly. It was then 4.20 a. m., and we remained in that position during the bombardment.

When the launches and native boats were almost abreast of us, by order of Captain de Marquessac, I sent the whale-boats to tow the native boats, keeping one man of each boat's crew for the oars of the bridge. The grapnel was weighed, the steam-launch went ahead, and the men pulled at the oars, trying to maintain the alignment of the bridge. We were soon obliged to cast off the tow, and we hauled ourselves in by means of a grapnel carried out by the Trident's dinghy, and a small anchor which I had sent ashore by the whale-boat of the Marengo. The boats which landed first interfered with our movements somewhat. We finally, however, made our bridge fast after the Trident's boat had landed, and our bridge served for the rest of the expeditionary force.

I am, &c.,

JUGE.

The naval brigade should be a fleet affair; every vessel should furnish a factor of the whole, but there should be no such organization as is now generally furnished by our ships of war, where all the elements are more or less those of a parade on shore, and are not such as the best offensive use of a body of men would call for.

VII.

Mr. Crompton has the following novelty to offer in the use of the electric light for the debarkation of an army at night. He says:

> It may be often necessary, on account of a dangerous coast, or signs of approaching bad weather, that this operation should be carried on at the utmost speed by night as by day. All the apparatus for producing the current would be retained aboard the steamships. The conducting cable need only be passed on shore. Tripod stands, to carry the lamps, would be placed at convenient intervals along the beach. The whole arrangement for lighting a mile of fore-shore could be got into position, and the lights shown in less than an hour's work by squads of men properly trained with the apparatus. The most difficult operations, such as landing guns and horses, will be carried on as easily by night as by day. If extreme celerity were needed, it is not absolutely necessary even to land the lights, the lanterns may be hung in such urgent cases from spars rigged out on the steam tenders or launches; the dynamo-machines being worked as before on board the ships. A distance between the machines and the lights may be as great as a mile without causing the cable to be unnecessarily heavy. I have not dwelt on the advantages which the light gives for night signaling, for they are sufficiently obvious.

The German authority, whom we have quoted a few pages back, is not in favor of the electric light being used on board ship for the general illumination of the situation, since he believes that its glare hinders, rather than helps, the vision, and by this means the torpedo-boat of the enemy obtains an excellent target.

To be used at its best, the electric lights of the vessels of the fleet should fulfill the following conditions:

1. They should be grouped at some one point, as, for instance, by installing a number of lanterns in some vessel or vessels, or on some point of land, connected by means of cables with a sufficient number of ships to afford a current, which ships shall, if possible, be masked from fire.
2. The beam from the concentrated light should fall on the object to be illuminated, so as to make as nearly as possible a horizontal right angle with the line of vision of the observer stationed elsewhere.

CHAPTER XI.

DEFENSE OF THE COAST AND TORPEDO FLOTILLA TACTICS.

I.

Since every point on the coast can become a place of debarkation f an enemy's army; every town on the coast can be burnt and pillaged by the hostile fleet, or even by simple cruisers, it is necessary to distribute over several centers of action the different constitutent naval elements for the defense of this coast. These comprise rams, floating batteries, corvettes, gun vessels of different sizes, and the various classes of torpedo steamers.

These, in connection with shore defenses, must guard and protect those points from which our squadrons and cruisers can escape into the open sea, and to which they may retreat for asylum in case the enemy be too formidable.

These centers must be beyond the range of guns of greatest caliber, and should prevent, by their number and their distance inland, the enemy knowing what is going on.

The defense of a coast comes within two categories, a stationary defense and a movable defense. The first comprises submarine mines, booms, fortifications of every kind, placed beforehand or extemporized on the coast; the second relies on the action, isolated or combined, of rams, floating batteries, gunboats, torpedo-vessels, &c., supported, according to circumstances, by armored ships, or even the sea-going squadrons, should circumstances so conspire as to render necessary this combination for war remaining in its own waters.

Admiral Penhoat says that the best coast defense is a fleet of specially constructed armor-clads, capable of going to sea in any weather along a coast. Then each harbor should have its flotilla of torpedo-boats. These coast-defense vessels should have great battery power, draw little water, have good speed, and be nearly unsinkable. They will require but a small amount of provisions, rather small crews, little coal on board, and large amounts of ammunition. They should be accompanied by lookout vessels.

These opinions of the Admiral are also formulated in the marine policy of his Government, so that it, in common with many other European nations, has organized fleets to fulfill this purpose. This system of defense should especially appeal to a country which is self-supporting, has no food routes to keep open, is concrete, and which has a large extent of coast line requiring protection, such as is our own.

Captain Harris says that gun-vessels and gunboats, small steamers, and tenders, are especially useful for coastwise employment. They should be under the protection of larger vessels, and should not be trusted far from their bases. They, and the coastwise armored fleet, and the torpedo flotillas should do their utmost to annoy a menacing fleet, and prevent its anchoring and blockading any port. They must be careful, however, not to bring about a general engagement, or to be caught at sea and cut off. Non-seagoing armor-clads are, as a general thing, of more value than fixed forts for the protection of harbors.

Coast batteries cannot alone prevent an armored squadron from forcing a passage; they must supplement their guns by mines. Conversely, any mine which is not protected by a gun is harmless, as it can be raised or destroyed.

Captain Maubenge expresses the following opinion in regard to torpedoes:

> It would be hazardous to place too much confidence in torpedoes, notwithstanding the perfection they have recently attained, for seamen will often succeed in raising them, in cutting their wires, in exploding them at a safe distance from their ships, or, still better, will build the latter to be almost, or quite, indestructible by torpedoes. This method of construction is that of water-tight compartments, whose partial destruction does not endanger the existence of the vessel.

II.

In regard to the question, which is the best to employ, a gun-vessel fitted with torpedoes, or a torpedo boat to use to make an attack with auto-mobile torpedoes, it is conceived that the gun-vessel has the following advantages:

1. It is harder to disable.
2. It can be used in heavier weather.
3. It is not obliged to stop to discharge its torpedoes.

As far as the torpedo-boat is concerned, Mr. Fontaineau lays down the following points in its favor:

1. Probably great speed.
2. Smaller target than a gun-vessel.
3. Great handiness, little momentum.
4. In case of accident fewer people lost.

Should practice prove to be true, the common report that torpedo boats will not have to stop to fire their auto-mobile torpedoes, the advantage will, however, lie strongly with this class of vessel.

If obstructions are placed about a ship, they must be strong enough to resist the onset of a vessel of fair size. A ship constrained to remain anchored must thoroughly mine her anchorage ground with a regular system of submarine defense. The cables for electrical connections can be stopped to the chain and come in through the hawse-holes.

To render the attack as irresistible as possible the torpedo-vessels must possess the following qualities:

1. Great speed, so as to enable the boat to be in the field of fire as short a time as possible, and so diminish the risk of being destroyed.
2. Show as little surface as possible, so as to reduce to a minimum the size of the target for the enemy's guns.
3. Be divided into as many water-tight compartments as possible to prevent being easily sunk.
4. Have the vital parts as well protected as possible.
5. A possibility of using auto-mobile torpedoes without reducing speed.
6. Protection for the crew against small-arm and machine-gun fire.
7. Noiseless engines, so as to put off discovery as long a time as possible, and so be enabled to approach the enemy.
8. Great handiness.
9. Armament with machine guns, to allow fighting a vessel of the same size interfering with its designs.
10. Facility of being handled out of the water and transported.
11. The most unobtrusive painting and disguise, to prevent being seen by the enemy's search lights.

The best torpedo-boats now possess most of these *desiderata.* There are some officers who pretend that this stopping to discharge a torpedo is no defect, for it lasts for only a minute, and the torpedo is ejected before the battery can be concentrated. Possibly this is so, still the fact that it *need not be done* certainly adds greatly to the tactical worth of the vessel.

In considering the defense of the vessel from an attack by torpedo-boats, the details of the fitting of the multitude of ingenious inventions devised to meet this end are not entered into by Mr. Fontaineau. In regard to the artillery, however, he says that it must fulfill the following conditions. Each gun must—

1. Be easily trained, permitting it to follow all the movements of the enemy.
2. Be capable of rapid loading, so as to fire the instant the aggressor comes in sight, and to keep it up.
3. Have the projectile heavy enough to injure seriously a gunboat or sink a torpedo-boat.

III.

Towing and spar torpedoes, owing to the improvement in machine guns, are now rarely fitted except as an alternative armament, as only under the most favorable conditions will it be possible to approach sufficiently near to a vessel to use them under the terrible hail of missiles which could be kept up by her machine guns. The result is that, at present, all the torpedo-boats under construction are armed with the automobile torpedo, and nearly, if not all, of them are armed with machine guns, to enable them to fight other boats, and to distract the guns' crews ship they are attacking.

The tactical qualities of the torpedo-boat must be as well known as are those of the ship. They must have their turning circles and helm-angles determined, and their commanding officers must be perfectly familiar with them. Their turning circles will be very large for their length, owing to their shoal draught of water and lightness. For this reason to insure quickness of evolution, drop-rudders have been invented and fitted.

That these points must be well known is patent from the fact that torpedo-boats must always attack in flotilla. The torpedo-boat acting singly has no place in modern warfare. No success can be derived from independent action, as the assailed vessel will always be more than a match for each individual boat.

Admiral Penhoat, in discussing this subject, says that the torpedo flotilla should be composed of boats representing two classes; one class capable of going outside the harbor, and the other intended to act in smoother water. The flotilla should be ready to attack at all times, being moored in ambuscades; natural features of a harbor being taken advantage of, if possible, to effect this object. They should be organized on a section or group basis, and they should be accompanied by swift tenders armed with a heavy mechanical battery.

A large number of tacticians believe that the best formation for torpedo-boats to resist an attack on a friendly ship by torpedo-boats is probably in double line abreast or in alternate lines abreast. The first line to charge the enemy's line and come around quickly, all boats turning the same way. The second line to keep between the attacking boats and the beset ship. The vessel should keep up a fire over the line of her own boats nearest to her. The ship should be underway and perhaps stopped; the line of boats nearest her would soon resemble a cordon, and the outer line should concentrate on the most dangerous point of the enemy's attack. The ship should retreat as soon as she sees her way out of the danger.

An attack on a vessel by torpedo-boats should be made with the flotilla divided into two or three divisions; one of these should act as a reserve. This last should either dash at the ship when the other divisions are engaging her torpedo-boats, or they should follow the ship when she seeks to retreat. If the ship must retreat through a channel, it would be a piece of strategy to have her attacked at one or two points in her passage out; the first attack being intended to engage her torpedo-boats, and not to destroy the ship.

Let us consider an attack on a fleet lying off and on the mouth of a harbor, by a flotilla of torpedo-boats at night. The boats should be divided into two or more divisions. Each division will tow astern of a corvette or tender. The slowest boat of each division will be nearest the towing vessel, and will, in the attack, act as the reserve boat. The towing corvettes and the reserve boats should be supplied with rockets and signal lights. The lines should tow out the harbor, each line separating as soon as possible from the others and towing each to some spot at about equally estimated distances from the fleet to be attacked. One or two heavy vessels should move out to the mouth of the harbor. When the corvettes and the heavy vessels have reached their assigned positions, they should drop an anchor under foot and stand by to slip. These positions should be so chosen by the Admiral that the torpedo flotilla shall be given every advantage of shelter and cover. At a certain set time, the torpedo flotilla will cast off from the towing vessels and be towed by the reserve boat directly towards the enemy. As soon as he is discovered each boat will separate from the reserve and dash for him. The painters connecting the boats had better be of chain, and each end should be slipped and the chain permitted to sink, otherwise the whole exploit might miscarry through a fouled screw.

No special rule can be given for attack, other than that the lines should mutually support one another. Each commanding officer of a torpedo-boat should be thoroughly informed of the appearance of each ship of the enemy, and the disposition of her vulnerable points. When the attack becomes general, the reserve boats should dash in. If the enemy is worsted the corvettes and heavy vessels should approach the scene and help the torpedo flotilla with their search-lights and weapons of offense.

If the torpedo-boats are obliged to retreat, they will fall back on the corvettes, and since these are separated, the boats will stand a good chance of picking up one of them, which will afford them shelter. Their chances, indeed, would be greater of their doing this than if the corvettes were all at one rendezvous. The anchorages of the corvettes should not be farther apart than a quarter of a mile.

An engagement between small vessels, bringing out several tactical situations, occurred in Callao Harbor during the Chili-Peruvian war, an account of which is as follows:

> At 2.30 a. m., May 25, a Peruvian old-type steam-launch, that formerly belonged to the ill-fated Independencia, commanded by Lieutenant Galvez, with a crew of sixteen men, and armed with a Gardner gun in the bow and a 2-inch breech-loading rifle in the stern, came suddenly upon the Chilian steel Thornycroft torpedo-launch Guacolda, which had a speed of 11 knots and was fitted with three spar-torpedoes, one right ahead and one on each bow. The Peruvian started at full speed for the mole as soon as he made out his enemy. The Janequeo, a steel Yarrow torpedo-launch, with a speed of 18 knots, now appeared on the scene, and passing ahead of her sister boat exploded her bow torpedo under the Peruvian's counter; at the same moment Lieutenant Galves and Surgeon Ugarte exploded a torpedo on the Janequeo's bow, which opened a large leak and killed two men. Her commander, Lieutenant Senoret, managed to get her alongside of a lighter, where she sank. Lieutenant Goni, in the Guacolda, continued to chase the Independencia, which kept up a heavy fire from her small-arms and stern gun. At last the Peruvians, finding their launch sinking, ceased firing and surrendered. Goni sent his dingey to her rescue and succeeded in saving Lieutenant Galves, seriously wounded, and seven of the crew. It was not till this

time that Goni missed his consort; but thinking that she had returned to the fleet, he went back to the flagship, put the wounded and prisoners on board, and finding that the Janequeo had not returned went in search of her. As he approached the floating dock he met Lieutenant Senoret and his crew coming out in two small boats which they had picked up alongside of the hulk Callao.

Besides doing their legitimate work, torpedo-vessels will have to fight small adversaries barring their passage. As we have before observed, they may be the enemy's torpedo-boats, but again they may be picket launches, tugs, or even booms and other obstructions. These will have to be overcome by machine-gun fire, hand grenades, spar torpedoes, and necklaces, or mines of gun-cotton or some other high explosive. For this purpose torpedo-boats should be fitted with the necessary weapons, leading wires, and batteries.

The attack on a fleet at anchor will rarely occur. However, *should* such a condition of affairs happen, the boats should separate, and, acting in pairs or groups of three, take as many vessels as possible at the same moment, and make as many victims as they can in the least time.

CHAPTER XII.

THE CONCLUSION.

I.

Sir Thomas Brassey, K. C. B., says:

> The loss of the Grosser Kurfürst occurred undoubtedly from the want of practice in fleet-sailing among the officers of the German Navy. On the last-named occasion the squadron of four ships was reduced to *one* in forty-eight hours after leaving Wilhelmshaven. On the first night one of the ships grounded on a sand-bank. On the following day the collision occurred between the König Wilhelm and the Grosser Kurfürst.

The destruction of a large vessel represents the direct loss of about $3,000,000. Then there are incidental losses of officers, men, and material of war. To these may be added the capture of a tactical center or the laying under bonds of a large business capital through the failure of this vessel to appear and defend it, making the amount of money involved, rise to such a sum that the imagination fails to follow.

With the certain knowledge that ships of such size are, and will be, needed; with the certain knowledge that just such ships, when we have them, will be lost through collision and bad handling, is it not the bounden duty of the nation to prepare for this condition of things, and in the interests of economy to see that its naval officers are well instructed in practical tactics and the handling of ships?

To again quote Sir Thomas Brassey, we read:

> The history of not only our own Navy, but that of all other navies which have attained any importance in the world, from the most ancient times downwards, has shown that tactical efficiency and naval success went hand in hand, and that the absence of the former assuredly led to the want of the latter.

This knowledge can never be gained in the class-room, since theory will not make a seaman, even in the case of men who have an intuitive faculty for seamanship.

Admiral Randolph, writing a few years ago, asks the question in regard to his own service:

> Are we taking every pains, not merely to perfect our few employed captains in their art, but to train and habituate all ranks of executives in the practical management of ships? We cannot think that an affirmative reply can be accepted as satisfactory until a system is established under which, at least, every second in command, and every lieutenant of a certain standing (who may of course at any moment become so, or even in charge of the ship), is made fully competent to do so by experience in handling one, not only in ordinary navigation, but in narrow waters, and all fleet evolutions.

> Why should there not be a systematic course of practical maneuvers, including experiments in turning under difficulties in the shortest time and smallest space; in stopping dead from different speeds, and going astern, &c., through which every executive should pass, in vessels of any available size, from steam pinnaces to big armored ships (the larger the better, of course, but nothing is too small to be of great value), to be carried out abroad and at home, whenever opportunities occurred? If economists are alarmed let them soothe themselves! * * * At the worst, it would amount to little more than the necessary coal, the saving of which cannot be justified and might easily turn out not only a pernicious but a disastrous economy. Let the financier who considers this a wicked waste of money put his price on these two qualities, viz, skill and nerve, but don't let him expect to get them for nothing; * * * they require careful and constant cultivation, and if desired of the best quality, must be paid for at the highest price, like all other commodities.

What is true of the British Navy is true of our own. If we have fewer ships, a more disheartening system governing promotion, and no punishment for mental laziness, our duty is still plain! Harder, more precise work, a devotion to a specialty, is what is required!

Since the necessity for a navy will arise, if it has not already arisen, it is but fair to conclude that one will be set afloat. It will be the practically instructed officer in the science under consideration who will proudly lead our new fleet into action and to victory.

If this work is demanded of the officer, what duty devolves upon the nation? Primarily, to establish a graded course for practical drill. Secondly, to maintain a squadron of evolutions.

It is not proposed here to draw up a course of instruction. Such a course will be the result of great thought, consultation, a utilization of the means at hand and available, and a gradual elaboration from time to time.

Every officer must be given a chance to serve in the squadron after passing through the school of practical tactics.

On this subject Captain Colomb says:

> I therefore feel the greatest possible anxiety that further steps should be taken towards the establishment of a systematic method of training our younger officers in the practical work of handling our ships at sea. The gunboat trials in the Russian squadron are full of information; a vast deal of information is got out of very little experience in that way, and it could be very easily carried out a little further than steam-launches and gunboats by larger vessels, which need not ram each other, but spars or rafts towed astern.

II.

Several years ago a squadron of instruction was organized in Russia. Several gunboats are fitted with fascines as buffers to prevent injury from ramming, and tournaments are repeatedly held in the presence of the superior officers of the fleet. Each gunboat is maneuvered by the captain of an armor-clad assisted by one of his officers and his chief engineer. In this way every captain, in his turn, has a practical lesson in ramming and being rammed or avoiding it, which they could not with safety attempt in their large commands. "All day long, and every day, one or other of the armor-clads, taking it in turn, is underway, threading her way backward and forward through the anchored fleet. The captain who makes the closest shave, without touching, is highly commended."

Naval tournaments should take place at sea between protected gunboats. These sea sham-fights would throw much light on disputed points in the rule of the road, and settle in a week what the most experienced and practical seamen may go on disputing about for years.

Much, too, can be learned in the way of fleet tactics from exercise in steam-launches. The launches should be organized as a fleet, and the movements, after determining the evolutionary circle of each launch, be gone through with. After the captains are thoroughly conversant with the drill, then astern of each launch should be towed a cutter. The helm-angle of the launch should be made smaller, and the launch and its tow should be considered as one vessel. Distances and intervals should be made greater to correspond with the new length, and the flotilla, under the new circumstances, should be again drilled in evolutions. By veering the boats farther astern of the launches, decreasing the helm-angles, and increasing the distances and intervals, the system of tactics resembles that of the movements of large vessels in its application.

By this means commanding officers can be brought to know fully the amount of room required in which they can maneuver their ships. Of course this method of drill is at best a makeshift, and that amount of nerve required in the commanding officer, nowadays, is in no way developed.

No course of instruction in tactics will be complete without a thorough discussion in some graphic manner of the relation existing between opposing ships and fleets. We think this end will be best served by a study of "The Duel: A Naval War Game, invented and arranged by Captain P. H. Colomb, R. N." Without entering into the rules governing it, it may be said that the game is based upon two ships carrying guns the same in number, but differently distributed, according to the choice of the players. The ships make the same or different speeds, according to lot. All during the combat, founded either on artillery or the ram, both ships must keep up their speeds; that is, they can neither slow, stop, nor back, and they must always use the same amount of helm in turning, so that each ship's turning-circle has an invariable diameter. There are different values for each gun when fired, and the battle is decided when one of the ships is rammed, kept under artillery fire, which she cannot adequately return, or when she is driven on shore or into neutral waters. We see here different speeds and varying helm-angles, for each ship is excluded from the game. The distinguished inventor, however, promises that they will be introduced as soon as sufficient authentic *data* is obtained bearing on these points. We can easily see that the sphere of this game, between experienced players, could be so enlarged as to include combats between fleets. Under all circumstances, whether played in its present simple state or whether elaborated into something very much greater, it should be found in the hands of every naval officer, who is interested in the highest and most conspicuous branch of his profession—the meeting and vanquishing of an enemy in a fair fight on the open sea.

Whilst this book is in preparation, the English are considering the necessity of following out the Russian system of drill. A class of gunboats is proposed, protected where necessary with buffers, going at a slow rate with low steam pressure, and using a small helm-angle. The idea is to make them unhandy in their movements, so as to resemble somewhat larger ships in their evolutions.

III.

The run across the Atlantic from New York to Queenstown is now made in a little more than six days. Nearly every week some new vessel distinguishes herself by her quick trip. Comparing the one which first made this great speed with the last one, we see a great gain in the expenditure of coal; so much less being burnt per ton of displacement, and larger runs being made on individual days.

In the near future we shall see an ordinary sea-speed of 20 knots maintained. If, now, this will be the speed of merchant steamers, there must be a cruiser class put afloat which will at least be their equals in speed, and their superiors in length of time in which they can keep the sea.

The tactician may well stand appalled at these immense speeds. What formations can be used for the ordinary purposes of navigation? In what order will the attack be made? What system of evolutions will be followed? And so on through the whole list of tactical requirements.

We fancy these questions can only be answered in a very general way. Any improvement in speed or turning power, or means of warfare, simplifies formations and evolutions, but enjoins greater complication upon the mutual duties of ships. It also causes a decrease in the number of ships which can with safety be set to act together. It may be that the number of vessels which can be combined will be only four, if, indeed, it is not two. Distances and intervals will perhaps be greater. The time during which a fire will be effective will last for only a few seconds. Then, again, the amount of sea traversed, after a charge, before a turn can be made, will be so great that a fight will only be possible on the open sea or in wide estuaries, between other than single ships.

The question now arises, since ships will be in a fight such a short time near together, what kind of guns will be used, and what will characterize the modern ship of war fitted for the line-of-battle? To us it looks as if the coming ship would be, as regards her hull, nearly, if not quite, torpedo-proof through numerous water-tight compartments coming up to the spar-deck; have her engines, boilers, and controlling officers protected; a large number of guns of moderate or even small caliber; labor-saving machinery everywhere, and therefore a small crew; no torpedoes; auxiliary rudder; and guns or tubes for firing some sort of high-powered explosive. She should also have a capacity for *full sail-power;* ordinarily to be barquetine rigged, with generous fore-and-aft "schooner" sails (lashed on the foot to booms, and not try-sails), with yards ready to go aloft and square sails to bend and set.

In conclusion, it may be mentioned that the foregoing pages have not been written with any idea of exciting controversy, but to refreshen the line of thought upon a subject which is at present engaging the minds of the officers of the navies of most foreign Governments. It may be, that enough has been drawn from the works of others to stimulate an endeavor to develop scientific research in a direction at once very interesting and vitally important.

1

1

2

3

5

6

7

8

9

10

11

12

13

14

15

16

17

18

20

22

23

24

25

INFORMATION FROM ABROAD.

PUBLISHED BY THE OFFICE OF NAVAL INTELLIGENCE.

WAR SERIES.

I.—Operations of the French Navy during the recent war with Tunis, 1881. Translated from L'Année Maritime. (Edition exhausted.)
By Lieutenant M. FISHER WRIGHT.

II.—The war on the Pacific coast of South America, between Chili and the allied republics of Peru and Bolivia. (Edition exhausted.)
Lieutenant T. B. M. MASON.

III.—Report of the British Naval and Military Operations in Egypt, 1882. Part I, text. Part II, plates. (Edition exhausted.)
Lieutenant Commander CASPAR F. GOODRICH.

GENERAL INFORMATION SERIES.

I.—Observations upon the Korean coast, Japanese-Korean ports, and Siberia, made during a journey from the Asiatic Station to the United States through Siberia and Europe, June 3 to September 8, 1882.
By Lieutenant B. H. BUCKINGHAM and Ensigns G. C. FOULK
and WALTER MCLEAN.

II.—Reports on the Exhibits at the Crystal Palace Electrical Exhibition, 1882.
By Ensign F. J. SPRAGUE.

III.—Examples, conclusions, and maxims of modern naval tactics, 1884.
By Commander W. B. HOFF.

NOTICE.

The office of Naval Intelligence will furnish the above publications until the editions are exhausted, upon the personal application of officers.

The office of Naval Intelligence will assist officers in obtaining information printed by the Government.

Officers are earnestly requested to send to the office of Naval Intelligence late information in any form.

U. S. — Office of naval intelligence

General Information Series, No. IV.

INFORMATION FROM ABROAD.

VII. 2662

PAPERS

ON

NAVAL OPERATIONS

DURING

THE YEAR ENDING JULY 1885.

GENERAL INFORMATION SERIES, No. IV.

INFORMATION FROM ABROAD.

PAPERS

ON

NAVAL OPERATIONS

DURING

THE YEAR ENDING JULY, 1885.

NAVY DEPARTMENT,
BUREAU OF NAVIGATION,
OFFICE OF NAVAL INTELLIGENCE,
1885.

WASHINGTON:
GOVERNMENT PRINTING OFFICE.
1885.

VII. 2662

1885. Oct. 12.

Engd

The Bureau of Navigation

INTRODUCTORY NOTE.

The following papers, made up in great part from the reports of officers, descriptive of the more important naval operations of the past year, are published for the information of naval officers.

The action at the Pagoda Anchorage, in the Min River, furnishes the only example of a fleet engagement since the battle of Lissa, and while it throws no additional light upon the interesting and vexed problem of Tactics it illustrates the effect of gun and torpedo, and draws attention to the preparations for action on board vessels in the French fleet.

The successful attack on two occasions by torpedo boats armed with spar torpedoes make it clear that our only service torpedo is not to be wholly condemned, even in comparison with the Whitehead whose field of usefulness is much more extended.

The operations of the United States Naval Brigade on the Isthmus of Panama, aside from the public interest in the results accomplished, and the landing of a brigade of 660 officers and men from the North Atlantic squadron on Gardiner's Island for instruction, should direct attention to the absolute necessity of a complete and uniform organization for landing parties and brigades, so that each vessel of a squadron, or any assemblage of vessels from different stations, may be prepared at an hour's notice, or upon the display of signal, to land its contingent, properly equipped and instructed, to take promptly, and without special directions, its place in the battalion or brigade formation.

The value of instruction, such as was given on the occasion of the landing at Gardiner's Island, cannot be overestimated.

The notes in Chaper IV present facts in reference to the design or performance of vessels recently laid down, launched, or completed, and a description of the latest improvements in other implements of naval warfare.

CONTENTS:

Page.

Chapter I. The French naval operation in China. 1884–85 9

Chapter II. The United States Naval Brigade on the Isthmus of Panama..... 41

Chapter III. The landing of the naval brigade of the North Atlantic Squadron on Gardiner's Island, August, 1884 101

Chapter IV. Notes on the most recent design and performance of vessels and other implements of Naval warfare 111

DESCRIPTION OF PLATES.

PLATE I.—Plan of Foo-Chow.
II.—Map of Min River.
III.—Plan of city of Panama.
IV.—Map of the Panama Railroad.
V.—Armed car arranged by Lieutenant Kimball, U. S. N.
VI.—Armed car arranged by Lieutenant Kimball, U. S. N.
VII.—View of Aspinwall and the landing of a portion of the Tennessee's men.
VIII.—View of Aspinwall and the landing of a portion of the Tennessee's men.
IX.—The garrison at Matachin.
X.—Post No. 3 at Aspinwall.
XI.—Plan of camp on Gardiner's Island.

FRENCH NAVAL OPERATIONS

IN THE

MIN RIVER, CHINA,

AUGUST, 1884.

PREFATORY NOTE.

To understand the reasons for the bombardment of the arsenal of Foo-Chow, it is necessary to go far back in history. Before the Christian era China conquered Tonquin and Anam, but in the fifteenth century the Anamites obtained their independence, although the Chinese have always claimed sovereignty since. In the seventeenth century the French Jesuits went to Cochin-China, or Anam, to proselytize, and were followed by traders and politicians, until toward the end of the eighteenth century France obtained a small territory in Tonquin, a province of Anam, in sovereignty. This has since grown steadily. As a result of a war between the French and the Anamites, a treaty was made in 1874 recognizing the protectorate of France over Anam, and the latter's independence of China. In 1880 the Emperor of Anam claimed Chinese assistance to put down a rebellion, thus acknowledging Chinese sovereignty. In July, 1881, the French ministry asked a credit to maintain order in Tonquin, and in 1882 Captain Rivière was assigned to the command of an expedition to punish the rebels. The mandarins, however, were so unfriendly that Rivière found himself obliged to attack them and capture the town of Hanoi. This act was disavowed by the French authorities, and a period of inaction followed, during which the number of Chinese in the country greatly increased, and France found herself really opposed to the Chinese Government. In May, 1882, a reconnaissance of the French was defeated and Rivière killed. Troops were sent from France and placed under the command of Admiral Courbet, who was also in command of the naval forces. After some successful operations on the part of the French, Anam submitted and a treaty was made. This treaty left France and China opposed as to the protectorate of Anam, China being unwilling to yield her claims. China had not withdrawn her troops from Tonquin, and announced that a French occupation of certain towns garrisoned by Chinese would be cause of war. The French did occupy these towns, but the convention of Tien-Tsin settled matters peaceably. The convention secured France in her advantages and stipulated for the withdrawal of the Chinese troops, while France renounced her claims to an indemnity. When the French expeditionary troops were ready to return home, a small French column was sent forward to occupy Langson, which should have been evacuated by the Chinese. The Chinese had not yet withdrawn and a fight followed, upon which France demanded a large indemnity. This was finally refused, and France began a course of reprisals without declaring war formally. This brought about the bombardment of Foo-Chow.

EXTRACTS FROM REPORT OF REAR-ADMIRAL DAVIS.

* * * * * * *

At the time of my last communication of the 18th instant, the French and Chinese squadrons were still at Pagoda anchorage, awaiting the result of pending negotiations. On the 20th the news arrived that the French chargé d'affaires at Peking had given the Chinese Government forty-eight hours to promise to pay the sum of 80,000,000 francs indemnity, otherwise he would haul down his flag and negotiations would be stopped. It was further reported that the Chinese had emphatically declared they would not pay.

Vice-Admiral Dowell and I had agreed to send up more men to Foo-Chow in the event of an engagement at Pagoda anchorage, and Commander Barker, of the Enterprise, had instructions to send his at the same time that the British went up. On the morning of the 22d Vice-Admiral Dowell asked Vice-Admiral Courbet's opinion as to the advisability of sending them that morning, and was advised not to lose that morning's flood-tide. Vice-Admiral Courbet further stated that he had not as yet received any instructions to commence hostilities, but that one of his gunboats, the Lynx, was at the termination of the wire at the mouth of the river, and might arrive at any moment. At 1 p. m. our men from the Enterprise and the British from the Champion, Sapphire, and Vigilant arrived here. The British landing force was thereby increased to 200 officers and men and 2 howitzers and 1 Gatling. The Enterprise sent a force of 90 men, 7 officers, and 1 Gatling, increasing our landing party to a force of 165 officers and men and 2 Gatling guns. All our men were comfortably quartered on board the Monocacy, and immediately upon arrival organized. The 34 marines were divided into two detachments, and the blue-jackets into three companies of infantry and two Gatling-gun crews, also a party of 8 pioneers, and an ambulance party of 4.

* * * * * * *

On the morning of the 23d the French consul here notified all his colleagues that France not having received reparation for the breach of the Tien-Tsin treaty on the part of the Chinese at Langson, Vice-Admiral Courbet had received instructions to commence hostilities in the Min River, and that he (the consul) had hauled down his flag. I subsequently learned that Vice-Admiral Courbet had sent a similar letter to Vice-Admiral Dowell and Commander Barker, notifying them that he would commence hostilities that day, and requesting them to notify any neutrals that might be on shore.

* * * * * * *

The Vice-Admiral commanding-in-chief the Naval Divisions of Tonkin and the China seas to the captain of the American Corvette Enterprise.

VOLTA, PAGODA ANCHORAGE,
August 22, 1884.

SIR: In the absence of Admiral Davis and of any American consul at Pagoda, I have the honor to inform you that the French Government, having been unable to obtain from China the reparation which it demanded on account of the affair of Langson, has ordered me to retaliate in the Min River. I shall be indebted to you if you will warn the American merchantmen in harbor and also the American residents at Pagoda.

Receive, sir, the assurance of my most distinguished consideration.

A. COURBET.

REPORT OF LIEUT. H. MORRELL ON THE PREPARATIONS MADE BY NAVAL BRIGADE OF U. S. S. MONOCACY AND ENTERPRISE FOR DEFENSE OF AMERICAN LIFE AND PROPERTY AT FOO-CHOW, AUGUST, 1884.

I have the honor to make the following report in regard to the preparations made for the protection of American, English, and other neutral property at Foo-Chow. A plan of the settlement of Nantai is appended.

The Monocacy arrived off Nantai on the 3d of August, and took her position, as indicated in the plan, abreast the custom-house and about 80 yards from the Bund. The English gunboat Merlin, 430 tons, with a crew of 70 men, under the command of Lieutenant-Commander Brenton, R. N., had arrived on the 23d of July and was moored off Jardine, Matheson & Co.'s, about 75 yards E. by N. of this vessel. There were also 80 men from H. B. M. S. Champion, with 1 7-pounder field-piece and 1 long Gatling gun, quartered on 2 cargo-boats anchored near the Merlin. Several house-boats were used for the accommodation of the officers in charge of this detachment.

Preparations were at once made for landing. An officer was stationed at the United States consulate with an outfit for day and night signals and a special code of signals was prepared to facilitate communication. Officers were directed to acquaint themselves with the settlements, particularly with the routes to be used and places to be protected.

As in the event of an outbreak it was imperative that the detachments should reach the different points assigned with the least possible delay, and as the streets were narrow and crooked, and provided with barricades liable to be closed at any moment, it was deemed necessary to transfer to the shore whatever might retard the movement of the men. Accordingly the Gatling gun was dismounted and carried in pieces to the consulate, and the 4 signal-men detailed to remain at the consulate took charge of it. The reserve and Gatling gun ammunition was distributed as follows: At Hedge & Co.'s, 1,000 rounds; at Russell & Co.'s, 1,000 rounds; at consulate, 3,080 for Gatling gun and 1,000 for rifles; at American Missionary Compound, 1,000 rounds. These preparations were made as quietly as possible to avoid alarming the natives, who had been very restless since the arrival of the French at Pagoda anchorage on the 14th of July. Twenty rounds of ammunition were issued to each man. Eight of the Gatling gun's crew were armed with rifles, provided with slings made of canvas; the remainder with revolvers and cutlasses.

The Blue-jackets were not supplied with knapsacks and canteens. The want of these in actual service would undoubtedly be felt, especially the latter as water in this country cannot be used without endangering health. The cartridge-boxes furnished were not efficient; the leather, after a little service, loses its stiffness, and the cover bends up and the box down, leaving a space large enough for cartridges to pass through. In my opinion, this cartridge-box should be changed for another of a better and more reliable pattern.

* * * * * * *

On the 22d, Admiral Courbet having announced his intention of commencing hostilities the following day, the English and American re-enforcements proceeded to Foo-Chow.

The Enterprise's landing party numbered 84 men, organized as follows: Lieut. Commander G. M. Book, commanding; Surgeon H. N. Beaumont; first company, 23 men, Lieut. H. Osterhaus, Ensign Rohrbacker; second company, 23 men, Lieutenant Hodges; Gatling gun's crew, 16 men, Ensign C. N. Atwater; marines, 18 men, Ensign C. A. Gove; pioneers, 4; nurse, 1; stretcher-bearers, 2. This body was supplied with 18,000 rounds of ammunition. The men were provided with blankets, but not with knapsacks or canteens. The accommodations for this extra force were ample, and had hammocks been provided the men would have been as comfortable as on their own ship.

The Monocacy's battalion was now reorganized as follows: Lieut. F. W. Nichols, commanding; Passed Asst. Surg. E. Norfleet; first company, 30 men, Lieut. H. Morrell, Ensign H. Kimmell; Gatling gun's crew, 16 men, Ensign J. H. L. Holcombe; marines, 16 men, Lieut. M. L. Wood; pioneers, 4; nurse, 1; stretcher-bearers, 2.

* * * * * * *

In case of landing, the Enterprise's first company was to occupy Russell & Co.'s and Hedge & Co.'s, with Lieut. H. Osterhaus at the former place and Ensign Rohrbacker at the latter. The remainder of the force was to land at the custom's steps, abreast the ship, and, with Monocacy's battalion leading, was to advance by the route marked —·—·—— on the plan, Plate I, to the consulate. One company was then to be detached and sent to the Missionary Compound. The marines and Gatling guns were to defend the consulate, the rest forming a reserve to be sent wherever required.

The English landing force consisted of 190 men, and were stationed as follows: 30 blue-jackets at Jardine, Mathison & Co.'s, 30 at Bathgate & Co.'s hong near bridge; and at the English consulate, 60 marines, 20 blue-jackets, one 7-pounder, one Gatling gun, and one Gardner, with their crews, 50 men, 36 of whom were armed with rifles.

Between Foo-Chow and the mouth of the Min, according to the Chinese, 60,000 men were stationed in the different forts and camps; 30,000 of these were raised in Kwangtung (Swatow and Canton), Hunan, and Hupeh, the remainder belonging to this province, Fukien. These formed as many factions as there were provinces represented, and entertained the most bitter feelings toward one another. They were, as a general thing, well armed and poorly disciplined, and to their friends a source of greater danger than to the enemy. Before the French commenced operations it was considered quite probable that, in the event of a bombardment of the forts and camps, the soldiers on the right bank of the river would make their way in a disorganized and disorderly condition through the settlement of Nantai, across the bridge to Foo-Chow, and, after the fashion of Chinese braves, loot and commit other outrages on the way. That this was expected by the people was evidenced by nearly one-half of them fleeing to the mountains.

It was therefore necessary to make preparations to prevent the rush of a mob across the bridge from Foo-Chow and to check any riot or disorder caused by troops during a retreat. Ample provision was made to meet the first emergency, the bridge to the southward of Chung-Chow being commanded by a cross-fire from Bathgate & Co.'s hong near bridge and the British consulate, and if necessary by an enfilading fire from the hill about 50 feet east of the Club, while the Monocacy and Merlin controlled the bridge to the northward of the island. The second, however, was more difficult to contend with. An orderly retreat could not be opposed, and whether it would be disorderly or not could not be determined until the fugitives were actually in the settlement.

The dispositions before mentioned seemed the best that could have been made with the force at hand, in order to exert the best influence on a rabble.

The preventive measures taken and heretofore described having had the desired effect of preventing any outbreak on the part of the mob, it resulted in there being no occasion to land men. By the 4th of September there being no appearance of disorder and affairs having settled to their normal condition, Vice-Admiral Dowell and Rear-Admiral Davis considered the further display of additional force unnecessary, and the re-enforcements were ordered to rejoin their ships.

REPORT OF VICE-ADMIRAL COURBET, COMMANDER-IN-CHIEF OF THE SQUADRON OF THE EXTREME EAST, TO THE MINISTER OF MARINE AND THE COLONIES.

MATSU, *September* 11, 1884.

SIR: I have the honor to forward you an account of the operations carried out in the Min River by a part of the forces under my command.

On the 22d, about 5 p. m., the order to open fire was received by telegraph.

The following ships were off the Pagoda: The Volta (flying my flag), the Duguay-Trouin, Villars, D'Estaing, Lynx, Vipère, Aspic, and Nos. 45 and 46, torpedo boats. The Chinese had assembled eleven men-of-war; that is, one cruiser, five transports, a dispatch boat, a dispatch gun-vessel, and three gunboats. Besides they had twelve large war-junks, seven steam torpedo launches, three or four pulling torpedo boats, and some fire-junks.

The Chateau-Renaud and the Saône were anchored at Quantao, at the Kimpai Pass, with orders to prevent the obstruction of this channel, either by the sinking of some thirty stone-laden junks which had been collected there, or by the sowing of torpedoes.

There were also at the Pagoda anchorage, but further down, three English men-of-war, the Vigilant (flag-ship of Admiral Dowell), the Champion and Sapphire, the American corvette Enterprise, and some merchant steamers and sailing ships.

The French vice-consul at Foo-Chow, whom I had asked to come on board the Volta in good time, was immediately informed of the Government's decision, and went up to Foo-Chow to haul down his flag and warn the viceroy and the other consuls that fire would be opened the following morning. On my part I informed the English admiral that evening, and the captain of the Enterprise early the next morning, and asked the English vice-consul at Pagoda to warn the merchant ships. The greater part of these had, like the men-of-war, already anchored outside the probable line of fire.

On the morning of the 23d M. Bezaure returned, informing me that his flag had been hauled down; that at 8 a. m. the consuls, and at 10 a. m. the viceroy, would all have been warned of my intentions. This was a mere formality, because on the 22d everyone knew that I would open fire the next day.

All preliminaries being arranged, it remained only to select a favorable moment for destroying the ships and war-junks, and the flanking torpedo boats, before attempting anything else. The first of the ebb was thought the best time for accomplishing this first object in view of the respective positions of the squadrons, and of having to maneuver in a narrow channel where the strong currents made movements difficult. As the ebb began several hours after the viceroy and consuls were officially warned, I set 2 o'clock as the time for beginning operations.

From early morning the vessels on both sides had their fires lit and were ready to slip and get under way. While the flood was making, from 9.30 to 1.30, the Chinese were clearing for action and getting ready to weigh, and several of their torpedo boats ran down to the Volta, making false attacks, but retired upon pointing a gun or Hotchkiss at them. At 1.45 I made signal to weigh and to be ready to carry out the plan of attack. My plan was as follows:

Upon beginning the action the torpedo boats Nos. 45 and 46 were to attack the Foo-Poo and Yung-Woo, being supported by the port battery and riflemen of the Volta; this vessel was to open fire with the starboard battery upon the war-junks who chiefly threatened her. At the same time the three gunboats, Aspic, Vipère, and Lynx, leaving the Volta, the torpedo boats, the Foo-Poo, and Yung-Woo on the starboard side, were to run up quickly abreast the arsenal and attack the three gunboats and three transports lying there. Four steam launches under Lieutenant Lapeyrère were to protect the Volta, Aspic, Vipère, and Lynx against the Chinese torpedo launches.

The Duguay-Trouin, Villars, and D'Estaing were to attack, with one battery, the three ships near them, while raking the junks and a battery of three Krupp guns which commanded the arsenal with the other. Their armed steam launches were to defend them from the enemy's torpedo boats. As soon as the three vessels ceased firing the D'Estaing was to go to the mouth of the little channel by the custom-house to sink some junks which were said to be armed for boarding.

The plan was carried out in every particular. All the ships opened fire as the torpedo boats attacked; the Chinese replied immediately. The air was almost calm, and for a few minutes a cloud of smoke surrounded the combatants and a shower of projectiles whistled about them. As soon as the smoke lifted we saw the Yung-Woo ashore, having been destroyed by No. 46, Lieutenant Douzans commanding, and several sinking war-junks; the Foo-Poo, struck by No. 45, Lieutenant Latour commanding, but less seriously hurt, was still resisting. The other ships seemed already greatly damaged.

The Fei Yuen, Chi-an, and Chuen-Wei, dismasted and on fire by the shells of the Duguay-Trouin, Villars, and D'Estaing, were drifting with the tide; they grounded, and then sank some miles down the river. A little later the same end befell the two alphabetical gunboats.

After the first set-to the fire sensibly slackened, and our well-pointed guns soon destroyed the Chinese fleet.

Owing to the light draught of the Yung-Pao and Yei-Sing, these boats ran up the river where our gunboats could not follow them. Their injuries, however, were such that both of them grounded and afterward sank. This was the end of the Chinese squadron.

Our gunboats now gave their attention, first to the ships lying at the arsenal and then to the arsenal itself, while the other ships silenced the batteries at the arsenal and at the Pagoda on the island of Losing.

The Triomphante arrived a little after 2 and anchored below Pagoda, opening fire upon points within range, but principally upon the Pagoda batteries. By a shell from thence two men of the Volta were killed, and my flag-lieutenant, M. Ravel, and three men were wounded.

The torpedo boats which had armed the day preceding and on the morning of the action had been threatening us disappeared just before its commencement and sought refuge, some up the river and others in the channel of the custom-house. Lieutenant Lapeyrère tried in vain to reach them, and then turned his boats upon the Foo-Poo, which would probably have succeeded in getting up the river. He took her by boarding, and ran her aground below the anchorage, where she sank.

Late in the afternoon our armed boats dislodged the torpedo boats sheltered in the little custom-house channel, and at the same time they destroyed the junks and sampans which seemed to be prepared as fire-ships.

Foreseeing that the Chinese would attempt to surprise us during the night with their remaining fire-ships, I caused my ships to anchor at such a distance as to allow them time to weigh and save themselves.

These precautions were also necessary, as the burning hulks of the destroyed ships ascended with the flood and drifted out again with the ebb. There was also reason to expect torpedo boats, and they did appear. The night of the 23d–24th was one of constant alarms; most of the vessels had to weigh three or four times. Nevertheless, the attempts of the Chinese resulted unfavorably for them. About 9 p. m., at the end of the ebb, the Chuen-Hung, fired by our shell, was shoved toward our anchorage by two large junks, manned by some thirty men. A few shot from the D'Estaing, our picket ship, sank the junks with their crews, but the transport continued to drift with the current, threatening in succession several vessels.

On the 24th my first object was to finish the destruction of the junks and of the burning fire-ships which lay in the custom-house bay and above the arsenal. Two divisions of boats were sent for this purpose, one in charge of M. Peyronnet and the other of M. Lapeyrère.

I weighed with the Volta and the three gunboats to support the second division, and also to complete the destruction of the arsenal.

By the afternoon our 28-kilogram shells had destroyed all that they were equal to attempting. The direct fire upon the offices, shops, and a cruiser building did much damage, but not all that I wished. With guns of 14 centimeters it was impossible to do more.

The foundry, designing office, and office of precision were considerably injured. The hull of the cruiser was peppered with holes, but this caliber (14 centimeters) was not large enough. I should have had 24 centimeters, or at least 19 centimeters; in other words, I needed the Triomphante or the Duguay-Trouin, but the pilots declared it impossible to bring them within range even for an hour before and after high water, and soundings made by M. Renaud with this object in view confirmed their statement.

On the morning of the 25th I confined myself to taking by assault, with the landing parties of the Duguay-Trouin and Triomphante, the battery of three Krupp guns at Pagoda. Its garrison abandoned it upon the approach of our people, but we soon saw a great number of troops descending from the neighboring heights. The fire from our boats and some 14-centimeter shell kept them beyond the sandspit which at half-tide joins the island of Losing to the mainland. At 10 a. m. the boats and landing parties returned, bringing the three guns.

Nothing more could be done at Pagoda with the means at our disposal. I left the Volta and hoisted my flag on the Duguay-Trouin. After the men's dinner all the squadron weighed in order to destroy the forts on the river.

At 1.30 we anchored above Cuding Island and cut the telegraph line which connects all the forts with the arsenal and with each other. The next step was to destroy a casemate battery armed with an Armstrong 21½-centimeter gun (No. 12 fort), which commands the Mingan Pass. Only the guns of the Duguay-Trouin and Triomphante were heavy enough to be effective, but in less than an hour the fort, being taken in rear, was much damaged, and the guns on Cuding Island were silenced. A few well-pointed 14-centimeter shell convinced me they were abandoned.

The landing parties of the Villars and D'Estaing, under M. Sango, were sent ashore to support some torpedo men who were ordered to destroy the Armstrong gun with gun-cotton. Strong eddies in the river and the insufficiency of our steam launches made it difficult to put these parties ashore, but the Chinese did not think of disturbing them, and at nightfall they all returned.

The next day, the 26th, the other batteries of the Mingan Pass were attacked. The Duguay-Trouin and Triomphante, although giving most of their attention to the five casemated batteries, delivered several very effective broadsides against the other works. The Mingan battery made some resistance, but the shells of the Villars and D'Estaing soon disabled it, after which a party of torpedo men, supported by a landing party under M. Le Pontois, destroyed the guns.

The work was scarcely finished when a brisk musketry fire broke out from the neighboring heights where is the house of the Tao-Tai-Fan, in charge of the river defenses. Our boats promptly replied, and were aided by some 14-centimeter shells and a few rounds from the Hotchkiss guns of the Villars and D'Estaing, which dispersed the enemy.

At the same time the Volta and the three gunboats which had anchored near the Cuding forts supported another party of torpedo men and landing party under Lieutenant Fontaine, who was ordered to destroy the magazines and guns of this fort. As on the day before, the party was not disturbed.

The Duguay-Trouin and Triomphante destroyed the other batteries, noticeably one of the casemated ones on the right bank, protected by fifteen thicknesses of 2-centimeter plates solidly fastened together (No. 10 fort). The garrisons of these forts abandoned them and fled to the neighboring mountains, whence those who showed themselves were dislodged by our small arms and Hotchkiss guns.

Before night our torpedo men had destroyed the six guns in casemates on the left bank and two of those on the right bank. The next morning the rest were destroyed, but that required some hours, so that we could not weigh before the tide turned flood, or about 1 p. m.

About 2.30 all the ships had joined the Chateau-Renaud and the Saône, above the Kimpai Pass, where they had been on the lookout. This was easy enough in the daytime, but offered considerable difficulty at night.

They had to leave their anchorage off Quantao and send out picket boats, making great use of the electric search light, but they were successful. The stone-laden junks were collected under the right bank and the raft for completing the obstructions was grounded on the other side.

Captain Boulineau made all the preparations for destroying the junks, and his boats, supported by the Vipère and Aspic, undertook the operation. The intrenched camp at Kimpai opened a sharp musketry fire, but did not succeed in preventing the destruction of the junks, which were all sunk or burnt by 6 o'clock. Lieutenant Bouet-Villaumez was killed here and Sub-Lieutenant Charlier and several men of the Vipère were wounded.

At the same time the cruisers bombarded the camps in sight, and the Duguay-Trouin and Triomphante ran down below the Middle Ground to reconnoiter the defensive works and begin the attack. Upon their approach two batteries of 14-centimeter guns, recently erected to rake the channel, opened fire. In less than half an hour these batteries were silent, but they were not dismounted, and this was put off till the next day, as it was then necessary to go above the Middle Ground to find a convenient anchorage for the night. Putting aside the safety of the ships, I had to consider that of the crews, as had I remained at the open part of the pass, close to the left bank, commanded by the hills, the enemy's sharp-shooters would have caused me serious losses. We perceived on the following day that our precautions had not been excessive.

On the 28th, at 4 a. m., the Duguay-Trouin and Triomphante weighed anchor, and at daylight opened fire on the two batteries attacked the previous day. These replied at first with some vigor, but they did not last long. The Chinese preferred to depend chiefly on small-arm fire, but the ground was remarkably favorable to that mode of fighting.

On the right bank earthen walls about breast high with loop-holes, and on the left bank bushes and the village of White Fort fort gave shelter.

Our 14-centimeter and Hotchkiss guns slowly dislodged them. We saw them run toward the camp of Kimpai on the other slope of the mountain. A lucky shell blew up the magazine and completed their disorder. At first the village on the left bank offered them a refuge, but they were soon driven out by the flames.

All this time the heavy guns were breaching the battery protected with 15-centimeter armor and the casemate battery of the White Fort, and dismounted all the neighboring guns mounted in barbette, of which the principal was a 21-centimeter Krupp gun commanding the seaward approaches. I finished the work by bursting the guns with gun-cotton.

On the right bank we destroyed half a dozen pieces, but the musketry fire from the heights of Kimpai recommenced, to which we replied, without succeeding in subduing it entirely.

Besides this the landing places on the left bank were sown with electrical torpedoes of which we could not find the wires. The Triomphante exploded two or three with her Hotchkiss guns. Our landing parties would certainly have suffered greatly here, and the results to be obtained by them not being worth the probable loss, I decided to go on. On the left bank there still remained batteries Nos. 5 and 6 and fort No. 1 to be dismounted.

No. 5 battery seemed abandoned, and after a few shots I sent to destroy its guns The work was interrupted by a few chance shots from No. 6, which was out of effective range, but at the same time a large body of soldiers came down from No. 2 fort and caused us some loss. Captain Sango, in command of the party, was wounded, and two officers and eight men who could not rejoin their comrades sheltered themselves behind the sides of a steamer which was ashore in the vicinity. Our shells soon cleared the ground. I sent the Aspic and Lynx to anchor to the east of No. 5 battery, where they swept the valley leading to No. 2 fort. Under this cover an armed boat brought back uninjured the party that had been cut off. At the same time the interrupted work of the previous day was finished by destroying the three guns. Battery No. 6 and fort No. 1 were still uninjured, but they caused me no uneasiness, as I was sure of dismounting their guns without difficulty.

The evening of the 28th we reached an obstacle which, by the best authority obtainable, might be very serious. For a long time a line of rafts had been lying between Pass Island and Salamis Island, but so as to leave a passage on this side. The pilots said these rafts had electric torpedoes on board. We found them in the same position as a month before and the channel seemed as clear as ever it was.

Nevertheless we saw some buoys recently laid down, and on the 25th a German steamer, carrying troops, had been warned not to approach without a pilot from Kimpai, and, from various sources, I had reason to fear the presence of torpedoes. It was necessary to make sure of this before trying to cross the line, no matter what time should be consumed. Besides, from the place where the Duguay-Trouin and Triomphante were lying, I was in telegraphic communication with Sharp Peak, as the gunboats could take the channel south of Salamis at high tide, and so I sent the Aspic to carry dispatches and (by request of the English admiral) to protect the cable-house against pirates

The night of the 28th–29th our boats dragged the channel for torpedoes and examined the rafts.

This double task was ably done by Lieutenants Champion and Merlin, the torpedo officers of the Duguay-Trouin and Triomphante.

The rafts only supported chains, making an extensive barrier, but one that would have given us little trouble to destroy. The new buoys seemed to be fishermen's, and the dragging gave no cause to suspect torpedoes. The 29th, at the first of the flood, the Duguay-Trouin anchored to the east of the rafts, in a favorable position for bombarding No. 6 battery and of forts Nos. 1 and 2. At the same time the other ships of the squadron came out of the river, and the greater part of them reached the anchorage of Matsu on that tide. When all had got by Kimpai Pass the Triomphante weighed in her turn and anchored near the Duguay-Trouin. Two hours later not a single gun of the enemy could be served. The Chinese, who were certainly very careful of their troops, had scarcely tried to return the fire. At this time the Galissonière arrived, having been detained at Keelung by a heavy gale, which prevented her from arriving in time.

The 25th, as soon as he could get a pilot, Admiral Lespes came up to the anchorage of Woga, where he hoped to engage the works of Kimpai, but the narrow channel and swift current prevented him from engaging more than his port turret-gun, while he was threatened by several batteries, and after a few shots he thought it necessary to seek a more favorable position.

While the Galissonière was shifting her berth she was struck on the port bow by a 21-centimeter shell from the barbette battery of the White Fort, which pierced the plating, killing one man and wounding several.

On the 30th, toward evening, the Duguay-Trouin, Gallissonière, and Triomphante arrived at Matsu. The Aspic alone remained at Sharp Point to guard the telegraph line until an English gunboat, which had been ordered from Hong-Kong, should relieve her.

We have suffered severely: Ten killed (including an officer) and 48 wounded (including 6 officers). As for the Chinese, it is impossible to estimate their losses with any precision. To the first estimate, inspired by the terror of the first days, has succeeded a more reasonable one of from 2,000 to 3,000 killed and wounded.

The ships of the squadron are engaged in various repairs, in overhauling engines, and in coaling.

The Nive brings supplies to last until November 15.

This, sir, is a summary account of the events of a fatiguing week. I am happy in telling you that officers and crews can never do better in similar circumstances than these have done.

During the month before I had the pleasure of seeing with what energy they supported the fatigues of a continual lookout, at quarters, and with steam up. They knew an action was at hand and waited for it with secret impatience and full confidence in the result.

The brilliant work of the 23d justified all our expectations. Although the work of the succeeding days was of a less exciting nature the general ardor was not relaxed until the last Chinese gun was dismounted.

I am proud to command officers and men animated by so high a love of country. France may expect anything from their bravery and devotion.

With profound respect, I am, sir, your obedient servant,

A. COURBET.

REPORT OF THE ACTION BETWEEN THE FRENCH AND CHINESE FLEETS AT PAGODA ANCHORAGE, MIN RIVER.

By Lieut. H. OSTERHAUS, U. S. Navy.

On August 23, 1884, the negotiations between France and China having failed, Vice-Admiral Courbet, commanding the French forces in Chinese waters, was directed by his Government to make reprisals on the Min River. In anticipation of this event, the French fleet had taken an anchorage off Pagoda Point for more than a month, and had made all preparations for commencing hostilities.

Pagoda anchorage is off the point of the same name, about 25 miles above the mouth of the Min River, and 12 miles below Foo-Chow City. It is the usual anchorage for all vessels of deep draught. The river here makes a sharp turn and is about half a mile wide, but the channel is barely 200 yards wide. A short distance above the point, on the left bank, Ma-moi arsenal is situated, at the foot of Ma-moi hill. This arsenal was built by the French for the Chinese Government, and for many years was controlled and operated by Frenchmen employed for that purpose. Its equipment, outfit, and machinery were all procured from France at a very great cost.

To protect this valuable property and to resist an attack of the French fleet a Chinese fleet of eleven vessels was stationed in the river; but, with the exception of two old stone forts and a field battery on Losing Island, no fortifications were constructed on the surrounding commanding hills.

Upon the Chinese fleet, therefore, devolved the protection of the arsenal. This fleet was composed of the following vessels: The Yung-Woo, a full-rigged corvette, commanded by Captain Chang Sing, the senior officer afloat; the Yung-Pao and Chuen-Hung, transports; the Chang Sheng and Fah-Sheng, gunboats, carrying 1 18-ton Armstrong M. L. rifle; the Foo-Poo, Chi-an, Fei-Yuen, Chuen-Wei, and Fah-Shing, gunboats, and the Yei-Sing, a small vessel used as a practice vessel for cadet engineers, and carrying 3 small brass guns.

In addition to these vessels, about a dozen war-junks, armed with small, obsolete cannon, and manned with large crews, were moored close inshore. These were to be used in carrying some of the French vessels by boarding. Also a number of fire-junks were in readiness to be sent down among the French fleet.

The fortifications to assist the fleet were obsolete works of masonry, situated on Losing Island; one on Pagoda Hill, just to the eastward of the tower, and the other just below the first, close to the water. The former had 14 obsolete guns, about 10-pounders, mounted on wooden carriages; the latter had 6 guns of larger caliber, and equally worthless. Besides these an earthwork mounting 3 field-pieces had been thrown up on Pagoda Hill commanding the lower reach of the anchorage. A visit to these works after the action plainly showed that they played no part in it, and were probably deserted at the first discharge of the heavy guns of the French fleet.

The destruction of the arsenal as well as the protecting fleet was the object of the French admiral. With this end in view he had anchored his fleet in a commanding position around Pagoda Point. The fleet consisted of the Volta, temporary flag-ship, Triomphante, Duguay-Trouin, Villars, D'Estaing, Vipère, Aspic, and Lynx. In addition to these vessels two modern steel torpedo boats of high speed were at hand.

Besides these vessels the admiral had the following vessels of his command in the vicinity: the Chateau-Renaud, anchored lower down the river between Kimpai and Mingan Passes, the Bayard, regular flag-ship, the Galissonnière, flag-ship of Rear-Admiral Lespes, division commander, the gunboat Lutin, and the transport Saône, converted into a gunboat, were lying opposite the mouth of Min River, off the island of Matsu, the base of operations of the French.

For more than a month the French and Chinese fleets had been anchored within short range of each other stripped for battle. During every day of this time the preparations of the different vessels were perfected. The French vessels had been cleared for action by striking light masts and yards, sending down yards on the main and mizzen masts and landing them across the rails and on deck; mounting machine guns, the Hotchkiss revolving cannon, on the lower mast-heads, in the tops, and along the rail; by constructing sheet-iron shields and bulwarks of chain, rope, and canvas to protect exposed parts of ship and the crews, having chain ready for slipping, kedges slung on the quarters with springs bent, temporary torpedo launches rigged and ready alongside each vessel, and steam up to move at any moment. Each of the larger boats of the vessels had a machine gun mounted, and when the ships went into action all the davit boats were lowered to the water's edge.

The vessels were anchored in the following order: The flag-ship Volta above the point with the Pagoda bearing about east, the Vipère, Aspic, Lynx, Duguay-Trouin, Villars, and D'Estaing below the flag-ship in the order named. The Triomphante only arrived a short time before the action commenced and took her station below and near the D'Estaing. The two torpedo boats were anchored close to the flag-ship, with steam up and torpedoes rigged. All the crews of the vessels were considerably strengthened by details from the ships outside. All the guns were manned so as to fight both sides. With the exception of the Volta, all the vessels were of modern construction, and carried heavy batteries of modern breech-loading rifles of French pattern. These guns varied in caliber from 4½ to 9⅜ inches. The whole number of guns of the fleet was 71, with a broadside of 43 guns throwing over 2,300 pounds of metal.

Each vessel had one or more guns mounted to fire directly ahead or astern, and in the four smaller vessels, the Volta, Aspic, Vipère, and Lynx, the batteries were mounted on pivot carriages, to be fought on either side. Each vessel carried four or more Hotchkiss revolving cannon. The larger vessels had two mounted in each top and the smaller vessels one. In the latter a platform was built around the lower masthead, on which the guns were mounted. Besides these each vessel had at least four of these guns mounted along the rail, generally one on each bow and quarter. The tops were protected by iron shields, as were also the guns along the rail. Evidently the vessels outside were stripped of their machine guns to strengthen those that took part in the action.

The vessels of the Chinese fleet were also of modern construction, but of lighter build, except the Yung-Woo, which was a fine corvette, built at the Mamoi arsenal and carrying a good battery. All the vessels were built in China, mostly at the Foo-Chow arsenal. The two smaller gunboats were built at Hong-Kong, after the model of the Alpha-Beta gunboats built by Sir William Armstrong, but they carried only 18-ton guns. This fleet carried but 45 guns, 3 of which were small brass cannon and of little use. Therefore the French guns outnumbered them nearly two to one. These Chinese guns were of the Whitworth, Armstrong, and Vavasseur types, muzzle and breech loading, and varied in caliber from 40-pounders to 18-ton guns. Each vessel, with the exception of the two transports and the Yei-Sing, carried a pivot gun abaft the foremast. The Yung-Woo and the two mosquito boats were the only vessels that had a directly-ahead fire. The former also had a gun mounted to fire directly astern. The Chinese fleet could fire 23 guns in broadside. It carried no machine guns, and during the action the want of them was sadly felt. The officers of the fleet recognized the utility of these arms and had applied for them, but they were refused on some absurd pretext.

This fleet was disposed as follows: The Chi-an, Fei-Yuen, and Chuen-Wei were anchored in the lower reach, off the custom-house, on the right shore, abreast of the larger vessels of the French fleet. The other vessels were lying in the upper reach above the Volta; the Yung-Woo within 200 yards of her. The ships were cleared for action in a similar manner to those of the French as far as the means at hand would permit. The fleet was under the disadvantage of orders from the Government at Pekin to act entirely on the defensive.

Such was the condition and disposition of the two fleets on the day of action. No one who saw them lying so close together, stripped for battle, could have a doubt as to the issue of an action between them, and yet no one was altogether prepared for the scene of that day.

The French commander-in-chief had given due notice to all the foreign vessels as to the time of commencing hostilities. His plans were all made, and all his commanding officers had received their instructions, and were ready to begin the battle as soon as the signal was made. The officers and crews of his fleet were anxious for the preconcerted signal to open fire, and when it was made on the afternoon of the 23d of August their response came quickly. The admiral selected the beginning of the ebb tide as the best hour to open fire. The Chinese vessels above his ship, not having anticipated him by dropping a kedge astern, presented their sterns to the bow guns of the French ships, and had to turn partially before they could bring their guns to bear.

The signal, the discharge of a machine gun in one of the tops of the Lynx, was given at 1.56 p. m., and was answered immediately by the batteries and machine guns of all the French vessels. The Yung-Woo replied at once with her stern gun, and the other vessels as soon as they could bring their guns to bear. The action at once became general and the scene was soon enveloped in a dense smoke. At the signal the two torpedo boats launched out on their errand of destruction. The admiral in his flag-ship, with the Lynx, Aspic, and Vipère, slipped and moved up against the Yung-Woo and the vessels lying above him. To the Villars, Duguay-Trouin, and D'Estaing, assisted by the Triomphante, which came into action shortly after it began, was allotted the destruction of the three gunboats anchored abreast of them and in silencing the works on Pagoda Point.

The Triomphante, which had been discovered coming in about 1.30 p. m., opened fire with her bow gun when about a mile off, and stood up to her station off the custom-house and near the D'Estaing.

Four minutes from the commencement of the action a heavy explosion told the successful work of the torpedo boat detailed to destroy the Yung-Woo. In this short time, and before the Yung-Woo was fairly in action and had brought her guns to bear, the torpedo had done its deadly work and had destroyed this fine vessel. The officer in charge of the torpedo boat had successfully placed a torpedo under her counter while she was in the act of turning. It nearly blew her out of water, and the vessel soon sank, on fire fore and aft, a total wreck. Many of her officers and crew perished. She lies close inshore, 100 yards above the point.

The torpedo boat dropped down the river out of action, her commander and one of her crew having been wounded, probably by one of the French machine guns.

Soon the whole scene was enveloped in smoke, nothing could be observed, and the effect of the incessant discharge of the heavy guns and machine guns was deafening. In about fifteen minutes the fire slackened and as the smoke rose, the complete destruction of the Chinese fleet was disclosed, while the French vessels appeared uninjured. The Chuen-Wei was sinking at her anchors, riddled by shot, on fire from stem to stern, carrying most of her officers and crew down with her. She was gallantly fought, and went down with her colors flying and guns firing. She was overpowered by her antagonists and one of the torpedo boats finished her. The two other vessels near her, the Fei-Yuen and Chi-an, met a similar fate. They drifted down the river total wrecks, in flames, and finally sunk near Flat Island. These three vessels could make no impression upon their opponents, the largest French vessels, and most of their officers and crews must have been cut down by the machine guns in the tops. They were riddled with shot.

The admiral, with the French gunboats, did equally destructive work above the point. All the Chinese vessels above him were sunk, and, with the exception of the Foo-Poo, were total wrecks. The commander of the Foo-Poo ran his vessel up the river, after receiving several shots. She sank and broke her back. One of the mosquito boats drifted down the river, a helpless wreck. Her decks were covered with dead and wounded, and she sank near the foreign shipping, a short distance below the point. About an hour after the action began one of the gunboats above the point, the Fah Shing, drifted down the river in flames, with the French colors flying. She had been carried by boarding, and passed out of sight through Mingan Pass. Two hours afterward a heavy explosion down the river told the story of her sad end. About 8 o'clock one of the transports which had been destroyed drifted down the river in flames, burned to the water's edge. She was sunk in a few moments by the French vessels before she exploded. (This was some time after these vessels had resumed their anchorages.) The war-junks played no part in the action, and only served as targets for the French gunners. They were mostly sunk at their moorings. A number of fire-junks drifted down the river without doing any harm, and they passed out of sight below the pass.

In less than half an hour the entire Chinese fleet was destroyed, and all that could be seen of the fine fleet were hulks in flames, or sunken vessels. The French gunboats took position off the arsenal and kept up an active bombardment until sunset, when the fleet returned to their anchorage. The Chinese troops on the hills back of the point occasionally received attention with a few shell, which soon effected a retreat to safer quarters. During the night the electric light was actively employed to discover any movements on the part of the Chinese, and the occasional discharge of a gun reminded them of the alertness of their opponents.

The French fleet received no injury in any of its vessels. They were apparently unhurt after the action. The only casualties that occurred to them were on board the Volta, whose crew lost 6 men and the pilot, an Englishman engaged by the French. These men were killed by the first discharge of the guns of the Yung-Woo; a shell striking the bridge near the admiral.

The Chinese loss in killed and wounded must have been very heavy, being variously estimated from 800 to 1,500. The former number is probably the more correct. Many lost their lives in attempting to swim ashore, but the greatest destruction was occasioned by the machine guns, which rained their explosive shells upon the decks, cutting down the crews at the guns so that they could hardly reload them. Their fire demoralized men and officers, and drove them to seek shelter and escape by jumping overboard. The decks of the vessels as they drifted down the river were covered with dead and wounded. To these guns may also be ascribed the rapidity and thoroughness with which the vessels were set on fire.

The importance of this class of armament was clearly demonstrated in this action and the conditions for their use were the most favorable. No modern man-of-war will be efficient without them. Her crew would be at the mercy of an opponent armed with them.

The accuracy and rapidity of the French fire were remarkable, fully demonstrating the advantage of the breech-loader over the old muzzle-loader. Notwithstanding the exposed position of the buildings on Pagoda Point they were hardly struck by shot, and then only by a few shell of the machine guns.

On the morning following the battle the launches and boats of the fleet were sent to destroy the junks which had collected in the creek just above the custom-house for piratical purposes. The junks were destroyed and many of the crews were killed; the rest escaped over the hills. The gunboats got under way and resumed the bombardment of the arsenal, where a great deal of valuable property must have been destroyed. It would have been entirely demolished had the French admiral considered it safe to land men. It was reported to have been mined, and this no doubt deterred the admiral from risking his men. While the gunboats were thus engaged, the larger vessels occasionally threw shells into the camps upon the hills and made it dangerous for any one to show himself.

This was kept up during the greater part of the day. In the afternoon the French landed at the custom-house and buried their dead.

On the morning of the 25th they landed parties at the custom-house and at the point, clearing the way with their heavy guns and holding the troops on the hill in check by an occasional shell. They did not take formal possession at these points. At Pagoda Point they took possession of the field-pieces mounted there, and carried them off to their vessels. In the afternoon the French admiral transferred his flag to the Duguay-Trouin, with which vessel he led the attack on the forts at Kimpai and Mingan Passes. The fleet got under way and stood down the river. With the exception of the Triomphante and the Duguay-Trouin, the vessels anchored above the pass. The two vessels named bombarded the forts, but met with no resistance as all the guns were mounted to repel an attack from below, and during the long time that the French fleet was anchored above them with hostile intentions no attempt had been made to resist an attack. They could not bring a gun to bear upon the French ships, which thus took them in the rear, and in fact not a gun was fired against these ships.

During the remainder of this day and on the morning of the following, the 26th, the bombardment was continued, the small vessels going close to the shore, which is very bold, sweeping the hills with their machine guns.

After having battered down the works at the pass, a force was landed and destroyed all the modern guns by blowing them up with gun-cotton. The ships covered the party with their guns.

The loss to the French was inconsiderable, no resistance whatever having been offered. The works consisted of old masonry fortifications, strengthened here and there by earth embankments. They mounted a number of heavy rifled guns of Krupp manufacture. From the Mingan forts the fleet proceeded to those at Kimpai and repeated the same tactics. They met no enemy to annoy them in their operations. As they moved down the river they destroyed every semblance of fortifications, and with their machine guns cleared the hills of all Chinese. The only losses they sustained were from troops firing from behind the crest of the hills where they could not be reached. In all their operations on the river the French lost less than 50 men in killed and wounded. But 1 officer was killed. Having thus completed his operations, the French admiral withdrew with his fleet and anchored off Matsu Island, leaving a vessel to guard the telegraph at Sharp Peak.

During the afternoon of the 24th, while the operations at Pagoda anchorage were in progress, the Galissonnière steamed into the river evidently with the intention of feeling the forts at Kimpai Pass. When she was within 2 miles of them the forts opened fire, to which she promptly replied. At first the firing was wild, but soon the Chinese got the range and succeeded in striking her, when she withdrew. This shot was from one of the heavy Krupp guns and would have inflicted very serious injury on the vessel had it been filled with powder instead of charcoal. It entered just abaft the foremast, and lodged on the berth-deck. As it was, it necessitated a visit to Hong-Kong to make the repairs.

Whatever may be thought of the disparity between the two hostile forces, all admit that the operations were conducted in a masterly and brilliant manner on the part of the French. Admiral Courbet conceived his plans well and clearly impressed them upon the minds of his subordinates, who when the time came carried them out in the most thorough and efficient manner, winning the admiration of every one.

Description of the French vessels that took part in the action at Pagoda Anchorage.

Triomphante.—Sea-going iron-clad, second class, with ram; 4,127 tons displacement; 5⅞-inch armor; central battery and belted; six 9⅜-inch B. L. rifles, four in central battery and two in barbette turrets on spar-deck; one 7⅝-inch B. L. rifle under forecastle to fire ahead, and six 5½-inch B. L. rifles on spar-deck.

Duguay-Trouin.—Iron cruiser of second class, with ram; 3,289 tons displacement; unarmored; five 7⅝-inch B. L. rifles, four in sponson turrets and one under top-gallant forecastle, with fire directly ahead; five 5½-inch B. L. rifles on spar-deck, one firing directly astern.

Villars.—Wooden cruiser, second class; 2,268 tons displacement; fifteen 5½-inch B. L. rifles on spar-deck, two on top-gallant forecastle to fire ahead, and one aft to fire astern, twelve in broadside.

D'Estaing.—Wooden cruiser, second class; 2,236 tons displacement; fifteen 5½-inch B. L. rifles; carried as in Villars.

Volta.—Old wooden gunboat; 1,200 tons displacement; four B. L. rifles, two of 5½-inch caliber and two 4-inch. The former carried on spar-deck, on pivot-carriages abaft and forward mainmast, the latter on poop and top-gallant forecastle.

Lynx, Aspic, and Vipère.—Gunboats of 471 tons displacement, carrying the same battery as the Volta, and mounted in the same manner. The Lynx is a ram.

Also two steel torpedo boats, about 50 feet in length, of high speed, armed with spar torpedoes.

Description of Chinese vessels that took part in the action at Pagoda Anchorage.

Yung-Woo.—Composite, full-rigged corvette, of 1,393 tons displacement; carried eight 3-ton ½ M. L. Whitworth rifles, six in broadside, one under forecastle, firing directly, and one aft to fire astern; one 6½-ton M. L. Whitworth rifle abaft foremast on pivot-carriage.

Foo-Poo.—Gunboat of 1,258 tons displacement; carried six 45-pdr. B. L. Vavasseur rifles in broadside and one 10-inch smooth-bore M. L. on pivot-carriage abaft foremast.

Fei-Yuen.—Gunboat of 1,258 tons displacement; carried six 45-pounder B. L. Vavasseur rifles in broadside and one 4-ton Armstrong M. L. on pivot-carriage abaft foremast.

Chi-an.—The same as Fei-Yuen.

Chuen-Wei.—Gunboat of 572 tons displacement; four 45-pdr. B. L. Vavasseur in broadside, and one 4-ton Armstrong M. L. rifle on pivot-carriage abaft foremast.

Fah-Shing.—Gunboat of about 500 tons displacement; two 45-pdr. B. L. Vavasseur and two 40-pdr. M. L. Whitworth rifles on spar-deck in broadside, and one 4-ton Armstrong M. L. rifle abaft foremast on pivot-carriage.

Yei-Sing.—Small gunboat of about 400 tons displacement; carried three small brass cannon.

Yung-Pao and Chuen-Hung.—Transports of about 1,400 tons displacement. Three guns.

Chang Sheng and Fah Sheng.—Armed with one 18-ton gun each, something like the Alpha class, but inferior.

EFFECT OF THE BOMBARDMENT OF THE FRENCH FLEET ON FOO-CHOW ARSENAL.

(By Lieut. H. Morrell, U. S. Navy.)

Sir: I have the honor to submit the following report of an inspection of the Naval Arsenal, Pagoda Anchorage, Min River, made December 23 last, with a view to ascertaining the damage sustained during the bombardment on the 23d and 24th of August last:

Through the kindness of a gentleman connected with the Chinese Imperial College, permission was obtained to visit the arsenal.

There were no foreigners employed in the establishment, and as no information could be obtained from the Chinese official and it was not considered advisable to make notes, data for a detailed report could not be procured, and a general idea only of the effect of the bombardment can be given.

A landing was made at the iron pier, marked A in the accompanying sketch, which supports the shears used for handling boilers, machinery, &c. The pier and shears were in good condition, and showed no signs of having been struck. Alongside were the Foo-Poo and a gunboat of about 500 tons, lately launched. Workmen were busy completing the latter and repairing injuries received by the former during the engagement and while aground at Limpoo. The boat-building sheds 1, 1 were slightly damaged; the building slips 2 and 3 were hardly touched, only a few Hotchkiss shells having struck the uprights of the ship sheds. On each of these slips was laid the keel of a composite gun vessel of about 600 tons, with about twelve of the forward frames in place. This work was not injured. The gunboat launched since the engagement, on building slip marked 5, was pierced about eighty times and greatly damaged. The boat-building shed 4 was nearly demolished, and has since been rebuilt. The pattern and carpenter shops 6 and 7 had not been touched, and together with the adjoining shops 8 and 9, used for bending iron ship frames and plates, were in full operation. The small-tool machine-shop 10 had apparently escaped without any injury, as no marks could be found on the building, and the machinery was in operation.

The front of the foundry 11 had been pierced several times; no signs of internal damage; foundry in operation. The large-tool machine-shop 12 is two-storied, with the second floor devoted to offices, designing and drafting rooms. The latter had been severely handled, and the front of the building on the ground floor penetrated about five times. The machinery showed no evidence of injury from the bombardment, and every tool was found at work. In the small wing setting off from the front of their building are two large wooden cranes traveling on a railway. The wall abreast these had been pierced about five times, the only perceptible damage being the carrying away of a few braces and the imbedding of several pieces of shell in the uprights. They were not disabled. The ordnance building 13 was struck three times, but nothing inside was injured. Here were stowed large quantities of torpedoes and shells, loaded and unloaded, four Krupp field-pieces, and three Vavasseur guns of small caliber. The front of the boiler shop 14 was penetrated eleven times. The front half of the shop was empty, only the beds of the different apparatus being in place, while in the rear half work was going on as usual.

The rolling mill 15 and blacksmith shop 16 were only slightly injured. The high chimney of the former had been knocked down, but the plant seemed uninjured, and in the blacksmith shop nearly every tool and hammer were at work. The marine railway 18 was damaged considerably and was still under repairs. It will probably be in working order in a short time.

Taken as a whole the injuries received were slight, and a good estimate of their extent may be found from the fact that only three months after the bombardment the Chinese were able to launch a vessel that had been much damaged.

Two reasons may be assigned for the comparatively slight damage inflicted. First, the inefficiency of shell fitted with quick-acting impact fuze used against brick walls of moderate thickness; second, the forbearance of the French.


16
15
High chimney knocked down.
14
13
12
11
10
18
A
1
1
9
8
2
7
3
4
6
5

REPORT OF VICE-ADMIRAL COURBET TO THE MINISTER OF MARINE.

MATSOU, *February* 17, 1885.

SIR: I have the honor to report the results of a cruise I have just finished along the coast of China with the Bayard and several vessels of the squadron of the Extreme East.

The Chinese had assembled in the Yang-tse-Kiang a squadron composed of five ships, consisting of two steel cruisers, the Nau-Tchen and Nau-Choni, built at Kiel; the cruiser Kai-Tsi, built on the same model at Foo-Chow, the Yu-Yuen, a frigate of 3,400 tons, and the corvette Tcheng-King, of 1,300 tons (Dupleix type).

These ships decided to put to sea in the latter part of January.

I left Kelung on February 5, at 4 p.m., with the Eclaireur, the Saône, and the Aspic; the next day I was joined by the Triomphante, Nielly, and Duguay-Trouin.

Between the 6th and the 12th of February I visited several points along the coast of China, and on the morning of the 13th the Eclaireur and Aspic, which had been sent in advance, reported five sail in sight. I headed for them.

The Chinese fleet, doubtless warned by a lookout ship, made off immediately; we were about 5 miles astern.

After having rounded the northern sides of the Medusa, Tunis, and Sanchesan Islands, the three, Nan-Tchen, Nan-Choni, and Kai-Tsi, turned to the south, and seemed for an instant to slow down and rectify their line. I thought they were going to fight, but this illusion was short, for soon we saw them running to the southward at full speed. The frigate had headed at the same time for Sheipou, and the Tcheng-King after a moment's hesitation followed her.

I left the Triomphante, Saône, and Aspic to watch these two, and followed the three cruisers with the Bayard, Nielly, and Eclaireur. At 9.40, the fog getting thicker, I abandoned the chase and returned to the neighborhood of Sheipou to make sure of the frigate and corvette.

I immediately sent the Eclaireur and Nielly to the anchorage east of Tung-Moon, while the Bayard anchored in Sheipou Roads. The eastern passes were thus well guarded. On their side the Triomphante and Saône the southern ones, and the Aspic reconnoitered there. As soon as at anchor I sent Lieut. Ravel in a steam launch to the head of the pass, between Sin and Nyew-tew Islands, to see if the Chinese frigate and corvette were at anchor.

Before risking our ships in the Sheipou Passes I thought it necessary to reconnoitre, and the Aspic and Eclaireur were sent to do so. But while waiting for their report I decided to try an attack by the two torpedo launches of the Bayard.

The weather being too bad during the night of the 13th–14th the attack was postponed to the following one. The Chinese new year coming on the 15th I hoped celebrations on its eve would decrease vigilance and make surprise more easy.

Accordingly about midnight our boats left with the intention of attacking the frigate. One was in charge of Commander Gourdon, commanding, and the other in charge of Lieutenant Duboc. Lieutenant Ravel, who had seen the Chinese vessels and examined the channel, piloted them. He was also to afford them assistance and afford a rallying point at the conclusion of the affair. Mr. Muller, a pilot for the Yang-tse-Kiang, who has been in the French service since last July also accompanied the expedition.

On account of the difficulties of navigation and the insufficient speed of our steam launches, the expedition did not get near the Chinese ships till half-past 3 in the morning. Guided by Lieut. Ravel our torpedo boats saw the frigate at about 700 or 800 metres. They headed for her at the greatest speed possible without making too much noise. Commander Gourdon's boat going faster than the other, they lost sight of each other for an instant. The ships and shore kept a good lookout. There were men at the guns at the Nordenfelts and riflemen on deck and in the tops. Our boats were discovered before getting up, and were received by a warm fire from the frigate, which was supported from the shore. Our boats put on full speed. Commander Gourdon struck first right astern. The torpedo exploded, but the boat could not get away, as her spar was caught, and she had to unscrew its fittings to let it go. In this critical position a man was killed by a shot from the shore.

This boat was backing off when Lieut. Duboc's boat came up at full speed, struck the frigate on the starboard quarter, and exploded her torpedo. The engine had been reversed before the collision, and she got clear at once, and the two boats made off together under fire of the enemy's small arms and machine guns.

Carried on by the current, these two boats passed the place where Lieut. Ravel was waiting for them, and did not see his rallying light. The two groups of boats looked for each other until day, and then were obliged to return.

Lieut. Ravel came on board the Bayard after having been able to see by the light of early dawn that the corvette was sunk and lying heeled over. The frigate seemed upright, as if she was unhurt.

It was learned later, at low tide, that the two Chinese ships were sunk, the frigate being upright and sunk half way to her tops, the corvette being inclined and sunk to her rail. It seems probable that the corvette was sunk by the fire of the shore batteries and frigate against our boats.

The frigate Yu-Yuen was a fine ship of 3,400 tons, built at Shanghai, on the plans of American constructors, about twelve years ago. She was armed with twenty-three breech-loading guns, twenty of which were in broadside and three on the forecastle and poop. She had also some Nordenfeldts.

The corvette Tcheng-King was one of the last ships built at Foo-Chow, and carried 7 guns.

REPORT OF VICE-ADMIRAL COURBET TO THE MINISTER OF MARINE.

The minister of marine has just received from Admiral Courbet the details of the capture of the Pescador Islands, which took place March 29 last.

The expedition was composed of the Bayard, Triomphante, D'Estaing, Duchaffaut, Vipère, and Annamite, which had on board two companies of marine infantry and a section of 80-millimeter mountain guns, commanded by Chef de Bataillon Lange, of the marine infantry.

These troops were reinforced for the operations on shore by the landing parties of the Bayard, Triomphante, and D'Estaing, with two sections of 65 millimeter guns.

On the 29th, at 7 a. m., an attack was made on the casemated fort and four batteries which defended the ports of Ponghon and Makung.

At 10 o'clock most of the guns were dismounted and the fort dismantled; two magazines had blown up. A large fire broke out in the village of Makung, which burnt for twenty hours.

A chain barrier had been placed at the entrance to Makung, and during the night the admiral sent two aides-de-camp to examine it. In the morning the boats of the Triomphante, under Lieut. Talpomba, destroyed it. One man was killed here.

During the bombardment the ships, which were well handled, kept in the dead angles, and were untouched.

The landing parties disembarked on the 29th near Dome Peak, marched on Makung on the morning of the 30th, supported by the fleet both inside and outside the port. After several encounters the French occupied Makung on the evening of the 31st. A company of marine infantry occupied Lixsitah Light the next day. The French losses on shore were 4 killed and 12 wounded. The Chinese garrison, 1,500 strong, suffered considerable loss.

UNITED STATES NAVAL OPERATIONS

ON THE

ISTHMUS OF PANAMA,

APRIL, 1885.

REPORT OF COMMANDER McCALLA

UPON THE

NAVAL EXPEDITION TO THE ISTHMUS OF PANAMA,

APRIL, 1885.

NAVY DEPARTMENT, BUREAU OF NAVIGATION,
June 8, 1885.

SIR: I beg leave to submit a report of the service performed by the naval force recently under my command on the Isthmus of Panama.

In compliance with the Department's instructions of April 2, I proceeded to New York and reported to the commandant of the navy-yard as the Commanding Officer of the Force to be sent to Aspinwall, United States of Colombia. These instructions directed me to organize that force.

The force consisted of the First Battalion of Marines, about 200 strong, the Second Battallion of Marines, 259 men, and the available Blue-jackets at New York, numbering about 280 in all.

The First Battalion of Marines, under Major and Brevet Lieutenant-Colonel Heywood, U. S. M. C., with Asst. Surg. F. N. Ogden, U. S. N., sailed in the City of Para (delayed one day at the request of the Department), at 2 p. m. on April 3.

Lieut. T. B. M. Mason, U. S. N., who had been ordered to New York on the 2d of April, was instructed by me to drill the Blue-jackets in the use of rifles and gatling and field guns twice each day. This he did with zeal and ability. Lieutenants Southerland and Mentz and Junior Lieutenant Walling were directed by the Commandant to assist Lieutenant Mason.

On the 4th of April the Blue-jackets were separated into two battalions of three companies each, to facilitate their instruction. On the 5th I was ordered by the Department to go in the Acapulco with the Second Battalion of Marines, the necessary Blue-jackets for six guns, and such of the officers as had been ordered by the Department for service on the Isthmus as I might elect to take with me.

Lieut. William S. Cowles was appointed Adjutant-General of the force, and Lieut. W. H. Reeder, A. D. C. Surg. G. A. Bright had been orordered to report for duty, but not arriving in time for the steamer, his place was filled by Passed Asst. Surg. R. Whiting, U. S. N., who volunteered for this service. Paymaster Stephen Rand, U. S. N., reported for duty on the 6th of April, and Mr. James Gregory was appointed paymaster's clerk.

Lieutenant Allibone was ordered to command one battalion of three Gatling guns, and Lieutenant Mason was given a battalion of three 3-inch B. L. R. guns. Lieutenants Badger and Sharp, and Gunner J. J. Walsh commanded the gatling gun sections; Lieutenants Kellogg and Colwell, and Ensign Witzel commanded the sections of rifled guns. The organization of the force is shown on the inclosure marked A.

At 1 p. m. of April 7 the force was transferred to the Pacific Mail steamship Acapulco in the navy-yard tugs, and the Acapulco sailed at 4 p. m. of the same day.

I had received the following orders on the 6th:

NAVY DEPARTMENT,
Washington, April 5, 1885.

SIR: You will proceed with a detachment of marines and blue-jackets per Pacific Mail steamer Acapulco to Aspinwall and report to the senior naval officer present for duty in connection with opening the transit and protecting and caring for the lives and property of American citizens upon the Isthmus of Panama. You will have command of the entire force sent from New York for the above purpose, subject to the orders of the admiral commanding the North Atlantic Squadron, or of the senior officer present, the force sent by the City of Para and by the Acapulco being considered as your particular command.

You will take every precaution to protect the health and lives of the officers and men placed under you, and while taking all the necessary steps to have your command in the highest state of efficiency, you will expose it to the trying climate of the Isthmus no more than is absolutely necessary.

Very respectfully,

W. C. WHITNEY,
Secretary of the Navy.

Commander BOWMAN H. MCCALLA,
U. S. Navy, Navy-Yard, New York.

A daily routine was established (appended, marked B), and the command was exercised morning and afternoon. Opportunities were afforded all for target practice at floating targets, and Passed Assistant Surgeon Whiting instructed officers and men in the general principles of anatomy, the use of bandages and tourniquets, recommending certain sanitary precautions to be adopted in the climate about to be encountered.

There was some confusion the first evening out, but the steamer's accommodations were excellent, the fare good, and after a pleasant passage of eight days the Acapulco came to anchor off Colon at 9 p. m. of the 15th of April. During that day, in order to prepare for landing at once in case of necessity, two days' rations were served out, and the ammunition boxes of the 3-inch rifles and gatlings were supplied with shell, shrapnel, and small-arm ammunition. Each man carried forty cartridges, his blanket rolled with a change of clothing, canteens, and haversack.

As it turned out, there was no necessity for landing the force that night; early the following morning the Acapulco hauled alongside wharf No. 1 of the Panama Railroad Company, which had been partially rebuilt, and at 9 o'clock Rear-Admiral Jouett inspected the command, expressing himself as well pleased with its appearance.

Rear-Admiral Jouett had arrived on the afternoon of the 10th of April, in the flagship Tennessee, accompanied by the Swatara. The marine garrison stationed at Pensacola, Capt. R. Meade, Second Lieut. Arthur H. Clark, seven non-commissioned officers, twenty-eight privates, and two musicians came down in the flagship.

On the 11th of April the transit had been formally opened by Rear-Admiral Jouett, and on the arrival of the Acapulco on the 15th, the regular trains were running under the protection of train guards from Admiral Jouett's squadron. Two armored platform cars had been prepared under the direction of Lieutenant Kimball, U. S. N., and were attached to the 11 a. m. train each way. These cars were protected on the sides and ends by plates of boiler iron, and were covered with water-proof roofs, each being armed with a Hotchkiss revolving cannon, one gatling, and one 12-pounder howitzer.

Lieutenant Colahan, U. S. N., commanded the Colon garrisons, composed of officers and men from the vessels of the North Atlantic Squadron. Passed Assistant Paymaster Martin, of the Alliance, had charge of the stores on shore and acted as quartermaster and commissary.

At Matachin, a turbulent center, there were stationed Captain Meade's company of marines and a force of blue-jackets from the Tennessee, all under command of Lieutenant Impey, U. S. N., with Passed Assistant Surgeon Ashbridge, U. S. N., as medical officer.

In compliance with instructions from Rear-Admiral Jouett, appended and marked C, the force was landed; the garrisons at Matachin and Colon were relieved that day, and Lieutenant Mason was directed to relieve Lieutenant Kimball in time for the early train of the 17th. Copies of the instructions to the several Commanding Officers are appended, marked D.

It was found practicable a short time afterwards to discontinue the use of armored cars, and later, in consequence of the discomfort entailed upon the men by the first arrangement, it was expedient to furnish train-guards from each end of the line, who exchanged as the trains passed each other.

The force assigned to duty on the Isthmus was distributed as follows:

COLON GARRISON.

[See plans E, F.]

Capt. J. H. Higbee, U. S. M. C., was assigned to command the naval force at Colon.

Post 1, *Capt. R. S. Collum, U. S. M. C., Commanding.*—This post commanded the water approach from the eastward, and the garrison was quartered in the building occupied by the mechanics of the Panama Railroad Company, near the hospital.

Post 2, *Capt. F. H. Harrington, U. S. M. C., Commanding.*—This post is on the beach near the church, an eighth of a mile nearer the center of the town than post 1. The men were quartered in a house marked D on plan E.

Post 3, *Lieut. T. B. M. Mason, U. S. N., Commanding.*—This garrison was quartered in a series of six houses shown on the appended plan E, marked I.

Post 4, *Lieut. C. O. Allibone, U. S. N., Commanding.*—This garrison was quartered at the Pacific Mail Steamship Company's wharf and guarded the causeway or approach by land to Colon, and the wharves and property belonging to the steamship company. (See plan F.)

The quarters for posts 1, 2, and 3 were furnished by the Panama Railroad Company, and those for No. 4 by the Pacific Mail Steamship Company.

THE DISTRICT OF MATACHIN.

MATACHIN.

Post 1, *Capt. R. W. Huntington, U. S. M. C., Commanding.*—The garrison was quartered in the railroad station, the officers having the paymaster's car on a siding assigned to them.

SAN PABLO.

Post 2, *First Lieut. G. F. Elliott, U. S. M. C., Commanding.*—The garrison at San Pablo was quartered in a fine house loaned by the courtesy of the Director-General of the Panama Canal Company. The post at San Pablo was an important one, as it commanded the approaches to the Barbacoas iron bridge over the Chagres River. A guard tent was put up at either end, and a small earthwork commanded the bridge and approaches.

This post was established on the 16th of April, in compliance with the following telegram addressed to Captain Huntington, viz:

[Telegram.]

COLON, *April* 16—4 p. m.

Captain HUNTINGTON,
Matachin:

Send twenty-five men and two officers back to San Pablo by special to-night to guard Barbacoas Bridge over Chagres River. Commanding officer at San Pablo garrison must ask Chief of canal what barracks he is to occupy, as agreed to-day with the director-general.

B. H. McCALLA.

The garrison at Panama was commanded by Maj. and Bvt. Lieut. Col. Charles Heywood, commanding the brigade of marines, and was quartered in the freight offices, old passenger station, and in two large freight-houses, well located, and open at both ends. The freight-houses belonged to the Canal Company. The strength of these several garrisons is appended, marked G.

THE POLITICAL SITUATION.

In order to make plain the political condition of the Isthmus, it is necessary to refer to the elections of last summer in Panama and the subsequent events.

The President of each of the eight States forming the United States of Colombia, as well as the National Executive, are elected for terms of two years. Each State is independent in the management of its local affairs. The elections in Panama occurred last summer, and two candidates were balloted for, viz; Señors Arosemena and Lambert. The former is said to have had the support of the Government at Bogota. Although the results of the balloting were disputed, it was claimed that Señor Lambert had been elected.

The Constitutional Assembly, composed of thirty-two members, met on the 6th of last January, decided that there had been no election, and proceeded to elect a President, as provided for by law.

General Santo Domingo Vila, who came to the Isthmus last November as a fiscal agent of the General Government to examine into the contracts between the Panama Railroad Company and the State, was chosen President of the State of Panama, January 7, by the Constitutional Assembly. Señors Arosemena and Vivas Leon were chosen or appointed First *Designado* and Second *Designado*.

The office and duties of the *Designado* are similar to those of Vice-President, and in the event of the death or the absence of the President they succeed successively to the presidency.

The other officers of the State government, such as Secretary of State, Governor of Panama, Prefects, &c., are appointed by the President. The Commander-in-Chief of the Colombian (National) forces is appointed from Bogota, and that office was filled by General Gonima.

The steamer Boyaca, which later on performed valuable service for the National Government, was lying off Panama, formed part of Gonima's force, and was commanded by Colonel Ulloa. The Boyaca, intended for the revenue service of Colombia, had been built at Wilmington, Del., by the Pusey & Jones Company, in 1883 and 1884, and was a staunch craft, about the size of our sea-going revenue cutters. The Colombian Government having asked that a United States naval officer might inspect the Boyaca to determine whether the specifications in the contract between the Government and the Pusey & Jones Company had been carried out, and whether she was likely to fulfill the conditions required of a revenue cutter, Commander J. W. Philip was detailed for the duty. Commander Philip having reported, on January 16, 1884, that the Boyaca fulfilled the requirements specified, and was likely to prove most efficient, she was accepted by the Colombian Government.

In February a portion of the national forces stationed on the Isthmus was sent to Buenaventura, the sea-port of the State of Cauca, about 300 miles south of Panama, to aid in suppressing the revolution which had broken out in that State. About the 1st of March General Vila, obtaining two months' leave of absence, sailed himself with more national troops for Carthagena, to help suppress the rebellion in the State of Bolivar. The strength of the national forces having been thus reduced in Panama, those who were discontented with the result of last summer's election took the opportunity to attempt a revolution.

First *Designado* Arosemena had succeeded to the presidency of the

State in the absence of Santo Domingo Vila, and General Gonima, the commander-in-chief, was in Colon.

General Aizpuru, who had been president of the State of Panama for one term, six or seven years ago, and who had served in the national legislature, was recognized as the leader of the liberal party in the State. On the 16th of March he made a demonstration against the Government which caused Señor Arosemena to take refuge on Her British Majesty's ship Heroine, then lying off Panama; broke open cars; opened and blocked switches; obstructed the road; prevented repairs to the same; cut the telegraph wires; seized and held railroad employés; claimed the right to exercise a censorship over the telegrams; and made it necessary to close the transit. General Gonima, hearing of this demonstration on the part of Aizpuru, proceeded by train to Panama with the national force then stationed at Colon. When Gonima arrived, on the 17th of March, Aizpuru retired from the city, and Señor Arosemena returned from the Heroine.

Colon was now without troops. Prestan, a Haytien negro, with a trace of white blood, the leader of a faction of the radical wing of the liberal party, took advantage of the opportunity and seized that city. Aizpuru and Prestan were pronounced in their dislike to all foreigners on the Isthmus, especially to the Americans living there, and this feeling was made use of to incite their adherents and hold them together.

About the 20th of March Arosemena resigned. Vivas Leon should then, in the absence of Santo Domingo Vila, have succeeded to the presidency of Panama, but was prevented by General Gonima, who declared himself the "military and civil chief of Panama." This title and office are established by law; the National Government may, under certain circumstances, make such an appointment. It is very questionable, however, whether General Gonima had a right to seize the reins of government, more particularly since the Second Designado, Señor Vivas Leon, was in Panama, and should according to precedent and law have succeeded to the presidency.

On the night of the 30th of March General Gonima sent Colonel Ulloa (then commanding the Boyaca) by train to Colon, with a portion of the troops in Panama, to put down Prestan's revolution. In order to prevent a conflict within the limits of Colon, Mr. Burt, the Superintendent of the Panama Railroad Company, notified Colonel Ulloa that he must disembark at Monkey Hill, about 2 miles outside of Colon. This was also made necessary by Prestan, who, hearing of the departure of national troops, went out with his force to meet Ulloa, tearing up the railroad tracks between Colon and Monkey Hill.

The two forces, numbering about 150 each, met on the Panama side of Monkey Hill. After a short conflict Prestan was driven from his position into Colon and behind his barricades in that city. After fighting for several hours on the morning of April 1, the insurgents were dislodged and put to flight by the national forces, led with great gallantry by Colonel Ulloa and his second in command, Colonel Broun, who was Chief of Police of Panama. Both officers were severely wounded in the engagement. During the conflict the city was fired by the insurgents and destroyed.

The departure of Colonel Ulloa and his command from Panama still further reduced the force in that city; and on the day of the fight in Colon, April 1, Aizpuru, with the ammunition taken on the 16th of the preceding month from a sealed car in transit to Central America, captured Panama. General Gonima, with less than 100 soldiers in the cuartel, made a gallant defense and held out for some time against a much larger force. He finally surrendered to Aizpuru to prevent the destruction of the cuartel by dynamite taken from contractors employed by the canal company and used for blasting.

When General Gonima surrendered the Boyaca was included in the stipulations, but Señor José Obaldia, who was in command of her, refused to be governed by the terms of the surrender and sailed for Buenaventura, then held by the National Government. General Aizpuru, having seized the government, declared himself President of the State of Panama, and filled the offices with his friends.

Colonel Ulloa, with less than 100 national troops, held Colon; the rest of the Isthmus included in the zone of transit was held by the insurgents under Aizpuru.

This was the condition of affairs upon the arrival of the naval force at Colon in the Pacific Mail Steamship Company's steamers City of Para and Acapulco, on the 11th and 15th of April.

On the morning of the 17th, accompanied by Lieutenants Cowles and Reeder, I passed over the line of railroad, inspecting the road and the garrisons at Matachin, San Pablo, and Panama, returning to Colon that evening.

Not deeming it necessary at that time to enter the city of Panama, I wrote a note to Mr. Adamson, our consul-general, asking him to visit me if perfectly convenient. The consul-general was kind enough to come to Camp Jouett, the name given to the position occupied by the naval force at the railroad station.

A few days prior to this General Aizpuru had borrowed a large steam tug from the canal company, in which he had sent two commissioners to Buenaventura for the purpose of coming to terms with the commander-in-chief of the national forces, which were assembling at that port to embark for Panama. The insurgent force in Panama was engaged in loop-holing the cathedral and the old monastery in the Plaza San Francisco, an indication that resistance would be made to the entry of the Nationals.

Although anarchy reigned along the line of railroad, I came to the conclusion that there would be little or no danger to the transit unless the *de facto* government of Panama, represented by Aizpuru, should be threatened or overthrown. This was not likely to occur until the arrival of a sufficient national force from the vicinity of Carthagena or Buenaventura. The danger then to be apprehended was the probability that during a conflict within the limits of Panama, the city would be fired by the insurgents, in whose ranks were some of Prestan's men who had taken part in the burning of Colon. The large sums of money paid semi-monthly to the employés of the canal company had attracted men of bad character from the West Indies and the West Coast. These men had nothing to lose, and the prospect of plunder was an incentive to fire Panama. The city was not supplied with water, and had no fire apparatus. In the prevailing strong winds the flames, in case of conflagration, would have spread to the buildings and wharves of the Panama Railroad Company and have destroyed them. Such a disaster would have prevented the transfer of freight for some months, and thus practically have closed the transit.

My chief anxiety was therefore that I should not be able to prevent the destruction of the city.

In consequence of the difficulty met with in discharging the stores from the Acapulco, on account of the burning of the wharves in Colon, it was not until Monday, the 20th, that we were able to place them in an accessible place, a large store-house which had been built in the mean time by the Panama Railroad Company opposite Post 3.

On that day I visited Matachin and San Pablo to investigate a reported attempt to blow up the house occupied by the force at the latter station. A Spanish negro had been seen hanging about within the lines at San Pablo late in the afternoon of the 19th instant. Shortly afterwards Lieutenant Elliott was informed that a man in the neighboring camp occupied by the canal employés had threatened to blow up the garrison. Lieutenant Elliott promptly caused the arrest of the man, who had in his possession a package of dynamite with fuse. He proved to be the man who had been seen within the lines a short time previous, and his clothes were found under the barracks. The man was sent to Colon and placed in confinement. He was afterwards turned over to the Colombian authorities.

On the following morning I transferred the headquarters from Colon to Panama.

On the same day Admiral Jouett inspected the several garrisons, returning to Colon the same afternoon.

At this time it was reported that the Commanding Officer of the National Forces at Buenaventura had declined to treat with the two commissioners sent by Aizpuru, and had seized the tug in which they were sent from Panama. It afterwards turned out that the Commissioners had been offered the option of returning to Panama with the National Forces or of remaining in the State of Cauca. They preferred the latter alternative.

It was also reported that the national troops at Buenaventura were being embarked in the iron steamer Guayaquil (from which the engines and boilers had been removed), belonging to the Pacific Steam Navigation Company, and used by them as a hulk to store freight. On that day Captain Higbee was directed to order Companies B and D, under the command of Captain Collum, to proceed to Panama by the 3 o'clock train. After the arrival of these companies, they, together with a gatling from the Alliance, and a howitzer from the Swatara, all under the command of Captain Collum, were quartered at night in cars at the new passenger station, extending our lines to the bridge crossing the railroad.

On the afternoon of the 21st, accompanied by Lieutenent Cowles and Mr. Icaza, I drove over the town for the purpose of acquainting myself with the condition of the city.

On the 22d instructions were issued to the garrison at Camp Jouett, a copy of which is appended and marked H. The dispositions required by that order were made on the evening of the same day, and again on the afternoon of the 23d for practice.

On the 23d I received information that 700 national troops had embarked in the Boyaca, the hulk Guayaquil, and a schooner; later I was notified that this force had sailed, the Boyaca and canal tug towing the hulk and schooner and three whale-boats in which to land the men at Panama.

THE OCCUPATION OF PANAMA.

[See plan marked I.]

On the 24th it was reported that barricades were being erected in the streets, an indication that General Aizpuru would resist the national forces and that fighting in the streets would follow. At 11.55 a. m. our consul-general called on me and notified me that two barricades were being erected at the points marked T on the plan, and that in consequence communication would be cut off with the Central and South American cable office, marked U.

I notified the consul that I would occupy the city in half an hour, but the occupation was put off until 1 o'clock in order that the men might have their dinner comfortably.

Rear-Admiral Jouett was notified by telegraph of my intention to occupy Panama. The signal agreed upon with Captain Norton to land all the available force from his ship was made, and the following telegrams were sent to Lieutenant Allibone and to Rear-Admiral Jouett:

PANAMA, *April* 24—12.30 p. m.

Lieutenant ALLIBONE,
Special Aid, Colon:

Direct Captain Higbee to send the entire force now at Colon, with all the guns, to Panama, using the utmost dispatch. A special train will be furnished by Mr. Burt.

McCALLA.

PANAMA, *April* 24—3.40 p. m.

Admiral JOUETT, *Colon:*

Send the reserve battalion of marines to Panama by special.

McCALLA.

At 1 o'clock the disposition of the force for an entry into Panama was completed, and as soon as the boats from the Shenandoah were in sight the signal was given to advance.

Tanks of powder and a Farmer's dynamo machine, with wire and fuzes, had been obtained from the Shenandoah to be used if necessary to blow up buildings.

The several columns advanced without music, the marines in two lines deployed for street firing, the gatlings and field guns between the lines of marines. Each man carried 80 rounds of ammunition, canteen, and rubber blanket. The marines carried 40 rounds in haversacks.

The instructions contained in my letter of the 22d were carried out, except that they were so far modified that the entire center column marched to the cable office, and that the force commanded by Captain Collum marched directly to the Plaza Santa Ana by the Chemin de la Savane and the Carrera del Isthme; Captain Reid's company and the gatling from the Alliance being left to occupy the junction of the Chemin de la Savane with the road leading to the hospital. That portion of the order directing the left column to advance by the beach, if the tide permitted, had been rescinded on the 23d.

The barricade in the Carrera de Caldas was made of heavy wooden posts set in the ground 3 feet apart, connected by boarding to be backed with earth. The barricade in the Carrera de Ricuarte, near the principal cuartel, was constructed of sand bags. The former was torn down. The latter was occupied and a Gatling mounted behind it, trained on the cuartel.

Having heard that General Aizpuru would be at the Panama Railroad depot during the afternoon, I gave orders that he should be held in case he came.

The force was now disposed as follows:

Company C, of the First Battalion was at the Cable Company's office; Company E of the First Battalion, a short Gatling, and 20 men under Ensign H. M. Witzel, were at the sand-bag barricade in the Carrera de Ricuarte; Company B, First Battalion, was stationed at the consulate; company A, First Battalion, was stationed at the Pacific Mail Company's office; Lieutenant Hughes, U. S. N., with 20 blue-jackets and a short Gatling, were stationed at the junction of the Carrera de Sucre and the Cathedral Plaza. Ensign Jas. H. Oliver, U. S. N., with 20 blue-jackets and a 3-inch. B. L. R. were stationed at the junction of the Carrera de Sucre and the Carrera de Cordova. Captain Collum occupied the Plaza Santa Ana, the most important position in the city, with company A, Second Battalion, Company D, First Battalion, and 40 blue-jackets with two pieces of artillery. Junior Lieut. F. E. Sawyer and Naval Cadet I. K. Seymour, U. S. N., were in charge of the latter.

A line of sentries was posted from the Plaza Santa Ana along the Carrera Chiriqui to the bay, and another along the Carrera de Bocas

Toro to the Sea, the former connecting with a line running parallel with the bay to Camp Jouett.

At Camp Jouett there were 33 blue-jackets under Lieut. Lucien Young, U. S. N.

General Rafael Aizpuru and other revolutionary officials, namely, Senor Carlos Vallarino, Secretary of War; Carlos Mendoza, Secretary of State, and Bernardo Vallarino, Governor of Panama, were arrested near the Consulate of the United States. By request of Mr. Adamson they were taken to the consulate for a time, on account of the temporary indisposition of General Aizpuru.

I explained in brief to General Aizpuru that I had no desire to interfere with the existing government, but that the barricades in the streets cut off my communication with the Central and South American Telegraph Company's office, and that the street fighting which would inevitably ensue threatened the lives and property of American citizens, which I had been instructed to protect. I also stated that I should be compelled to detain General Aizpuru until a definite assurance was given me that the lives of Americans should not be endangered, nor their property injured or destroyed. He was given the option of going either to his headquarters or to the hotel, under guard.

General Aizpuru stated that he would give up the city; I replied that I would be happy to assume the responsibility of its protection, and through the kindness of the proprietors of the Panama Star and Herald published the following notice, with translations in Spanish and French:

NOTICE TO THE PUBLIC.

Having been informed by the Consul-General of the United States that a military force was erecting barricades which would cut off communication with the American Cable Company, I have entered the city peacefully, in order to take measures to prevent injury to American interests. All law abiding citizens will be protected. All saloons and liquor shops must be closed. The city will be policed by the force under my command, and no one will be permitted to enter the city by land or sea.

B. H. McCALLA,
Commanding the U. S. Naval Forces on the Isthmus of Panama.

MAY 24, 1885.

Later, by the invitation of Mr. Shuber, the owner of the Grand Central Hotel, General Aizpuru and his friends decided to go there, accompanied by Lieutenant Reeder, in whose custody they were placed. A platoon from Company A of the First Battalion was detailed to guard the hotel.

A subterranean passage at one time led from the old monastery in the Plaza San Francisco to the cathedral. The Plaza Santa Ana was the center of the part of the city occupied by the worst classes. It therefore became necessary to occupy the church in the Plaza Santa Ana and the Cathedral, the keys of which were cheerfully turned over by the priests in charge. Care was taken that no injury was done to the churches.

Lieut. L. Young on his arrival from the Shenandoah relieved the force of Lieutenant Berryman, U. S. M. C., at the depot. The latter at once marched his command to the Plaza Santa Ana. Later in the afternoon Lieutenant Mason, U. S. N., was placed in command at Camp Jouett.

The garrison from Colon, consisting of Companies C and E, Second Battalion, two sections of Gatling and two sections of rifled guns, under command of Lieutenant Allibone, arrived about 5 p. m. Before sunset a strong picket-line was thrown across the peninsula on which the city was built, extending from Camp Jouett to the shore on the south, and shown on the plan marked I. This line was occupied by Companies D and E of the Second Battalion, Captains Reid and Harrington, three Gatlings under Lieutenant Badger, Naval Cadet Plunkett, and Gunner Walsh, the whole force under command of Lieutenant Allibone.

Company C, Second Battalion, Captain Muse, reinforced Lieutenant-Colonel Heywood's column, and was quartered in the office of the Pacific Mail Steamship Company. The second platoon of Company A, Captain Meeker, was sent to Shuber's Hotel.

About 7 p. m. there was a quarrel between some citizens in the Cathedral Square, during which several shots were exchanged. The Gatling gun in the Calle Sucre, sufficiently elevated to clear the tops of the houses, was fired across the plaza, clearing it in a few seconds. No further disturbance occurred during the night, the city being thoroughly patrolled under the direction of Brevet Lieutenant-Colonel Heywood.

The marines of the vessels of the North Atlantic Station, anchored off Colon, had been organized by order of Rear-Admiral Jouett into a reserve battalion. This battalion, about 100 strong, under command of Captain Young, U. S. M. C., arrived at Panama about 10 p. m., and was quartered for the night in the railroad station. On the 25th the companies of the reserve battalion relieved the companies at the barricade and the cable office.

The military force of Aizpuru was said to be from 600 to 800 men; but from information furnished me I estimated it to be about 500, distributed in the cuartels or barracks marked J, K, L, S, on the plan of Panama.

On the following day, while I was at the Consulate, the Commanding Officer of the insurgent troops came there and asked if the naval force would be withdrawn to Camp Jouett provided that a guarantee were given that no barricades should be erected, and that no street fighting should be permitted. An affirmative reply was made, and at the request of the officer I saw General Aizpuru.

In anticipation, however, of a possible attack that night, instructions had been given Lieutenant Allibone to break camp and enter the city at 5.30, to leave Company D, Second Battalion, and the Gatling from the Alliance, at the Plaza Santa Ana, and to march with the rest of his force to the Cathedral Square.

To cut off communication with the principal cuartel, which had purposely been left open the previous day and night, the force in the Calle Sucre was moved into the Carrera Narino, the barricade of sand bags was moved one block to the westward, and the 12-pounder howitzer was moved to the junction of the Carreras de Caldas and de Acevedo Gomez. The rest of the force in the vicinity of the cathedral square was so disposed as to hold the parallelogram embraced generally by the bay on two sides, the Carrera de Camillo Torres, and Carrera Narino.

Upon visiting General Aizpuru, in compliance with his request, he offered to give the guarantee before mentioned. In order that there should be no misunderstanding I obtained the services of Mr. Del Valle and Mr. Millet, American citizens who were familiar with the Spanish language, and who kindly consented to act as interpreters. The following agreement was made out in Spanish and in English:

> The undersigned, Rafael Aizpuru, president of the sovereign State of Panama, and B. H. McCalla, commanding the United States naval forces on the Isthmus of Panama, have agreed to the following, viz:
>
> ARTICLE I. Once this agreement signed, Commander McCalla will withdraw the American troops at present occupying the city of Panama to the quarters which they occupied up to yesterday, in the neighborhood of the Panama Railroad station.
>
> ART. II. General Aizpuru binds himself to fulfil the duty of thoroughly protecting the lives and interests of the American citizens and foreigners residing in the city of Panama; he will not allow any fighing to take place within the limits of the city, nor will he allow barricades to be erected.
>
> ART. III. Commander McCalla will take no part in any political contest.
>
> Signed in duplicate in the city of Panama, April 25, 1885.
>
> R. AIZPURU.
> B. H. McCALLA, U. S. N.
>
> True copy of the paper in English held by General Aizpuru,.
>
> NOTE.—A copy of the agreement in Spanish is appended, marked J.

In accordance with the agreement, the naval force was withdrawn from the city about 8 p. m., except portions which remained, by request of General Aizpuru, at the Consulate and in the Plaza Santa Ana until 9 o'clock.

Some dissatisfaction was expressed at the withdrawal to the railroad depot of the naval force, and some fear least Aizpuru would be unable to afford protection to Americans, but the object of the occupation of the city having been satisfactorily attained there was no good reason for remaining there any longer. As it turned out these apprehensions were groundless.

A cablegram received from the Navy Department late on the afternoon of the 25th, left me discretion so far as holding the town was concerned.

It happened that our position at the railroad depot was the best one strategically that could have been selected. From the new passenger station all roads leading from the city could be occupied in a very short time.

During the occupation of the city the men behaved in the most exemplary manner, and though they were always prepared for an attack, and the seamen were armed with either the Hotchkiss or Lee magazine guns, no accident occurred. To express to some extent my appreciation of their behavior, the next day at inspection the following order was published:

Order.] HEADQUARTERS UNITED STATES NAVAL FORCE
ON ISTHMUS OF PANAMA, *April* 26, 1885.

The Commanding Officer desires to express to his command his appreciation of their excellent conduct under the trying circumstances of the last two days.

No higher praise can be given than that which is conveyed in the notification that there was not an accidental discharge of any weapon.

The command will be held in readiness to move at any moment, and I desire to caution it against opening fire too soon.

Our only purpose is to protect the lives and property of Americans and to keep the transit open.

B. H. McCALLA.
Commander, Commanding.

On Sunday, the 26th, there was a fight between Jamaicans and Colombians at Paraiso Station, 7½ miles from Panama. Exaggerated reports of this disturbance reached Panama, and on Monday morning, the 27th, the British Consul called on me to report that 13 Jamaicans had been shot the preceding day at Paraiso, and that the calaboose was full of wounded men. The railroad officials also reported that the station-house at Paraiso had been fired into the previous night, and that the workmen were in fear of their lives.

Obtaining permission from Rear-Admiral Jouett to send a force to that place, Captain Reid, U. S. M. C., was sent to Paraiso the same day with his company. Assistant Surgeon Ogden, U. S. N., was ordered to report to Captain Reid and in addition to the instructions of the latter, appended, marked K, he was directed to offer the services of Assistant Surgeon Ogden to the Alcalde of Paraiso in case there were wounded men needing treatment in the calaboose. None of the latter were in need of a surgeon, and reports of the affair were found to have been grossly exaggerated. Three Jamaicans were killed in a race quarrel which was brought about by drinking. Indeed, nearly all the fatal quarrels occur on Sunday, and the origin may generally be traced to liquor. On Tuesday Lieutenant Mason, with one section of artillery in an armored car, relieved Captain Reid, the latter returning to Panama with his company.

On Monday evening, the 27th, after the departure of the garrison for Paraiso, the landing party from the Iroquois (which had arrived off Panama the day before) came ashore, and was quartered for the night on the railroad wharf. Early Tuesday morning the Boyaca, with the canal tug, hulk Guayaquil, schooner, and three whale boats were seen in the bay.

Lieutenant Reeder was sent to call on the Commander-in-Chief to present my compliments, and to explain, if necessary, more fully the request contained in the following communication:

HEADQUARTERS UNITED STATES NAVAL FORCE
ON ISTHMUS OF PANAMA, *Panama, April* 28, 1885.

SIR: I have the distinguished honor, in the absence of my Commander-in-Chief, Admiral Jouett, at Colon, to inform you that for the protection of the transit across the Isthmus, and for the protection of Americans and their property, I occupy the railroad station at this place with a United States naval force.

My lines, for this purpose, necessarily extend from the railroad wharves to the passenger station at the bridge.

May I beg leave to request that the National Force under your command may be directed not to land within my lines.

I shall take the first opportunity of paying my respects to you; meanwhile I shall be most happy to place my personal services at your disposition.

I have the honor to be, very respectfully,

B. H. McCALLA,
Commander U. S. N., Commanding.

To the COMMANDER-IN-CHIEF COLOMBIAN NATIONAL FORCES OFF PANAMA.

Colonel Montoya, who had been appointed Military and Civil Chief of the State of Panama, was on board the Boyaca, as well as Colonel Reyes, the Commander-in-Chief of the military force, which consisted of about 600 men. During the conversation Colonel Reyes stated to Lieutenant Reeder that he was having the entrance to the Rio Grande, south of the city, examined with the view of finding out whether he would be able to land his forces in that vicinity.

Rear-Admiral Jouett having come to Panama on the afternoon of Tuesday the 28th, on Wednesday Colonels Reyes and Montoya and Aizpuru met in the railroad office, Rear-Admiral Jouett taking part in the conference. The conference resulted in an agreement being signed between the representatives of the Colombian Government and Aizpuru by which the latter was to surrender.

The quasi government represented by Aizpuru having entirely disappeared with the signing of the capitulation, the reasons which had hitherto made it imperative to prevent the landing of the Colombian forces within our lines now ceased to exist. They accordingly landed at the railroad wharf early on the morning of the 30th, and we were able to facilitate their disembarkation. By the terms of this agreement the national troops marched into the city from their camp in the savannah, to the north of the lines occupied by us, at 1 p. m. on Thursday the 30th; a battalion under Captain Collum, made up of two companies of the Second Battalion of Marines, one Gatling section, and one B. L. R. section, were drawn up on the road in front of the new passenger station, and presented arms as the Colombian force under Colonel Reyes marched past. The latter halted his command and returned the salute. On the arrival of Colonel Reyes at the presidency, the Colombian flag was hoisted in Camp Jouett, and a national salute fired from the field pieces in front of our headquarters. This salute was returned on the following morning.

On the 30th the forces from the Shenandoah, Swatara, and Alliance returned to their ships.

On Friday, May 1, the four companies of the Second Battalion of Marines, two sections of the B. L. R. Battalion, and the Gatling Battalion returned to Colon, Lieutenant Allibone relieving Lieutenant Colahan of the command of the force at that place.

On Friday morning with Lieutenant Cowles, accompanied by Mr. Adamson, I called upon Colonels Montoya and Reyes. I had the pleasure of congratulating them upon their promotion to the rank of General, information to that effect having been received from Bogota. In this connection I desire to state that in my opinion the people of the Isthmus are to be congratulated upon having in authority two such able, energetic, and accomplished men as Generals Montoya and Reyes. Without the determination shown by these men the suppression of the rebellion must have been postponed and our stay on the Isthmus lengthened.

Before the arrival of the national troops from Cauca there had been much talk among those who sympathized with Aizpuru in regard to the ferocity and brutality of the expected Colombian forces. I am glad to state here that I saw them all land, and failed to detect among them any man who had the appearance of deserving such a reputation.

I returned to Colon on May 1, inspecting the garrisons at Matachin and San Pablo on the way. The same day the garrison at Paraiso returned to Colon.

On May 5, in consequence of the failure of the insurgents to deliver up their arms as agreed upon, General Aizpuru and his principal adherents were arrested and confined by order of General Reyes.

In consequence of the unsettled condition of the Isthmus, General Reyes found it necessary to issue the following proclamation:

The Commander-in-Chief of the Colombian Forces to the Inhabitants of the Isthmus of Panama:

In order to more effectually punish the numerous criminals who have disturbed the peace of the Isthmus, and who still persist in their outrageous crimes, I have declared martial law in this State as the best means to secure order for the present.

All persons are earnestly requested to remain at their homes and continue their customary occupations so that further disorder may be avoided.

I shall protect all peaceable and well disposed persons to the utmost extent of my power.

RAFAEL REYES,
General, Commander-in-Chief of the National Forces.

COLON, *May* 5, 1885.

On the 5th of May a stand of colors was presented to the Second Battalion of Marines, and guide flags to the Gatling and 3-inch B. L. R. Battalions. (The First Battalion had been supplied.)

On the 7th of May portions of the First Battalion of Marines were sent to San Pablo and Colon, and that night the remainder of the force under my command sailed for New York on the Pacific Mail steamship Colon. The Colon arrived the morning of the 16th of May, and in compliance with the instructions of the Department, the men were transferred to the Brooklyn navy-yard and the officers were ordered to resume the duties in which they were engaged prior to sailing for the Isthmus.

It is proper to state that Lieutenant-Commander Longnecker, U. S. N., with a landing party of 125 blue-jackets and marines from the United States steamer Shenandoah held the Panama Railroad station (Camp Jouett) from the 7th of April until the arrival of Lieutenant-Colonel Heywood, U. S. M. C., with the naval force under his command, on the 11th of April.

I take this opportunity of presenting certain conclusions as the result of my observations upon the Isthmus.

MARINES.

While the Marine Corps is highly efficient and admirably disciplined, their tactics are of a by-gone day. "Heavy Infantry" disappeared with the introduction of the long-range breech-loader. Unless officers and men are instructed in the principles of modern tactics and are taught to avail themselves of cover in advancing to an attack, they will only discover its advantages by fatal experience, as was the case with the Russian infantry during the last Russo-Turkish war.

The method of developing a modern fighting line advocated by the late General Upton in his book under the head of "deploying as skirmishers by numbers," is well adapted for the purpose, but it requires additional rules for deployment when in column. The manual for the rifle is also obsolete. "Carry Arms" should be abolished, and the different movements in the manual of arms should be executed from an "Order," in which position the piece should habitually be when at a halt. The above applies with equal force to the instruction of blue-jackets.

All Marine Officers should pass through the Torpedo School at Newport, R. I., and there should be one or more always stationed at the Artillery School at Fort Monroe.

The men should be instructed in practical electricity as applied to the use of land and submarine mines.

Much of the time now wasted in barracks could be profitably employed in drilling with machine guns and field pieces, which could be borrowed from the Ordnance Bureau. Every summer the marines in the United States should go into camp, half of those stationed at each naval station marching to a common center for that purpose. In midsummer they could be relieved by those who had remained on duty at the stations. The officers should sleep and mess in the camp. I am quite sure that Army officers would welcome an addition of this kind to the force of the Army which annually encamps in the vicinity of Washington.

The officers of the Marine Corps suffer, as do naval officers, from the want of a healthy flow of promotion, and from the absence of all stimulus to mental activity caused by the present system of advancement.

It may be well to state here that blue-jackets and marines performed outpost and sentry duty equally well.

LANDING PARTIES.

It has frequently been necessary in the past, and it will continue to be necessary in the future, to land a force of seaman and marines from all of our squadrons. The landing party from each ship, as well as the naval brigade of each squadron, should therefore be landed at least once a week for practice. There has been too much objection to such exercises on the part of naval officers, but the need of them must now be apparent to the most conservative. The necessity for such practice is now thoroughly recognized by the officers of other naval powers. Dress parades should be abolished, and only those manœuvres likely to be of use in actual service should be practiced.

I should recommend the adoption of some form of shield for use with the gatling gun and the 3-inch B. L. R.

The landing party which came on shore from the Iroquois under command of Lieutenant-Commander Stockton, U. S. N., showed evidence of having been carefully organized and frequently drilled.

ARMS, EQUIPMENT, AND CLOTHING.

The marines were armed with the Springfield rifle, the blue-jackets, (except the 8 cannoneers of each gatling and field piece, who carried revolvers and cutlasses) with the Lee magazine rifle.

More or less complaint was made of injury to the firing pins of the Springfield, and two accidental discharges occurred in my presence, caused by the shock due to the hammer at half cock striking the left fore-arm when shifting the piece from the "right shoulder," to "support arms." The Lee magazine rifles gave us no trouble, none of them having been disabled during the time they were in service. The model of this rifle had the disadvantage of being about 3 or 4 inches shorter than the rifle adopted by all nations for their infantry, and it was fitted with an inferior rear sight. Fortunately there was no fighting, and our force did not, in this instance, suffer from the reduced range and want of accuracy due to the shortness of barrel. The hands of the men, however, were frequently cut by the sharp edges of the rear sights. There seems to be no good reason why our seamen should not be armed with rifles equal in length of range and in sights to the most accurate supplied to the infantry of other governments.

The blue-jackets had grey webbing belts which fastened in front, and contained pouches for two rows of cartridges (eighty in all), the weight being transferred to the shoulders by means of cross straps; the marines had white leather belts and two cartridge boxes containing twenty cartridges each. The former answered admirably; the latter had the disadvantages of offering a good target to the enemy, of having no shoulder support, of adding materially to the discomfort and fatigue of the men wearing them, and of not carrying sufficient cartridges. They should be abolished at once. I should recommend that each seaman and marine be supplied with brown or tan-colored webbing belts, one about the waist containg forty cartridges, with shoulder supports, the other containing the same number of cartridges, to be worn over the right shoulder and under the left arm. The most convenient place to carry cartridges is in front of the center of the body. The space required for the clasps of belts is necessarily without cartridges. Therefore it would facilitate rapid firing if the waist belt were clasped on the side under the left arm.

In consequence of the long-range rifles now in use it becomes important to select neutral colors for uniform. White offers an excellent target. Some other colors should therefore be adopted for the helmets of the marines and the leggings of seamen. This necessity was impressed upon all the officers who were in Panama during the night of occupation. To those who advocate white on the score of effect, it is only necessary to say that the most serviceable uniform is always the most effective.

The helmets of the marines are much too heavy; those for naval officers, although much lighter, could also be reduced in weight. The fatigue cap for both officers and enlisted men of the Marine Corps is in every way unserviceable, and should be changed for one which has greater air space and better protection for the eyes. Without the straw hats purchased by direction of the Department, and issued to the blue-jackets, the latter would have been very uncomfortable, and would probably have suffered severely from the effects of the sun.. Marines on ship-board should always be provided with leggings, because from the character of the service they are likely to perform when forming part of a landing party, the leggings are as indispensable to them as to seamen.

AMMUNITION.

A large supply of serviceable rifle and revolver ammunition should be kept in readiness for instant service. When the Navy is called upon for an armed force the force is required in a hurry. The First Battalion of marines, about 225 strong, sailed from New York the day after the order was given to organize it. But 20,000 rounds of serviceable ammunition could be supplied to it, consequently 40,000 rounds of cartridges marked "unserviceable" were added to bring the amount up to 60,000 rounds.

With the entire force of 650 men and 3 gatlings, but 100,000 rounds of "serviceable" ammunition were supplied, an amount in my opinion much too small considering the distance of the Isthmus from the base of supplies, and the enormous consumption of cartridges by breech loaders, magazine and machine guns. The expedition should have been supplied with at least 300,000 rounds.

Of the pistol ammunition landed from the Swatara for the use of her men 75 per cent. was found to be too large for the pistols, and prevented the breech-blocks from closing.

The haversacks were not quite large enough to carry two days' provisions. The inside of the haversack might be fitted with small compartments or canvas pouches for tea, coffee, sugar, and salt. They, together with the canteens and blanket bags, should be numbered consecutively, in order that they may be recognized by their owners. Without numbers they are likely to be disfigured by marks or names.

The canteens were made from the ordinary tin of commerce and rusted badly in use. It will be advisable to consider the question of substituting some kind of natural or prepared wood for the tin.

INDIA-RUBBER BLANKETS.

The india-rubber blankets obtained from the army and taken to the Isthmus in the Acapulco were found most serviceable. Each non-commissioned officer, petty officer, and enlisted man carried one. They were also issued to such of the officers as were not provided with waterproof clothing.

PROVISIONS.

The provisions were excellent in quality and ample in variety; the only exception in quality being the tea, which had deteriorated by age.

Lieutenant Allibone reported that the pressed corned beef was excellent, but when served out and eaten cold, as was sometimes necessary, it produced indigestion; causing vomiting in a number of cases.

The men having their canteens filled with water drank immoderately, which probably caused the sickness mentioned. If the corned beef were cooked with potatoes, or with rice and biscuit in the shape of a stew, it would make a palatable dish.

All articles were put up in large packages. In issuing rations to the different detachments this arrangement was found very inconvenient. A barrel of beans, pork, beef, &c., served out to a small number of men caused much waste under the circumstances incident to the service. On each ship in commission, articles forming part of the Navy ration should be put up in smaller packages and kept ready for issue to the "landing party."

During our service on the Isthmus it was often necessary to move detachments without warning, and the want was felt of a supply of some form of compressed food from which, by the simple addition of boiling water, each man could have quickly made a nourishing soup.

WATER.

There is no distilling apparatus on the line of railroad. In the absence of distillers at the Brooklyn Navy-yard ready for shipment, a small boiler, pump, pipe, &c., were supplied by the Engineer Department to boil drinking water, if necessary.

Distilled water for drinking and cooking was supplied to the Naval Force in breakers from the ships at Colon and Panama.

The water at Frijoles, where there is a pumping station for the railroad, was tested and pronounced fit to drink, but an inspection of the source of supply was not reassuring.

From Taboga Island, Bay of Panama, excellent water can be obtained; but at the end of the dry season the supply is always very low.

HEALTH.

There were the usual cases of fever and other diseases to be expected on the Isthmus and one fatal case of yellow fever, thought to exposure on the night of the occupation of Panama; but the general health of the command was excellent; greatly due, in my opinion, to the comfortable quarters generously provided by Mr. Burt, the superintendent of the Panama Railroad Company, and to the efforts of the officers to protect the men from the sun and rain. It was a matter of interest and surprise that the blue-jackets suffered much less from climatic influences than the marines, although both performed precisely the same duties.

At Matachin and San Pablo there was practically no sick list. Although the elevation of this section of the Isthmus may have had much to do with the good sanitary condition of the garrisons, the excellent regulations established by the commanding officer largely contributed to this result.

CASUALTIES.

Private Marine David Irvine, Company E, First Battalion, was shot on the night of the 28th of April, while attempting to enter our lines, having been outside without authority. Thomas Brennan, Coal Heaver, attached to the Alliance, was shot on the morning of April 29 by Private Murray, Company E, First Battalion, during a quarrel. Both wounds proved fatal. Angus Flemming, Seaman Apprentice, from the Alliance, died of yellow fever on the 30th of April, in the French hospital at Panama.

MEDICAL SUPPLIES.

I desire to call attention to the medical supplies sent out with the First Battalion of Marines, in the City of Para. Although ample supplies were afterwards sent, those furnished the above-mentioned force were entirely inadequate to the purpose intended; consequently such medicines as were needed had to be bought at comparatively great cost in Panama.

I was informed that upon application being made for medical stores such as were likely to be required on the Isthmus, the Medical Officer who had charge of these supplies stated that the expedition would require but few medicines since it was only meant for a demonstration and would return immediately. Such a remark, if made, would show that the necessity of making an expedition complete in all its details in order to insure its success was not understood nor appreciated.

Soon after our arrival at Colon, knowing by experience the necessity of having a full medical staff, I applied by cable for one additional surgeon and one apothecary. The application was not, however, granted. As it happened, Dr. Whiting had been taken down with the fever two days after the arrival of the Acapulco at Colon, and the only apothecary attached to the force proved inefficient and was of no assistance. The expedition was therefore subjected to great inconvenience, which might have had very serious results, and the officers to considerable anxiety, from the absence of the necessary medical attendance. If a Commanding Officer is to be held responsible for the success of an expedition it is imperative that a reasonable request of this nature should be promptly granted.

In this connection I may mention that on the passage from New York Dr. Whiting gave me a copy of a paper, entitled "Notes" or "Suggestions on Sanitary Precautions," signed by the Surgeon-General of the Navy and approved by the Secretary of the Navy. They were not addressed, but were given to Dr. Whiting by the Senior Medical Officer stationed at the Brooklyn Navy-Yard. Although brought to the attention of the Commanding Officer in this somewhat informal manner, they were regarded as an order of the Department, and were enforced during the service on the Isthmus. The Commanding Officer of each garrison was supplied with a copy, and they were afterwards promulgated by the Commander-in-Chief in a Squadron General Order. The suggestions were found to be valuable in practice.

It was found before leaving New York that a portion of the ordnance supplies for blue-jackets was about to be shipped on board the City of Para, in compliance with the directions of the Bureau of Ordnance. As the execution of this order would have precluded the possibility of giving the seamen embarked on board the Acapulco the necessary instruction in the use of their arms during the voyage down, arrangements were made to take the equipments in the latter vessel.

The points referred to above illustrate the necessity for a central office in the Navy Department, the chief of which, having received a military education and being thoroughly cognizant of the intentions and desires of the Secretary, should be held responsible for the technical details necessary to fit out an expedition or ship in the most efficient manner. He should be aware of the contents of all instructions sent by officials relating to the fitting out of the force. Under the present system the Chiefs of half a dozen Bureaus may overwhelm the Commanding officer of an expedition or the Commandant of a Station with confusing telegrams, thereby causing delay or possible failure.

This suggestion is not meant to reflect upon the Bureau system, but is intended to call attention to the need of a central office in the Navy Department, by which unity of action may be secured and all confusion of the kind referred to be avoided in future expeditions.

TRANSPORTS.

The larger and better organized the force which a naval squadron can throw on shore quickly the more formidable that squadron becomes. This has always been the case! It seems probable that in future naval operations an additional number of seamen and marines, organized in naval brigades, will be carried in transports accompanying the battle ships.

In common with other maritime nations, the United States should own naval transports. One would have been of great use upon this occasion, and, in addition, would have answered as a hospital ship and movable base. During peace transports could be used to transport our own men or to transfer detachments of the Army from post to post on the sea-board. The experience gained in embarking and disembarking troops would be valuable to both branches of the service.

PANAMA RAILROAD COMPANY.

The Panama Railroad, under the able management of Mr. G. A. Burt, the present General Superintendent, has been vastly improved since my last visit to the Isthmus, three years ago. The rolling stock (a large part of which was destroyed when Colon was burned) was in excellent condition; the road bed was well ballasted, the embankments were in good order, and the trains ran on schedule time. It was not uncommon to run a locomotive and one car over the 47½ miles between Colon and Panama in one hour and eighteen or nineteen minutes, although there are 10½ miles of curves in that distance. Upon one occasion I was carried in a "special" 11 miles in thirteen and one-half minutes.

The few clusters of native huts which marked the stations before the advent of the canal company had grown into an almost continuous line of thriving villages. The passenger traffic has grown enormously, increasing from 26,801 in 1880 to 515,520 in 1884, nearly all of it local. Six of the daily trains, three each way, were for passengers. The gross earnings of the road for the year 1884 were $3,494,776.

I take great pleasure in stating that Mr. Burt did everything in his power to make officers and men comfortable in buildings owned by the company, and that he was always ready to transport our forces at a moment's notice. Mr. Ernesto Icaza, the agent of the Panama Railroad at Panama, often rendered us valuable service at considerable peril and inconvenience to himself.

Appended, marked L, is a map and profile of the railroad.

PERSONNEL.

While all the officers did well, I feel it my duty to call the attention of the Department to those who came under my immediate observation.

* * * * * * *

The conduct and efficiency of the noncommissioned and petty officers are worthy of the highest praise. The behavior of the enlisted men was admirable; less than 3 per cent. were found to be unreliable on duty or in camp. When the peculiar temptations to which they were subjected in the trying climate of the Isthmus are considered, this fact is highly creditable to them.

A statement of the force employed during the occupation of Panama is appended, marked O, together with a copy of Squadron General Order No. 19, marked P.

In conclusion I desire to state that I consider it a great honor to have commanded so fine a body of officers and men.

Very respectfully your obedient servant,

B. H. McCALLA,
Commander, United States Navy.

B.

Daily routine, Pacific Mail steamship Acapulco.

	A. M.
Reveille	5.45
Wash clothes	6.00
Breakfast	7.00
Sick call	9.00
Quarters	9.30
Recall from drill	10.30
Music practice	10.45 11.30
	P. M.
Drill call	2.30
Recall from drill	3.30
Supper	4.30
Sick call	5.00
Tattoo	9.00
Taps	9.10

A marine officer of the guard and a naval officer were on duty day and night.

C.

NORTH ATLANTIC STATION,
U. S. FLAGSHIP TENNESSEE (1st rate),
Aspinwall, U. S. C., April 15, 1885.

SIR: By direction of the Navy Department you will please assume command of the forces which have been sent from New York by steamer for the protection of American interests on the Isthmus of Panama. You will also include in your command all the forces which have been landed from the North Atlantic squadron.

You will land the men now on board the Acapulco at your own discretion, as soon as they can be properly accommodated on shore.

The transit is open and trains have been running regularly since the 11th instant. Aspinwall is held by the Colombian troops, and Panama is in the hands of the insurgents.

I inclose for your information a memorandum showing the number and disposition of the forces on shore; also, copies of a squadron general order relative to sanitary precautions to be observed, and of my orders to Lieutenant Colahan and Colonel Heywood.

Very respectfully,

JAS. E. JOUETT,
Rear-Admiral, Commanding U. S. Naval Force on North Atlantic Station.

Commander B. H. McCALLA, *U. S. Navy,*
Pacific Mail Steamer Acapulco, Aspinwall, U. S. C.

U. S. FLAGSHIP TENNESSEE (1st rate),
Aspinwall, U. S. C., April 11, 1885.

SIR: Proceed to Panama with the battalion of marines under your command, for the protection of American lives and property in that vicinity. The details of this service are left to your discretion.

Panama is now in the hands of the revolutionary forces, and it is feared that if the place is attacked by the regular Colombian troops these revolutionists will attempt to destroy the city, or portions of it, by burning. As the burning of Panama would involve the destruction of much American and other foreign property, you will prevent it if possible.

Please advise Captain Norton, commanding United States Ship Shenandoah, now at Panama, of your arrival there.

I inclose herewith a copy of my telegraphic instructions from the Department, and also some extracts of a sworn protest by Mr. George A. Burt, general superintendent of the Panama Railroad Company, for your information.

I have detailed a Gatling gun and a 12-pounder S. B. howitzer, with officers and crew, for service with your command.

The officers are directed to report to you.

Very respectfully,

JAS. E. JOUETT,
Rear-Admiral, Commanding U. S. Naval Force on North Atlantic Station.

Maj. CHARLES HEYWOOD,
U. S. M. C., Commanding Marine Battalion, Isthmus of Panama.

U. S. FLAGSHIP TENNESSEE,
Aspinwall, U. S. C., April 11, 1885.

SIR: You will proceed on shore and assume command of the forces landed for the protection of life and property in Aspinwall, relieving Lieut. W. P. Elliott, U. S. N., and directing him to return to his ship.

I desire to guard the city of Aspinwall from further attack or injury, and to preserve the property that remains, especially that belonging to Americans.

You are authorized to dispose of the forces landed from the fleet at your discretion, in order to accomplish the above-named objects; then report to me.

Very respectfully,

JAS. E. JOUETT,
Rear-Admiral, Commanding U. S. Naval Force on North Atlantic Station.

Lieut. C. E. COLAHAN,
U. S. N., United States Ship Tennessee.

GENERAL ORDER }
No. 16. }

NORTH ATLANTIC STATION,
U. S. FLAGSHIP TENNESSEE (1st rate),
Aspinwall, *April* 16, 1885.

The following sanitary precautions will be observed by all serving on shore on the Isthmus of Panama or in the tropics:

SANITARY PRECAUTIONS—PANAMA.

Prevalent diseases are malarial fevers, yellow fever, diarrhea, dysentery, sunstroke.

The most common causes that lead to a depressed vital condition, and so render the individual exposed to the causes of disease, are want of food, fatigue, excessive moisture, and these apply with multiplied force to masses of men, to which is added the dangerous factor of overcrowding.

Water supply.—There is a distiller on the wharf at Aspinwall. If destroyed, have a regular water police to supply the camp with distilled water from the ships. No other water to be used for culinary or drinking purposes.

Food.—Meals at regular hours—warm. The guard on duty at night to have a cup of hot coffee with buiscuit before going on duty, and this to apply to all relief parties. On turning out to go as soon as convenient to breakfast, previous to any exposure. The cooking to be inspected, and the food also before cooking.

Clothing.—Have a dry suit for each man, a water-proof coat to be used only when on guard in the rain. The weight to be carried to be diminished as much as possible; every ounce weight added to the clothing or materials to be carried imposes extra work, and in just that degree is a minus quality so far as efficiency is concerned. Flannel belts to be worn covering the abdomen. The head-gear to be as light as possible.

Air.—Avoid overcrowding in tents. If in barracks, have the floors elevated above the ground. A barrack with a wood roof, ridge ventilated and water-proofed canvas sides, so that they can be raised to admit air, with mosquito nettings for each man, is a ready and efficient help in the damp, hot, malarious climate against the effects of malaria.

Parkes states that even such small means as a mosquito netting is useful in preventing malarial infection.

General hints.—Burn all refuse from kitchen. Latrines to be inspected daily. The police of the camp and its sanitary conservancy to be rigid and exact.

No drills in full dress, or even in undress when the thermometer is near 80 degrees F., remembering the observations of Obernies on the danger from heat apoplexy from exercise at such temperature.

Inspections after sunrise or in the early evening. Scouting parties or detached parties to carry shelter tents and the usual boat cooking-stove.

If the rolling-stock of the railroad is utilized to transport troops, then use the inclosed freight cars for barracks. Canteens to be filled with weak cold tea. The detail for inspection to be minute, for "For want of a nail the shoe was lost," &c.

The greatest care must be exercised to preserve dryness in the clothing of the command, the tents, barracks, &c.

These suggestions present a summary from personal experience, and from a careful reading of the sanitary results of the Abyssinian war and the present experiences of the British army in the Soudan.

F. M. GUNNELL,
Surgeon-General.
JAS. E. JOUETT,
Rear-Admiral, Commanding U. S. Naval Force on the North Atlantic Station.

NORTH ATLANTIC STATION,
U. S. FLAGSHIP TENNESSEE (1st rate),
Aspinwall, U. S. C., April 17, 1885.

SIR: I send inclosed for your information a copy of my instructions from the honorable Secretary of the Navy relative to the purpose for which our Government has sent so extensive an expedition to the Isthmus of Panama, together with a copy of a letter which I addressed, upon my arrival here, to Col. Ramon Ulloa, of the Colombian Guard, the only representative of the constitutional government of Colombia who was in this vicinity at that time.

You will please require your command to carefully comply with the Department's instructions relative to the conduct of our forces while they remain on the Isthmus.

As I have already informed you, the city of Panama is now in the hands of the revolutionary forces, commanded by one Aizpuru, who assumes the title of President of the state. I do not wish to recognize the authority of the said Aizpuru in any way.

The regular Colombian forces have recently been very successful in the interior of Colombia, and I trust they will soon come to this Isthmus, re-establish the authority of the constitutional government, afford adequate security to life and property, and enforce order.

It is rumored that Aizpuru has threatened to burn Panama in case the Government forces attack him there. As the burning of Panama would cause the destruction of much property belonging to Americans, interrupt the transit, besides being an act of vandalism, you will prevent it if possible, with the force under your command.

I gave orders to this effect to Colonel Heywood before you assumed command of the force on the Isthmus.

I also learn, by rumor, that there is a number of evil-disposed persons at Matachin. You will, therefore, please direct the officer commanding that post to be vigilant, in order that excesses may be prevented in that vicinity.

I do not intend to allow any arms or ammunition to be introduced into this country during the present disturbance. It is reported to me that one hundred and forty-five boxes of cartridges have recently been landed here for parties on the Isthums by the steamer City of Para. I shall have them sent back to New York by the same steamer. You will please see that all freight arriving at the Isthmus is examined by some officer of your command, and will not allow arms or ammunition to be landed without my authority.

In order to preserve the strict neutrality of the Isthmus of Panama and to avoid interruption to the transit, you will please prevent any insurgent force from landing or operating in this vicinity.

Please keep me fully informed in regard to all matters affecting your command and our interests on the Isthmus.

Send daily sick report.

Very respectfully,

JAS. E. JOUETT,
Rear-Admiral, Commanding U. S. Naval Force on North Atlantic Station.

Commander B. H. McCALLA, *U. S. N.*
Commanding Naval Brigade, Isthmus of Panama.

OFFICIAL TELEGRAM.

WASHINGTON, D. C., *April* 3, 1885.

Rear-Admiral JAMES E. JOUETT,
U. S. S. Tennessee, Navy-Yard, Florida:

In addition to the force under your command in the steamships Tennessee, Swatara, Alliance, and Galena, all of which should be at Aspinwall upon your arrival, you will be re-enforced by about two hundred marines, dispatched to-day from New York by the steamship City of Para with tents and camp equipage. To provide for further contingencies, supplies will be sent at once. The duty you are called upon to perform calls for the exercise of great discretion. The object of the expedition is the performance by the United States of its citizens, to preserve the neutrality and keep open the transit from Colon to Panama, and further to protect the lives and property of American citizens. The circumstances, as understood, from which the necessity for the expedition has arisen are, in general, that a steamship belonging to Americans has been seized at Colon by an armed force and goods in transit taken from her, her officers and the American Consul imprisoned, and the transit across the Isthmus interrupted. With the consequences involved in these past acts you are not concerned. Your sole duty is confined to seeing that a free and uninterrupted transit across the Isthmus is restored, and that the lives and property of American citizens are protected.

If on your arrival at the Isthmus order shall have been restored, and the Colombian authorities are adequate to the protection of life and property and the maintenance of the free transit, you will interfere in no respect with the constituted authorities, but report and await orders.

You have no part to perform in the political or social disorder of Colombia, and it *will* be your duty to see that no irritation or unfriendliness shall arise from your presence at the Isthmus.

The incidental exercise of humanity towards American citizens in exigencies must be left to your sound discretion.

W. C. WHITNEY.
Secretary of the Navy.

D.

HDQRS. U. S. NAVAL FORCE ON ISTHMUS OF PANAMA,
April 17, 1885.

SIR: In addition to the instructions received from the commander-in-chief of the North Atlantic Station, which you will continue to enforce, be pleased to prohibit the use of all wines, spirituous and malt liquors. Report to me daily the condition of your command by the 11.30 train or by telegraph; keep me advised of the political and military situation in Panama; hold your entire force at all times in readiness to move. Make requisition on Paymaster Rand at Aspinwall for any supplies necessary to the comfort and health of officers and men. If necessary, purchase what you require in Panama and forward the bills to me. Avoid, as far as possible, ceremonies and parades. Instruct your officers and men early in the morning and late in the afternoon. Tea is better for all than coffee; use the latter but once a day; of the former you can have all that you desire.

Keep the transit open, and, should the emergency arise, exhaust every means in your power to protect the lives and property of Americans. In my absence from Panama open all cablegrams addressed to me, and repeat them either by mail or by wire as you may deem advisable. I will keep you advised of my whereabouts.

Very respectfully,

B. H. McCALLA,
Commanding U. S. Naval Force on the Isthmus of Panama.

Maj. and Lieut. Col. C. HEYWOOD, *U. S. M. C.*,
Commanding at Panama.

HDQRS. U. S. NAVAL FORCE ON THE ISTHMUS OF PANAMA,
Colon, April 17, 1885.

SIR: Proceed to Matachin, in a special train that will be provided by the Panama Railroad Company to follow the 3 p. m., with the company now under your command, and relieve Lieutenant Impey and the garrison now at that place.

I have directed the commanding officers of a section of artillery and of a Gatling gun to report to you as part of your command.

Your duty will be to keep the transit open, to protect the lives and property of American citizens, and to have your command in the highest state of efficiency. Take every precaution to preserve the health and lives of your command.

Prohibit the use of wines, spirituous and malt liquors. Dispense with all unnecessary ceremony and parades. Instruct your men in the early morning and late in the afternoon, avoiding the sun in the middle of the day. Take with you 3,000 rounds of rifle ammunition in excess of what has been served out. I inclose for your guidance a copy of "Notes on Sanitary Precautions" and a copy of General Order No. 15, North Atlantic Station.

Very respectfully,

B. H. McCALLA,
Commanding U. S. Naval Force on Isthmus of Panama.

Capt. R. W. HUNTINGTON, *U. S. M. C.*,
Commanding Company A, Second Battalion U. S. Marines, Colon.

HDQRS. U. S. NAVAL FORCE ON THE ISTHMUS OF PANAMA,
Colon, April 17, 1885.

SIR: You will relieve the command at garrison No. 1 at 5.30 to-day. You will dispose of your force so as to protect the water approach to Colon. A 3-inch rifle with 30 rounds shrapnel, 20 rounds shell, and the necessary primers and fuses will be issued to you.

Place a commissioned officer in charge of this gun, and direct him to instruct in its use the men necessary to work it. Issue 40 rounds of ammunition to each man, and take 1,000 rounds additional. Protect the lives and property of American citizens. Do not expose your men to the sun in the middle of the day. Instruct them early in the morning and late in the afternoon, and take every precaution to protect the health and lives of your command. Prohibit the use of wines, spirituous and malt liquors. Inclosed you will find for your guidance General Order No. 15, North Atlantic Station, and "Notes on Sanitary Precautions."

Continue to carry out the instructions now in force at garrison No. 1.

Very respectfully,

B. H. McCALLA,
Commanding U. S. Naval Force on the Isthmus of Panama.

Capt. R. S. COLLUM, *U. S. M. C.*,
Commanding Company E, Second Battalion, Colon.

HDQRS. U. S. NAVAL FORCE ON ISTHMUS OF PANAMA,
Colon, April 17, 1885.

SIR: Order Capt. Geo. C. Reid, with his company, to report to Lieutenant Mason for duty in connection with the protection of trains between Colon and Panama; with the remaining two companies of 2d Battalion relieve Nos. 2 and 3 garrisons at 5.30 p. m., to-day. Aquaint yourself with the disposition of the naval forces in the vicinity of Colon, as well as the approaches to that place.

Garrison No. 3 is headquarters. In my absence you will have command of the entire naval force at Colon. Your duty is to protect the lives and property of American citizens. There is a force of one hundred men of the Colombian Government in Aspinwall.

Carry out the orders now in force in the garrison. Prohibit the use of all wines, spirituous and malt liquors in your command, and take every precaution to protect the lives and health of your officers and men. Avoid unnecessary parades and ceremonies. Keep your men out of the sun in the middle of the day as much as possible. Instruct them in the early morning and late in the afternoon. Issue 40 pounds of ammunitiom to each man and take 1,000 rounds extra with you for each company. I inclose for your guidance copies of General Order No. 15 and "Notes on Sanitary Precautions."

One Gatling gun with 1,000 rounds and caisson will be assigned to you. Be pleased to place it in charge of a commissioned officer and direct him to instruct the men necessary to its use.

Very respectfully,

B. H. McCALLA,
Commander, Commanding U. S. Naval Force.

Capt. J. H. HIGBEE, *U. S. M. C.*,
Commanding Second Battalion U. S. Marines.

HDQRS. U. S. NAVAL FORCE ON THE ISTHMUS OF PANAMA,
Colon, April 17, 1885.

SIR: You will relieve Lieutenant Hosley, in command of No. 4 garrison, at 5.30 to-day, taking with you the remainder of your battalion.

Protect the lives and property of American citizens. Take every precaution to protect the health and lives of your command. Keep your men out of the sun in the middle of the day. Instruct them early in the morning or late in the evening, and avoid all unnecessary parades and ceremonies. Prohibit the use of wines, spirituous and malt liquors. Inclosed you will find for your guidance General Order No. 15, North Atlantic Station, and "Notes on Sanitary Precautions." Acquaint yourself with the regulations in force at the garrison and carry them out until further orders.

With regard to this garrison, the importance of guarding the causeway by which an insurgent force would be apt to approach is called to your attention.

Very respectfully,

B. H. McCALLA,
Commanding U. S. Naval Force on the Isthmus of Panama.

Lieut. C. O. ALLIBONE, *U. S. N.*,
Commanding Gatling Battalion, Colon.

HDQRS. U. S. NAVAL FORCE ON ISTHMUS OF PANAMA,
Colon, April 17, 1885.

SIR: You will relieve Lieutenant Kimball in command of the train guards in time to place guards on the early train to-morrow morning. Capt. Geo. C. Reid, U. S. M. C., has been directed to report to you with the company under his command. In addition, you will have the two remaining sections of your battalion.

Acquaint yourself with the duties now performed by Lieutenant Kimball's command. Keep the transit open. Protect the lives and property of Americans. Enforce the regulations of the railroad company. Consult with Mr. Burt, the superintendent of the Panama Railroad, and do anything in your power to aid him and the officials of the trains in guaranteeing safe conduct to passenger and freight. Take every precaution to preserve the health and lives of your command. Omit unnecessary ceremonies and parades. Prohibit the use of wines, spirituous and malt liquors. Protect the men from the sun as much as possible in the middle of the day, instructing them early in the morning and late in the afternoon. Your attention is called to the necessity of exercising tact in the important duty assigned to you.

Inclosed you will find for your guidance General Order No. 15, North Atlantic Station, and "Notes on Sanitary Precautions."

Very respectfully,

B. H. McCALLA,
Commanding U. S. Naval Force on the Isthmus of Panama.

Lieut. T. B. M. MASON, *U. S. N.*,
Commanding Battalion of Rifled Guns, Colon.

G.

Commander Bowman H. McCalla, U. S. N., Commanding.

PERSONAL STAFF.

Lieut. William S. Cowles, U. S. N., adjutant-general.
Lieut. William H. Reeder, U. S. N., A. D. C.

GENERAL STAFF.

Paymaster Stephen Rand, jr., U. S. N.
Passed Assistant Surgeon Robert Whiting, U. S. N.

COLON GARRISON.

Capt. J. H. Higbee, U. S. M. C., Commanding; First Lieut. W. F. Spicer, U. S. M. C., adjutant.

Post 1.—Capt. R. S. Collum, U. S. M. C., Commanding; First Lieut. S. H. Gibson, U. S. M. C., and Second Lieut. H. K. Gilman, U. S. M. C.; Company B, Second Battalion, 50 men, and one 3-inch B. L. R.

Post 2.—Capt. F. H. Harrington, U. S. M. C.; First Lieut. Henry Whiting, U. S. M. C.; Company E, Second Battalion, 50 men.

Post 3.—Lieut. T. B. M. Mason, U. S. N., Commanding; Lieut. Wainwright Kellogg, U. S. N.; Ensign H. M. Witzel, U. S. N., and 31 blue-jackets and one gatling. Capt. W. S. Muse, U. S. M. C.; First Lieut. R. Wallach, U. S. M. C.; Second Lieut. F. E. Sutton, U. S. M. C.; Company C, Second Battalion, 50 men. Capt. S. C. Reid, U. S. M. C.; First Lieut. W. F. Spicer, U. S. M. C.; Second Lieut. S. L. Jackson, U. S. M. C.; Company D, Second Battalion, 50 men.

Post 4.—Lieut. O. Allibone, U. S. N., Commanding; Junior Lieut. C. J. Badger, U. S. N.; Gunner J. J. Walsh, U. S. N.; 50 blue-jackets, one gatling, one 3-inch B. L. R.

Armored car—Hotchkiss Rev. Cannon, one gatling, one S. B. howitzer.

Paymaster Stephen Rand, U. S. N., clerk and yeoman.

Past Assistant Surgeon Robert Whiting, U. S. N., and apothecary.

Officers	21
Marines	200
Blue-jackets	81
Yeomen	1
Apothecary	1
Total	304

GARRISONS OF MATACHIN DISTRICT.

Capt. R. W. Huntington, U. S. M. C., Commanding.

Matachin Post.

Second Lieut. Carroll Mercer, U. S. M. C., 39 marines; Junior Lieut. J. C. Colwell, 38 blue-jackets, one Gatling and one 3-inch B. L. R.

San Pablo Post.

First Lieut. Geo. F. Elliott, U. S. M. C., Commanding, 13 marines; Junior Lieut. Alexander Sharp, 12 blue-jackets, one 12-pounder S. B.

Officers	5
Marines	52
Blue-jackets	50
Total	107

PANAMA GARRISON.*

Major and Bvt. Lieut. Col. Charles Heywood, U. S. M. C., Commanding; First Lieut. H. G. Ellsworth, U. S. M. C., adjutant.

Company A.—Capt. E. P. Meeker, Second Lieut. T. S. Fillette, 51 men.

Company B.—Capt. L. E. Fagan, First Lieut. Jesup Nicholson, 51 men.

Company C.—Capt. H. C. Cochrane, First Lieut. F. L. Denny, 50 men.

Company D.—First Lieut. O. H. Berryman, Second Lieut. J. A. Turner, 49 men.

Company E.—Capt. R. L. Meade, Second Lieut. A. H. Clark, 37 men.

First Lieut. A. C. Kelton, U. S. M. C., brigade quartermaster.

Assistant Surgeon F. N. Ogden, U. S. N.

Shenandoah's marine guard, First Lieut. T. N. Wood, 20 men.

Shenandoah armored car, Hotchkiss Rev. Cannon, one Gatling, one 12-pounder howitzer; Lieut. E. M. Hughes, Ensign J. H. Oliver, 60 men.

Alliance, Naval Cadet C. P. Plunkett, 24 men.

Swatara, Junior Lieut. F. E. Sawyer, 24 men.

Officers	19
Marines	258
Blue-jackets	108
Total	385

H.

HDQRS. U. S. NAVAL FORCE ON THE ISTHMUS OF PANAMA.
April 22, 1885.

SIR: In the event of it becoming necessary to occupy Panama this command will advance in three columns: The column on the right to be composed of two companies of the second battalion of marines, the field-pieces, and two Gatling guns, under command of Captain Collum. This column will advance from the new passenger station along the Chemin de la Savane to its junction with the road leading to the French hospital. This junction is marked by a short broken column on a pedestal. One company, with a field-piece, will advance and occupy the road leading to the cemetery road, which it will occupy, and advance along the Carrera de Cocle to the junction of the Carrera de Bolivar and the Carrera de Camillo Torres; from thence by the Carrera de Camillo Torres and the Carrera de Caldas to their junction with the Carrera de Sucre. The remaining company of the column will advance by the Carrera del Isthme or the Carrera de Veraguas to the Plaza Santa Ana, which it will occupy and hold. Should the Plaza Santa Ana have been occupied by the center column, this part of the force, which should be under the command of Captain Collum, will relieve the force which occupies it.

The center column, consisting of two companies of the first battalion of marines, one field-piece, and one short Gatling gun, will advance by the Carrera de Colon to the Carrera de Chiriqui and occupy one end of the Plaza Santa Ana, moving into the plaza by the Carrera del Isthme, or by the street to the northeast leading into the Calle de la Cherrera.

The Plaza de Santa Ana will be occupied by one company and one piece of artillery, the remaining company and Gatling to advance either by the Carrera de Pais or the Carrera de Bolivar to the Plaza de la Cathedral and occupy the hotel of Mr. Shuber, marked "H" on the map.

As soon as the force from Captain Collum's battalion shall reach the Plaza Santa Ana the commanding officer of that portion of the center column holding the plaza will advance either along the line of the Carrera Constitution or the Carrera de Caldes to the telegraph station, which it will occupy. The left column, under your personal command, consisting of two companies of the first battalion, one field-piece, and one short Gatling gun, will advance by the beach if the tide permits, or by the street running parallel with the beach, to the angle just to the northward of the Carrera de la Chiriqui, marked with a * on the plan of the city, thence by the street leading into the Chiriqui, past the marked house to the Plaza Alfaro; thence by the Carrera de Cordova to the American consulate and the Pacific Mail office, which it will occupy. It is intended in these instructions to give the general directions of the advance and the places to be occupied.

The object of the naval force under my command is to protect American property and the lives of American citizens. This must be done at all hazards.

As soon as the landing party from the Shenandoah, which shall be signaled for before the advance is made from Camp Jouett, the officer commanding the reserve, which shall consist of the present naval force not detailed as part of the right, center, and left columns, will advance to the Plaza Santa Ana and wait for instructions. The landing parties from the Shenandoah (and Iroquois, if here) will hold Camp Jouett.

Should the city be fired, every effort compatible with the above instructions will be made to extinguish the fires.

Should resistance be made to the advance, direct the commanding officers to overcome it; shoot all who may be found firing or attempting to fire or blow up buildings. Capture and disarm all persons found with arms in their hands, unless it is positively certain that they belong to the National force. These instructions do not apply to the forces that may be landed from foreign ships of war in the harbor to protect foreign property. Avoid collision with them. Instruct the commanding officers of battalions in writing in accordance with these orders, and direct them to report to me at 1 o'clock to-day with a rough drawing of the plans of Panama.

Have the entire force under your command disposed for an advance into Panama as above directed at 5.45 p. m. to-day for my inspection. Have the men thoroughly instructed to-day in the principles of street firing. Have the canteens filled, and instruct the men always to put them on when the long-roll is sounded or when they fall in, in readiness to repel an attack. Report to me at 1 o'clock to-day in writing that the preparations and instructions contained herein have been carried out.

Lieutenant Cowles and Lieutenant Reeder are my aids, and all instructions given by them in my name will be implicitly obeyed.

Should an advance be made into Panama, I will be found with the center column, which will carry the colors of the First Battalion of Marines.

Very respectfully, your obedient servant,

B. H. McCALLA,

Commanding U. S. Naval Force on the Isthmus of Panama.

It is a sound military principle never to underrate the strength of an enemy.

B. H. McCALLA.

Major and Bvt. Lieut. Col. CHARLES HEYWOOD, *U. S. M. C.*,
Commanding Garrison at Panama.

Supplemental instructions for occupying Panama.

HDQRS. U. S. NAVAL FORCE ON ISTHMUS OF PANAMA,
Panama, April 26, 1885.

ORDER.

Should an advance be made into the city to-night the following changes will be made in my order of the 22d, viz:

Lieutenant Allibone's column, consisting of two companies of the Second Battalion of Marines, one Gatling and one field-piece, will advance by the Chemin de la Savane to the Plaza Santa Ana, which it will occupy and hold until the arrival of Captain Collum's command. Upon the arrival of Captain Collum Lieutenant Allibone will push forward with one company of marines and a Gatling to the Cathedral Plaza and occupy the Cathedral. Captain Meade's column will advance to the Plaza de la Cathedral and then by the Carrera de la Sucre to the telegraph office, leaving one company and a Gatling at Shuber's Hotel. Captain Collum's command will advance at once to the Plaza Santa Ana by the Chemin de la Savane, relieving Lieutenant Allibone.

Lieutenant Mason, with the remaining force, will assume command of Camp Jouett, making the best disposition of his force to protect the camp. Be pleased to caution the commissioned officers against shell-firing, which is liable to set fire to the town, and indiscriminate firing with the Gatling guns and rifles.

Upon the arrival of the landing parties from the ships in the bay the landing party from the Iroquois will be sent directly to the Plaza Santa Ana, unless otherwise directed. The force from the Shenandoah will re-enforce the garrison at the camp. Should the town be fired every effort must be made to suppress the flames, and the only feasible way is to tear down buildings in their path. Sentinels will be established about the parallelogram embraced generally by the bay on two sides, the Carrera de Camillo Torres, Carrera de Narino. Great care must be taken by the several colums not to fire into each other.

B. H. McCALLA,
Commanding U. S. Naval Force on Isthmus of Panama.

J.

Entre B. H. McCalla, commandante de las fuerzas navales de los Estados Unidos en el Istmo de Panama, y Rafael Aizpuru, presidente del Estado Souberano de Panama, se ha Celebrado el siguiente convenio.

ARTICULO I. El Senor Commandante B. H. McCalla, una vez firmado este convenio, hara retirar las fuerzas americanas que ocupan la cuidad de Panama a las Cuarteles ocupados hasta ayer en el vecindario de la linea y'estacion del ferrocarril interoceanico.

ART. II. El Senor Presidente Aizpuru se obliga a cumplis con el deber de dar completa proteccion a la vida e intereses de los Americanos y demas extranjeros que habitan la cuidad de Panama; no consentira combate alfuero en su reciuto, ni construira barricados en las calles.

ART. III. El Senor Commandante McCalla se compremete a no tomar parte en las luchas politicas.

Se firman dos ejemplares de un tenor en Panama, a 25 de Abril de 1885.

B. H. McCALLA,
Commander, United States Navy.
R. AIZPURU.

K.

HDQRS. U. S. NAVAL FORCE ON ISTHMUS OF PANAMA,
Panama, April 27, 1885.

SIR: Proceed to Paraiso and occupy the depot there temporarily. Do not interfere with the local government. Make inquiries quietly as to the cause and facts of the recent shooting at Paraiso, and notify me. Take no part in any controversy.

You are sent there merely to see that the transit is kept open. Let any foreigners remain within your lines who apply for protection.

Very respectfully, &c.,

B. H. McCALLA,
Commander, U. S. N., commanding.

Capt. GEO. C. REID, *U. S. M. C.*,
Commanding D Company, Second Battalion.

HDQRS. U. S. NAVAL FORCE ON ISTHMUS OF PANAMA,
Panama, April 28, 1885.

SIR: Proceed to Paraiso and relieve Captain Reid, U. S. M. C., now in command at that place.

Take a copy of his instructions and govern yourself accordingly.

Very respectfully,

B. H. McCALLA,
Commander U. S. N., Commanding.

Lieut. T. B. M. MASON, *U. S. N.*

M.

CAMP DAISY.

Special instructions issued to pickets and men at San Pablo, United States of Colombia.

(First Lieut. G. F. Elliot, U. S. M. C., commanding post.)

INSTRUCTIONS FOR PICKETS AT BRIDGE.

Force.—One corporal, one patrol, and two privates.

Duties of corporal.—Relief being turned out, see that each man gets a cup of coffee and a piece of hard bread before relief is formed, and that he has his poncho. Form relief. Load pieces in front of the guard-house. See that the guns are at half-cock and the magazines shipped.

POST NOS. 1 AND 4.

March Nos. 2 and 3 with patrol to the bridge, posting No. 2 with patrol at east end, and remaining himself with No. 3 at west end, until sentinel in front of guard-house calls the half hour, when he will exchange places with the patrol.

On being relieved corporal will march relief back to guard-house, face toward the railroad, and cause pieces to be unloaded.

Patrol.—Will keep sharp lookout with sentinel; will shift from one end of the bridge to the other every half-hour, giving notice to the corporal of the guard of anything unusual.

In case of attack the entire relief will rally to the east end of the bridge and defend it to the last extremity The garrison will hurry to their assistance. In case a rocket should be fired the relief will fall back from bridge, passing under cover of railroad embankment opposite battery so as to be covered from shell-fire.

The relief will obey the orders of the corporal of the guard implicitly.

Remember! cool, deliberate firing will cause any force to respect the individual soldier.

RESPECTING MEN UNDER SENTINEL'S CHARGE.

The men will be kept under sentinel's charge. All requests from men will come through the sentinel, who has no power to grant such requests himself, but will make them known to the officer of the guard.

The men will report to the sentinel on going to the rear, and if they remain longer than ten minutes the sentinel will report it to the officer of the guard.

Allow no one to hold any conversation with men placed under your charge, and speak to them only when necessary.

DAILY ROUTINE.

6.30 a. m. Reveille and early coffee. Men allowed to bathe until 6.50.
6.50 a. m. Sick call. Men will receive quinine furnished by medical officer.
7.00 a. m. Breakfast; half-hour for smoking.
7.30 a. m. Air bedding, weather permitting.
8.00 a. m. Police work.
11.00 a. m. Bedding brought in and rolled up. Inspection of quarters.
12.30 p. m. Dinner.
1.00 p. m. Beds rolled down and men kept in quarters till 5 o'clock.
5.00 p. m. Supper.
5.30 p. m. One-half of garrison march to bathe.
6.00 p. m. Remainder of garrison march to bathe.
9.00 p. m. Tattoo.
9.15 p. m. Taps.

SANITARY REGULATIONS.

1. Air bedding every morning, if fine.
2. Bathe in evening.
3. Keep out of the sun in heat of the day.
4. Quinine to be taken before breakfast.
5. Meals at regular hours.
6. No drinking of liquors of any kind.
7. Use for drinking only distilled water.
8. Keep bowels open.
9. Keep sentries in tents during day.
10. Inform officer of the guard if perspiration is stopped on warm days.
11. If feeling giddy, wild, with headache, &c., inform officer of the guard.
12. No drill during the heat of the day.
13. Keep out of night air as much as possible.
14. Close windows and doors at tattoo.
15. Wear flannel next to skin at night.
16. Change wet clothes as soon as relieved.
17. Never put on damp clothing. Allow undersuit worn one day to hang and dry the next, putting on a fresh suit.

O.

Force employed during the occupation of Panama, April 24, 1885.

AT 2 P. M.

	Officers and men.
Right column	145
Center column	150
Left column	151
Depot	70
Total	516

AT 10.30 P. M.

In city	482
At depot	154
Picket line outside city	188
Total	824

P.

GENERAL ORDER No. 19.

NORTH ATLANTIC STATION,
U. S. FLAGSHIP TENNESSEE (1st rate),
Aspinwall, U. S. C., May 7, 1885.

The Commander-in-Chief takes great pleasure in expressing to all the officers and men of his command his high appreciation of their services on the Isthmus of Panama. Their strict attention to duty, their high state of discipline and efficiency, their promptness in emergencies, and above all their forbearance in delicate and critical situations, have won the respect and admiration of all.

He will not fail to represent fully to the Navy Department how well all have done, and with what alacrity and devotion officers and men have hastened at every call of duty.

He extends his sincere congratulations to all his command, that the object of their mission has been accomplished peacefully, and with honor to themselves and to their country.

To those who are about to return to their homes he wishes a joyous meeting with their friends, and to each and all long life and happiness.

This order will be read at muster on board each vessel of the squadron, and to the battalions on shore.

JAS. E. JOUETT,
Rear-Admiral, Commanding U. S. Naval Force on the North Atlantic Station.

EXTRACTS FROM REPORT OF LIEUT. W. W. KIMBALL, U. S. N. U. S. S. TENNESSEE, MAY 25, 1885.

* * * * * * *

All the ships of the North Atlantic squadron, except the Yantic which was left at Livingston, Guatemala, to attend to American interests at that point, were now assembled (10th April) at Aspinwall, where also arrived on the morning of the 11th, by the steamer Para, 214 officers and men of the Marine Corps under Major Heywood.

At this time the Panama Railroad and Pacific Mail property was guarded in Aspinwall by the landing force of the Galena and in Panama by that of the Shenandoah.

Relief trains had been run over the road, taking refugees from and bringing food to Aspinwall, but the transit was precarious and the superintendent of the Panama Railroad declined to attempt regular traffic until protection was assured. On the evening of the 10th, a few hours after arrival, and as soon as the number of the available men could be reported, the commander-in-chief issued orders in detail for the landing of a force sufficient for opening and maintaining the transit across the Isthmus and for the protection of all American interests upon it.

The detail was as follows:

For garrison at Panama, 214 officers and men of the Marines; and 45 officers and men of the Navy, with one Gatling and one 3-inch B. L. R., under command of Major Heywood, U. S. M. C.

For garrison at Matachin: 55 officers and men of the Marines; and 35 officers and men of the Navy, with one Gatling and one 3-inch B. L. R., under command of Lieutenant Wainwright, U. S. Navy.

For garrison at Aspinwall: 25 officers and men of the Marines; and 160 officers and men of the Navy, with three 3-inch B. L. R. and one 12-pounder S. B. howitzer, under Lieutenant Colahan, U. S. Navy.

For train guards: 42 officers and men of the Marines; and 58 officers and men of the Navy, with two 37-millimeter Hotchkiss guns, two Gatlings, and two 12-pounder S. B. howitzers, under command of Lieutenant Kimball, U. S. Navy.

The commander-in-chief also directed the fitting up of two flat cars with steel bullet-proof breastworks, gun platforms, &c., to take the artillery of the train guard. (See Plates 5 and 6.)

These cars were intended for out-post duty in case of a regular opposition by the revolutionists, as well as for patrol of the line after the transit was opened, and consequently each was so fitted as to deliver the fire of three guns, one 37-millimeter, Hotchkiss, one Gatling, and one 12-pounder S. B. Howitzer on either beam, and that of the Hotchkiss and Gatling ahead or astern, while the Gatling or the 12-pounder S. B. howitzer could be disembarked for use in the field at any point. On the morning of the 11th April the signal to land the above force was made, and within six hours the troops were all on shore, those for Aspinwall established in the posts mentioned, and those for Matachin and Panama embarked on railroad trains with camp equipage, ten days' rations, and distilled water from the ships. In the same time the armed cars had been fitted and were ready to move. The commander-in-chief directed the force detailed for Matachin and Panama to move out at 3 p. m. in two trains, the first consisting of an armed car ahead, with crew at quarters, passenger coaches filled with the marines, a passenger coach with the passengers of the Para, and an armed car with crew at quarters in rear; the second, closely following, consisted of passenger, box, and flat cars taking the garrison for Matachin, the artillery for Panama, and the rations, water, and camp equipage of the whole moving force. At this time Panama was in the hands of the Revolutionists, and Aspinwall was held by the small party of Nationalists that had defeated Prestan, but the whole country through which ran the Panama Railroad was utterly destitute of any government or authority whatever, civil or military. In view of this, and of the well-known fact, that among the fifteen or twenty thousand people living along the line of the canal there were many dispersed Revolutionists and desperadoes from all parts of the world, the commander-in-chief decided to make the moving force so strong that not only could any offered opposition be easily overcome but that the lookers on would be impressed with the folly of any attempt in that direction.

No opposition or detention was experienced, and by sunset the garrisons were established in obedience to the orders of the morning, the men and officers all quartered under roofs, mostly those of the Panama Railroad Company, the transit was opened and insured, and all legitimate American interests on the Isthmus given adequate and satisfactory protection. On the 12th April regular schedule trains began to run over the road, the six daily passenger trains being furnished with a guard; the important ones being attended by an armed car. Since the formal opening of the transit there has been no attempt at interfering with it by any one along the line.

The force as detailed and disposed on the 11th being ample for all purposes, the blue jacket infantry of the Shenandoah's landing party was relieved and returned to their ship. A few days afterward a garrison was ordered to be established at San Pablo and a picket thrown out for the protection of the Barbacoas bridge. As soon as rations for the purpose could be landed they were issued to the distressed at Aspinwall, including the Nationalist soldiers at that point, business was resumed, rebuilding the burned town was begun, confidence was established, and affairs on the Isthmus were generally quiet.

For the prompt arrangement of the trains on the 11th, for the furnishing workmen and materials for fitting up the armed cars, for the transportation of rations and water, for the providing of quarters in the railroad stations and afterward in barracks built by him for the purpose, the United States forces were indebted to Mr. George A. Burt, superintendent of the Panama Railroad Company. Owing to the efforts of this gentleman, none of the troops had to suffer the discomforts and sanitary dangers inseparable from quartering under canvas in the climate of the Isthmus. He gave up his own house for headquarters at Aspinwall, messed the officers there established, and in general rendered all possible aid, assistance, and advice in the numberless difficulties and delicate details entailed upon the landing of so large a force in a foreign and friendly country where two different government authorities were asserted, and where, as regards the Isthmus, except at two points, none whatever was exercised.

Having received information that Prestan was about to leave Porto Bello in a schooner bound for Cartagena, the commander-in-chief on the 14th sent the Swatara with orders to cruise for him as far as the last named port and to furnish the Powhatan lying there with needed provisions. The Swatara boarded a small schooner off Porto Bello, but failing to find Prestan, she carried out her orders in regard to provisioning the Powhatan. At Cartagena she found the town in the possession of the Nationalists under Santo Domingo Vila, besieged by the Revolutionists, about 3,000 strong under General Gaitan. The Revolutionists had two small river steamers and two tugs, one of which was the Gamecock, fitted up with boiler-plate shields and a 12-pounder Armstrong gun. The Nationalists also had a couple of shielded river steamers. On the 20th the Swatara returned to Aspinwall, bringing a request from President Vila for transportation for himself and troops to Aspinwall, which request was of course, not granted.

* * * * * * *

A couple of days previous to the occupation of Panama the Alliance sailed from Aspinwall for Cartagena, under orders from the commander-in-chief to take Lieutenant Very on a confidential mission to General Santo Domingo Vila, President of the State of Panama. When off Sabanilia at sea a brigantine was sighted, under full sail, which, as she came up, first showed Haytian and then Colombian colors. A blank cartridge was fired, when she hauled down the Colombian colors and hoisted what was afterward found to be the flag of the revolution, a red cross on a white field, but did not heave to. A shot was then thrown across her bows, when she hove to and was boarded. She was found to be an American-built vessel, but with no American papers later than 30th June, 1884, although she had been in Boston, Mass., in the spring of 1885. It appeared that she had been sold to one Pedro Sara, styling himself civil and military chief of Barranquilla, a province of the State of Bolivar, and by him commissioned as a man-of-war and armed with a 32 pounder carronade. Knowing that no governor of a State and much less a governor of a province, had authority to commission a vessel of war to cruise on the high seas, Commander Clark seized her as a pirate, under paragraph 18, page 137, of the United States Navy Regulations, and by authority of various precedents and rulings quoted by Wharton, Vattel, Woolsey, and others. As she had on board 17 officers and 37 men of the Revolutionary army, Commander Clark took them, with their arms and ammunition, on board the Alliance for safe-keeping, put a prize-crew on board the brig under command of Lieutenant Wright, and sent her in to Aspinwall, where she arrived on the 26th April.

At 12.30 a. m. of this date the superintendent of the Panama Railroad came on board the flag-ship and reported that the telegraph wires were cut, and that communication was cut off beyond Gatun. As a Revolutionist force might have arrived at that point, the commander-in-chief ordered a force of 100 blue-jackets, in a train with an armed car, under Lieutenant Wainwright, to move out at daylight and see the wires in order through to Panama. Accordingly the train left at daylight, but upon arriving at Bohio Soldado it was found that the line had been grounded accidentally, and that all was quiet along the railroad, and consequently the force moved back to Aspinwall.

* * * * * * *

A greater or less United States force was continuously on shore in Colombian territory from the 30th March to the 25th May.

QUARTERS.

The force landed on the 11th was quartered at the posts mentioned in Aspinwall in buildings belonging to the Panama Railroad and to the Pacific Mail Company, the men sleeping on the floors. The quarters were as a rule sufficiently comfortable except those at the Pacific Mail wharf, which consisted of a small cooper shop badly located and badly ventilated. This was improved as much as possible by the carpenter's gang of the Tennessee, who rigged sleeping benches and racks for arms and accoutrements. The quarters at this post were afterward moved to a small building on the other side of the wharf. The company did not wish any portion of the freight-shed used for quarters, as the rush of freight was so great. At the other posts the men slept upon verandas and in some unused buildings. * * * Four small barrack-buildings, quartering about 50 men each, were planned by Lieutenant Colahan and built by Mr. Burt, superintendent of the Panama Railroad.

These were light scantling, iron-roofed buildings, fitted with sleeping-benches, and as the men brought with them their hammocks and the straw mattresses from the steamer, they were quite comfortable for the people quartered in them. At Matachin (see plate No. 8) the people slept upon the platform of the railroad station, which had a shed roof over it. A couple of staysails were used to keep the rain from driving under the ends. At Panama two large freight stations were provided for quarters. In one the open spaces in the floor for two railroad tracks were floored over, thus giving space for four lines of men to sleep, and still leave room to form companies between the lines. No tents were used as quarters.

RATIONS AND COOKING.

The Navy regulation rations were served out to the force on shore, except to the detachment which arrived in the Acapulco, which came provided with extra ones. The cooking was done at camp fires and on boat stoves near the quarters, and, as a rule, was fairly good. In the extra rations brought by Commander McCalla's command, the tinned corned beef and the sausage proved particularly serviceable ashore, especially for the train guards and for men who could not be in camp at meal times.

Shelters or awnings were rigged over the kitchens, and the boat stoves were in some cases supplemented by stoves taken from burned houses.

WATER.

Distilled water from the ships was provided for drinking by means of breakers sent filled to the posts and returned empty. It was difficult to always supply the proper amount on account of the breakers going adrift on the railway trains, and when the supply was short the water from Frijoles, which, upon analysis, proved good, was made use of.

CLOTHING.

The fatigue dress of the marines proved serviceable, as did the clothing of the blue-jackets; these last used working clothes at times during the day, which proved comfortable but were of course considered bad in color for actual fighting. The helmets of the marines proved too heavy and gave too little protection from the sun, while the absurdity of most of the blue-jackets' head-gear was more than usually apparent. The blue-jackets sent out from New York were provided with straw hats which proved serviceable.

* * * * * * *

EQUIPMENTS.

The canteens and haversacks were all that could be expected, and the blanket-packs proved very convenient. The McKeever cartridge-boxes of the marines held the cartridges well, but as no man had more than two the supply of ammunition was less than one-half what it should have been. These boxes take but twenty rounds each. The blue-jackets from the ships were provided with old regulation and

Hitchcock boxes, neither of which hold the cartridges securely, nor do they, when filled, furnish more than half a proper supply of ammunition. The new double Mills belts, with pockets for magazines, seem extremely well suited for use. The cartridges are securely held, the supply is sufficient, and the weight is well carried by the shoulder-straps. Some complaint was made that the cartridges stuck in the loops when the belts were wet, but this trouble seemed to occur because the men did not to push the cartridge up by the bullet instead of trying to pull it out by the head.

SMALL-ARMS.

As but few shots were fired, and those mostly by sentries on post, the faults and good points of the small-arms were not made prominent. The Springfields, in the hands of the marines, showed a great weakness in the breaking of many firing-pins under the sledge-hammer blows of the awkward dock, but the absurdity of the breech mechanism and the poor system of rifling were not accentuated because the arms were so little used.

The old model Hotchkiss, with which some of the blue-jackets were armed, freely exhibited its well-known deficiencies—the weakness of the butt-stock and the inefficiency of the bolt-lock. The Remington-Keene, from the Tennessee, showed clogging of the bolt-lock, failure of carrier action, leakage of the cut-off, and general inefficiency.

The Lees, in the hands of the blue-jackets of the force sent out from New York, proved strong and serviceable. The lack of thumb-hold on the cocking piece was felt, and the sights were poor. The lack of slings on the Hotchkiss and Remington-Keene's was quite a serious one, and the fact that all the blue-jackets were provided with a low-power cadet-sized arm was regretted.

SIDE-ARMS.

Like the small-arms these were not used enough to prove anything new. The cutlasses were considered good, the revolvers fair, and the pistols bad.

ARTILLERY AND MACHINE GUNS.

Of course nothing new was learned as to the firing or effect of these arms. The 3-inch B. L. rifle howitzers seemed in every way efficient, as in their way did the 12-pounder S. B. howitzers, which last might, it was thought, prove particularly serviceable on the Isthmus, where there was no artillery to oppose them, and where short-range canister fire might be needed. There was not marching enough over rough country to accentuate the faults of the trail-wheel carriages. The Gatlings, both long and short, seemed to be all that could be expected of them in handiness, &c., but the lack of method to supply ammunition for these arms was apparent. Two Hotchkiss 37-millimeter revolving cannons were landed for mounting in the armed cars; the lack of a boat-mount made it necessary to fit standards aboard ship. As it was considered better to keep all the four sockets of the regular ship standards in place, sockets had to be improvised from boiler plate and boiler tubing. A cone boat mount for these weapons would be very convenient on shore, for they make excellent guns of position.

ARMED CARS.

These were two flat cars fitted up as follows:

Stanchions standing 44 inches above the floor of the car were firmly wedged in the sockets, and inside them was placed one-half inch steel boiler plates 42 inches wide. The bottom edges of the plates were held in place by cleats running the length of the cars, and the top edges by iron clips depending from bolts passed through the heads of the stanchions in the 2 inches of head that projected above the plate. The clips were held hard against the plates by nuts upon the bolts. The ends of the car were too wide for the steel plate at hand, and so two thicknesses of one-fourth inch iron were used there.

Amidships of the cars on both sides were spaces without shields, wide enough to admit a Gatling or 12-pounder S. B. howitzer field carriage by "cutting" the wheels back and forth. These spaces were left as embrasures for the 12-pounder S. B. guns, and for openings through which to disembark either of the field pieces of the armament. A plate was provided and fitted with clips for use as a port shutter on the disengaged side, and eye-bolts were fitted for making fast the breeching to keep the guns from recoiling too violently against the shutter or from going overboard if the rear embrasure were left open. At each end of the car were platforms 10 inches high, 5 feet in fore-and-aft dimensions, and the width of the car inside the shield, one of which was occupied by the short Gatling on field carriage, and the other served as a base into which to frame and brace the Hotchkiss cannon standard. These platforms were built in order to lift the Gatling and Hotchkiss high enough to fire en barbette. Thus all three guns could be brought to bear abeam, while the Hotchkiss and the Gatling gave fire ahead and astern. To the stanchions were spiked uprights carrying a roof covered with water-proof felt. A wire was stretched around under the eaves and awning curtains, bent so that rain and smoke could be kept out. By paying a little attention to stowage a car so fitted was found to be commodious enough to comfortably take its armament with full supply of ammunition, the crew of thirty men all told, with arms and equipments, two days' rations and water, and still leave room enough to work the guns and deliver a small amount of rifle fire.

BEHAVIOR OF THE MEN.

The marines sustained their well-known reputation for steadiness and effectiveness, doing their duty very satisfactorily and showing but few infractions of discipline.

The blue jackets fell into their shore duties well, and, as a rule, were reliable as sentries.

HEALTH OF THE FORCE.

As the rainy season did not set in till the 20th May, the health of the men was generally good.

The officers and men of the squadron and 1st battalion suffered considerably from climatic diseases, and at this date, 25th May, the number on the "sick-lists" is rapidly increasing.

Six deaths have occurred within a month; two from gunshot wounds (one man shot in trying to run the lines, and the other in a brawl), one from typhoid, and three from yellow fever.

EXTRACTS OF MEMORANDA UPON THE EXPEDITION TO THE ISTHMUS, ADDRESSED TO THE HON. THE SECRETARY OF THE NAVY.

By Lieut. T. B. M. Mason, *U. S. Navy.*

ORGANIZATION.

In order to carry out comfortably, as well as efficiently, the objects of such an expedition, a thorough system of organization, which shall define the duties and responsibilities of each individual, is required. Army customs are based upon long experience in the field and we cannot d better than to study them thoroughly, and enforce them strictly on such expeditions.

* * * * * * *

I am convinced that the company is the best unit of organization. When called upon to execute marches, parades, &c., the companies may be united as battalions, but unless the number of companies is very large one battalion would be much preferable. This is also true of the artillery organization; a section should be the unit, batteries only existing temporarily.

* * * * * * *

Next to the commanding officer the commissary is the most important, and should be most carefully selected.

A quartermaster (a line or marine officer) should have charge of assigning and looking after the quarters of the force.

The organization of the medical staff, with a sufficient and *healthy* set of assistants of all grades, would have lightened the duties and anxieties of the medical officers detailed for the expedition, to whom too much praise cannot be given for their untiring attention and care. The instruction given by Dr. Whiting to the officers and men on the passage to Aspinwall undoubtedly saved several lives.

The fact is probably deeply underlined in the memory of every officer who had the actual care of his men on his mind that a large permanent detail for service in the auxiliary corps is an absolute necessity. The fighting force may be thereby reduced in numbers, but not in strength or effectiveness. Per contra, the permanent details should not be used as a fighting force, except in an emergency to defend the base.

A regularly educated and properly qualified set of permanent petty officers is required in the service. The mere filling of rates because vacancies exist; the sudden and sometimes ill-advised disrating of petty officers; the rating of men as petty officers because they are good sailors on board ship; the equal treatment of a petty officer and the worst man on board under the present methods of the service; the over-marking of men on their transfer papers from a mistaken idea of generosity in order to insure continuous service papers, prevent the selection of good men to fill ratings, especially in an emergency such as the hurried fitting out of this expedition. The consequence is that officers have to perform much duty which in the Marine Corps and Army falls to the noncommissioned officers. This is bad for officers and petty officers. It gives the first too much work of a petty nature, taking time which should be devoted to more important duties; it takes from the latter the chance of establishing their superiority over the men they command. The quartering and messing of the petty officers in the cabin of the Acapulco on the passage down had an excellent effect in most cases, and would have had much more were it not that it was found that some of the men selected turned out to be the most incorrigible drunkards in the whole command, a fact that could only be developed by experience, as their papers were as good as those of the men who filled ratings to everybody's satisfaction during the whole expedition.

What has been said in regard to petty officers refers equally to the other rates which do not carry petty officers' rank. It would naturally be supposed that where there are several grades of seamen (or more properly speaking men-of-war's men) that only those who were thoroughly competent to perform all of the duties of a well-instructed man on board a man-of-war would be found in the first grade; that an imperfect knowledge of mere sailoring should entitle a man to draw more pay than an ordinary seaman who is perfectly instructed in every branch of naval requirements, and probably knows more about the naval methods than his superior, green from the merchant service, seems to show a screw loose somewhere and demand a change.

The machinists, firemen, and coal-heavers taken out from New York proved as effective, and in many cases more effective, members of the expeditionary force than the men from the seamen class.

EQUIPMENT.

ARTILLERY.

There is too much artillery for the number of infantry in our naval landings. Artillery to be effective requires a large number of men, many more than are generally allowed. Twenty-four men is the least number that can render a 3-inch B. L. R. effective in active service; twenty, the least number to man a Gatling, if properly supplied with ammunition. The service allowance of ammunition carried with guns is small, and would be exhausted in a short time in action. More ammunition and fewer guns should be provided. It is true that most of a gun's crew are armed as riflemen, but in order to make the gun useful and to secure it against capture these men must operate close to it. A man in a gun's crew cannot carry his personal arms and equipments in addition to ammunition for the gun. All of the gun ammunition must be carried on wheels. A limber is very necessary for all guns intended for use in the field; it is the only way to carry the necessary supply of ammunition. The wheels of the B. L. R. limber should be exactly like those of the gun. The Gatling limber should always be used with its gun, and as it is similar to the carriage it may be used to replace it in case of a breakdown. I would call attention to what I consider deficiencies and to make certain suggestions for their amelioration. The ammunition boxes on the carriage of the B. L. R. frequently jam. There is no provision made in the box for carrying cartridges, five projectiles have to be left out of each box to accommodate them. The limber should carry three boxes exactly similar to those of the carriage, so that they could be interchanged. There should also be a box of small-arm and revolver ammunition. The spare article box should be entirely done away with and the articles now carried in it, together with those carried in the quarter-gunner's haversack, should be stowed in a locker contrived between the cheeks of the trail of the piece. A fuse for each projectile should be carried in the ammunition boxes. A double supply of primers should be packed and carried in the same way. This would insure all the requisites for efficient service being found together. The tires of the wheels should be broader or sand tires should be supplied. The drag rope should be double, without toggles, and should reel up under the tongue of the limber. A few armorer's tools should be added to the spare articles, and many of the spare articles now carried with the piece should be placed in a reserve box to be kept at the base. Two axes and two spades should always be attached to the piece and limber.

Cannister should be supplied for the B. L. R., and a proportion of multi-ball cartridges for the Gatlings.

The number of passing boxes should be reduced to four, and these should be attached to the piece when not in use. The length ot the sponge handle should only exceed that of the bore by 12 inches. The rammer-head should be entirely removed. A better system of carriage brake is very much needed. It is very well to say that they should be properly tended and if properly tended will work well, but a long experience, at times with the most intelligent crew we can ever expect to have, proves that they freqnently jam. The ranges, times of flight, &c., should be engraved upon a piece of brass permanently attached to the gun, and the officers of the guns and petty officers should be provided with similar tables printed on rubber cloth. Had it not been that one officer happened to burden himself with our Ordnance Instructions we should have been entirely deprived of this necessary factor of accurate fire. It is true the sight is well marked, but more is needed. A dummy primer should accompany each piece for drill purposes. An India rubber blanket of sufficient size to cover the entire carriage, and another for the limber should be secured to each vehicle.

All carriages and boxes should be painted the regulation brown, and no deviation should be allowed in this respect on board of sea-going ships. Scraped and white carriages are unserviceable, and other fancy painting mars the uniformity of pieces when brought together. The guns themselves should be kept as issued.

The present light artillery tactics should be altered so as to complete the drill for guns with limbers if they are adopted, and to correct the faults in equipment already mentioned. A pot of axle-grease and a small can of oil should be added to each gun's equipment.

A great improvement in the 3-inch B. L. R. would be the adoption of a metallic cartridge. A telemeter or some better means of measuring ranges should be provided for officers commanding artillery, and all artillery officers should be required to carry a good field-glass.

SMALL-ARMS.

Rifles.—The rifle supplied was the Lee magazine rifle. As a general thing the arm stood the wear and tear of service in the hands of men who had never seen it before exceedingly well. One or two springs gave out, but were easily replaced. There were some defects which could be remedied in future issues. The sights are too sharp, cutting the men's hands in use. They should be covered with sight-aprons. A baize bag should be provided for the piece when stored aboard ship or transported in boats. This bag would protect the piece very much on such service as this expedition. Good serviceable sling straps should be provided with each piece and the upper end secured further down the barrel; the lower end should be secured on the butt; when slacked off this strap would not interfere with the magazine, and would render the carrying of the piece, when slung, much easier. Should it be proved that the sling thus placed interferes too much with the magazine it might be placed on the side of the piece instead of under it. The magazines are too flimsy, several gave out in the brazing and the springs of some became upset and useless. The lower part of the magazine should be corrugated to give a grip for the hand. There should be a double action for the magazine; pushing it in half way should attach it to the piece; a second push or a longer one in the first place should unlock it and open the feed. There should be a thumb-piece on the firing-pin instead of a button, which is liable to slip through the fingers and fire the cartridge prematurely. The method of half-cocking the piece given in the pamphlet directions was found to be too dangerous for use.

The following was substituted: The piece was dropped muzzle down and held under the right arm. The left hand was carried across the body; the left hand seizing the button between the thumb and fore-finger, palm of the hand to the front. A slight pressure was exerted with the left hand towards the body at the same time the fore-finger of the right hand was carried to the trigger and pressed against it, the firing-pin being eased into the safety-notch with the left hand. The men discovered a quicker, but perhaps more damaging way of half-cocking; they raised the bolt, slightly pressed the trigger; the pin stopped in the safety-notch and the bolt was then turned down. The pamphlet requires the muzzle to be raised to a vertical position in "in" and "out magazines;" this causes the right hand to be in a very awkward position for pressing on the catch-trigger. It was found more convenient to keep the piece in the ordinary position of load.

A manual of arms suggested by Commander McCalla, which embodies the level trail authorized in the Light Artillery Manual, was used for the riflemen, and met with complete success; it was considered by every one as far superior to the manual of arms now authorized. Similar manuals are used by all of the great military nations of Europe. The "order arms" was the basis instead of, as at present, the "carry." All positions now set down in the manual were reached directly from an "order." Dressing and facing were performed at an "order," the man simply raising the butt of the piece from the ground. At the order "forward march," the man took up the position of "trail arms." This "trail" differed from the "trail" now authorized in that the barrel was horizontal and the piece balanced in the right hand. For the "support" now authorized the old heavy infantry "shoulder arms" was substituted, that position of the left arm being easier with the bolt gun. A "slope" was adapted from the "support," the barrel being simply inclined to the rear, the left hand and butt advanced. The "secure" was the position in which sportsmen usually carry their pieces under the right arm, barrel up, right forearm and hand carried across the stomach. It was found that the men picked up this manual much quicker than the old one, and liked it much better in every way. One of the magazines carried in the belt should be filled with multi-ball cartridges. Every piece should be distinctly marked with its number in large figures on the butt. The figures to be sunken, if possible, and filled in with some bright-colored paint. The bayonet as at present issued is excellent, and should not be done away with or altered.

Revolvers.—The present revolver is not adapted for the necessities of our service. It is too long, the ejecting apparatus is very poor and slow, the thumb-piece on the end of the ejector is a great inconvenience, catching in the holster and clothing. The butt is badly shaped. For the officers, at least, a self-cocker is required. A revolver, if used at all, is going to be used quickly and at close quarters. A .45 caliber revolver similar to the new Smith & Wesson Russian model, .44 caliber, would seem to be the best. All revolvers should be nickel-plated. The ammunition should be multi-ball.

Swords and cutlasses.—Swords and cutlasses appeared to be of no use except as a badge of office. A much less cumbersome badge would be a handsome revolver and cross-belt, with a holster for a field-glass attached. For *service* and *service dress* the sword should be *abolished*.

EQUIPMENTS.

Cartridge belts.—The general idea of the present new cartridge belt is correct. The hooks should all be done away with. The buckles on the shoulder supports should be of better make. The belt should be made to overlap and secure with straps at the left side. This would bring more cartridges in front, where they are most needed, and would insure a better fit. The belt was much liked by the men, although all were prejudiced against it at first. No complaints were heard when 80 rounds of ammunition were carried for several days. Men constantly slept with their belts on, and lay on their backs without difficulty. The shoulder supports should be a little stiffer, as they become creased and do not look neat. The bayonet-frog, and scabbard should be hung on a light strap to be worn around the waist under the cartridge belt. The frog never comes in proper position as worn now. The light belt would permit the carrying of the bayonet for drill and fancy duty. There should be several sizes of belts; one very much larger than any made now. Three belts out of eighty-eight had to be transformed by ripping off the eyelet straps and riveting their bitter ends to the end of the belt webbing. In these cases no cartridges appeared in the front. Each belt should be distinctly marked on the inside with its maximum and minimum length. On the outside, in large figures of bright color, its number. This would prevent much confusion and fix the responsibility of possession. This remark refers to every article of the outfit. On the expedition it was found necessary to scribble the owner's initials on the outside of everything. Not a neat method, to say the least of it.

Haversacks.—Good, but economy must have dictated the omission of the mess-gear intended to fit in this article. The marines who had the same haversacks properly supplied were comfortable; our men were constantly in trouble about their mess-gear, if they were fortunate enough to have any. A cup of proper shape and provided for in the storage would have been an addition even to the marine's outfit. There should be no tie-ties and make-shifts in a complete equipment; every thing should have its place provided for it and should be of exactly the size to fit. A small tin for pepper, salt, sugar, coffee, and pickles would have added to the comfort of our men. The strap is too heavy.

Canteens.—The canteen is good; the strap unnecessarily heavy. Some canteens were found to be leaky. An air test would discover this defect when they are inspected for acceptance. Like the cartridge belt and haversack the canteen should be distinctly marked with a number. These numbers should be the same for all of the articles of one man's equipment and should be on the outside at the most visible point.

Blanket bags.—Neither useful nor ornamental. A bag with one compartment and a good flap, wider and not so deep, would have been much better, and should be provided for future work. This is important, as they would be of much use. The marines were far more mobile and more comfortable than our men.

Color of equipments.—The mouse-colored equipments now used become quickly soiled; the light red ones of the marines equally so. All canvas work should be tan-color. This tanning preserves the canvas, always looks clean, a fact that was easily observable, as some of the men and officers had tan-colored canvas shoes; is cheap, can be reproduced by dipping in a division tub of tan mixture. The leather should be of the same shade.

Clothing.—Blue flannel and cloth carried off the palm for comfort and wear. The men complained of the heat whenever put in white, and were glad to get in blue again. Flannel is the healthiest for the climate of Central America and the Isthmus.

Blankets.—For the work we were called upon to perform a gray blanket would have had a more cleanly appearance than the white ones carried.

Blankets, rubber.—A rubber blanket should be kept and issued with every set of equipments. They are invaluable night and day, forming a rain-coat, bed, tent, and bed cover.

Head gear.—The straw hats bought in New York were invaluable. It is thought that the new canvas hat adopted for the Navy will be equal to them, and will have the advantage of cleanliness and shapeliness. Straw hats soon get very dirty and if wetted once lose their shape. For extended shore service the hat (regulation) should be dipped in the tanning tub.

Corps badges.—In order to distinguish the men and officers of the batteries corps badges were adopted and found very useful. The men were able to find their own officers although they did not know them personally, and every one could tell just where the men belonged. The badge was of red flannel or serge about an inch and a half in size. They were worn on the front of the helmets, straw hats, and blue caps. A ◇ (diamond) for the rifle battery and a △ (triangle) for the Gatlings. The guidon flags of the batteries were similarly marked, and if time had allowed and the conveniences been at hand every article of equipment and armament would have been similarly marked.

Leggings.—As provided, bad. Leggings should be made of tan-colored



canvas. The white duck ones provided were too flimsy and too visible at night, and were easily soiled. They should be cut by an expert, and made to fit well over the shoe, one size for each size of shoe issued. This would assure a neat fit over the foot and ankle. The calves of men's legs differ, of course, in size for the same sized foot. This should be provided for by making the pieces overlap very much at the top. The ankle part of the opening to be secured by loops, the calf part by a lacing with hooks. The leggings, as provided, were too long. If they are properly made and thick enough to be serviceable, they will keep themselves in position.

Officers' clothing and equipments.—A dark blue flannel shirt, similar to that ordered for petty officers, first class, in the new regulations, should be made part of the uniform of officers when in service dress for expeditionary service. The helmet and leggings should be tan-color. The leggings to be the same as those heretofore suggested for the men. It is probable that the new hat adopted for enlisted men will prove a substitute for the present helmet. The strictly regulation helmet is waterproof, and can be wetted and scrubbed without injury. Those of inferior make are injured by wetting, and soon become misshapen and very dirty.

As previously stated, the sword and belt should be entirely withdrawn in service dress. In lieu thereof, the best revolver obtainable, all to be uniform in make and calibre with those of the men, and a canvas cross-belt, fitted in front with thimbles for cartridges, at the side with a holster for the pistol, and behind with a case to contain map, writing materials, telemeter, compass, &c. A fine field-glass should be slung across the other shoulder. On service the haversack, canteen, and blanket bag should be worn by officers, and unless bags and hammocks are carried no extra baggage should be allowed. When officers can provide their own transportation, they will find a tin wash-basin and a canvas stretcher cot, such as are made for hunting and sold for $2.50 by sporting dealers and outfitters, to be of great additional comfort.



Front.



Side.



Rear.

Intelligence map.—Each officer should be provided with a good intelligence map of the country in which he is to operate. These maps should be prepared by the Office of Naval Intelligence, and printed on rubber cloth. On the cloth side should be printed such intelligence, notes, and data as may be thought of possible use.

Note-book for field service.—A small note-book for rolls, arm and equipment list, with proper printed headings and columns ruled; a few leaves arranged to be detachable with stubs, ready to be filled in for requisitions, receipts, and invoices; a few leaves for accounts, a space for a short journal, and for abstracts of orders received and issued. The book to be stoutly bound in a water-proof cover, and provided with a good pencil with India rubber end. It is useless to order these things to be provided by officers. The Government should manufacture or purchase all these articles of outfit, and issue them to officers, or they will never have them when needed. The components of the Navy ration should be given in this book, also methods of treating ordinary diseases and accidents.

Provisions.—The new Navy ration worked admirably. Had the directions in regard to half barrels and exact number of rations in packages been carried out, it would have been more convenient. Sausages similar to those issued to the German army, each containing, say, five days rations, and marked on the side of the cover with a scale to show rations and one-third rations, would have been very convenient, and would also be a valuable addition to a ship's stores for any detached service, whether afloat or ashore.

Provisions.—The present methods of issuing provisions to the men will never do on active service, and must be modified. Men were often in want of articles of which there was an abundant supply in the hands of the paymaster, and when they were issued they came in quantities and shape perfectly unmanageable. A barrel of pork once opened is an ugly customer to transport, and as for a barrel of flour, sugar, or beans it is a simple impossibility. These articles should be put up in very much smaller packages.

On service the field force should never be called upon to handle stores before they are issued to them individually. It is mere laborers' work, and can be much better performed by that class of people, especially in a bad climate where they have the advantage of being acclimated.

Cooking facilities.—The boat stoves were excellent, and with the addition of a temporary fire for a camp kettle, were found fully capable of preparing food for fifty men each. In each boat stove box a couple of hatchets should be packed.

A nest of kettles should be provided instead of several kettles of the same size. By this method enough kettles for use as water buckets, &c., could be carried in the space required for one mess kettle.

Stoves and kettles should be distinctly marked with the corps badge or name of the detachment to which they are issued.

Camp gear.—Tents and sentry shelters in moderate numbers should be supplied to all expeditions. It would seem that much room in stowing could be saved by using iron piping for poles instead of wooden ones, and iron pins for tent pegs. Tanned canvas would look cleaner after short service than white, and would be less apt to mildew.

Axes, hatchets, brooms, rakes, hoes, buck-saws and bucks, lanterns, and buckets should be provided in fair quantities.

A condensing apparatus should be kept ready for similar expeditions.

A supply of spades, picks, and shovels should accompany every expedition, to be issued as required. The bugles should be the same as those issued to the marines. They are now inferior in make and of a different key.

Weights carried by men.

RIFLEMAN.

	Pounds.
Waist belt with bayonet and 80 cartridges	11.50
Haversack, two day's rations complete	4.50
Canteen filled with water	4.00
Blanket and rubber blanket with underclothes	9.50
Rifle	9.00
Pot, pan, and spoon	75
	39.25

CANNONEER.

Waist belt, revolver, cartridge-box, and 20 rounds of ammunition	4.50
Haversack, two days' rations complete	4.50
Canteen filled with water	4.00
Blanket, rubber blanket, and underclothes	9.50
Pot, pan, and spoon	75
	23.25

MARINE.

Rifle and accoutrements, haversack complete, canteen full, clothing-bag packed, and 80 rounds of ammunition	53.00

SUGGESTIONS.

Concentrate the personnel and everything referring to their organization, drill, equipment, conduct, &c., under one head.

Concentrate the enlisted men waiting for ships at one *barracks*, and drill them thoroughly as infantry and artillery. They will all know enough seamanship to start with when they go aboard ship, and their great gun and other drills can be given them in the service.

Have always ready, say at New York, a complete expeditionary equipment for 1,000 men, issuing part of it every summer to the North Atlantic squadron for an encampment on some part of the coast.

Refer the whole matter of the selection of this equipment, and the preparation of a proper manual for all arms, to a board of officers.

LANDING

OF THE

NAVAL BRIGADE OF NORTH ATLANTIC SQUADRON

FOR

INSTRUCTION

ON

GARDINER'S ISLAND,

AUGUST, 1884.

REPORT ON ENCAMPMENT OF NAVAL BRIGADE OF NORTH ATLANTIC SQUADRON, AT CAMP MILLER, GARDINER'S ISLAND, AUGUST 11-14, 1884.

The North Atlantic Squadron, under the command of Rear-Admiral S. B. Luce, left Portsmouth, N. H., on the 6th August.

It was generally understood that the vessels were en route to Newport, but on the afternoon of the 8th instant, Captain Miller, commanding the Tennessee and Chief-of-staff, received an order to proceed to Gardiner's Bay, where the ships were to be moored, and to land the naval brigade for an encampment of three days.

The vessels were accordingly moored about 9 o'clock on Saturday morning, the 9th. Officers were sent to select a site for the camp and to obtain the necessary permission to land from the proprietor of the island, Mr. Gardiner. At the same time the following memorandum of instructions was sent to each vessel. Capt. J. N. Miller was appointed to command the brigade and was charged with the arrangements for landing.

MEMORANDUM.

1. The landing will be as if unopposed, and provision will be made for an absence of three days.
2. The force to be landed from each vessel will be that indicated by Squadron General Order No. 9.
3. The tents, provisions, and other heavy articles will be landed with the marines from the Tennessee as a guard before the main body lands. After the brigade is landed the boats will be towed back to the ships by the steam launches, leaving one whaleboat from each vessel at the beach.
4. Unless otherwise directed, the brigade will be ready to embark from their ships at 7.30 a. m., on Monday, August 11.
5. Each vessel will provide shelter for her own landing force (keeping the infantry companies separate from the artillery sections), utilizing sails, awnings, and spars, for the construction of tents. Stakes for side stops and guys for tents will be provided before landing.

COMMISSARIAT.

Each vessel will be prepared at the time designated to land cooked pork packed in barrels, bean soup in kettles, and bread in bags, sufficient for its men for one meal. The commissary will provide all other supplies for the command.

AMBULANCE CORPS.

The ambulance corps will consist of one surgeon and one assistant surgeon, as detailed.

The apothecaries and stretchermen required by General Order No. 9 will be detailed by the commanding officer. The fleet surgeon will superintend the medical outfit.

OFFICERS' OUTFIT.

Officers will wear service dress with caps, leggings, and side-arms. One change of clothing and blankets, rolled in a hammock as prescribed, will be carried.

Transportation for 10 pounds of baggage will be provided for each officer.

MEN'S OUTFIT.

The men will wear blue with underclothing, leggings, and knives. They will carry, rolled in a hammock blankets, one change of clothing, and a supply of tobacco.

They will carry their pots, pans, and spoons slung to their waist-belts on the left side.

MARINES.

The marines will wear fatigue uniform and caps, will carry overcoats and blankets, and in their knapsacks, undress coats, trousers, and change of underclothes.

HAMMOCK ROLLS.

The hammocks, without clews, containing change of clothing, blankets, &c., are to be rolled along their lengths, tied with five stops, and the ends tied together; to be worn over the left shoulder, with the ends resting on the right hip.

COOKING AND MESS ARRANGEMENTS.

It is intended that the brigade shall depend upon its own resources for subsistence and cooking appliances. The stores will be landed in advance of the brigade, together with the heavy articles.

[Here followed a tabulated form distributing the stoves, cooks, mess cooks, &c., together with directions as to the articles to be carried and furnished by the cooks.]

Cooks and mess cooks will land with their scouse-kettles, mess-kettles, and other articles at the same time that the provisions are sent on shore.

The quartermaster will be in charge of the transportation service, which will consist of all the cooks and mess cooks, servants, and such men as may be detailed.

There will be but two messes for all officers.

AMMUNITION.

All the marines and infantry men will carry their cartridge boxes filled. The packages of ammunition are not to be broken or opened unless ordered.

The ammunition boxes of each B. L. R. are to be filled with 20 charges of powder, 10 rounds of shell, and 10 of shrapnel; projectiles to be filled and plugged; spare article boxes to contain the fuses for the above, and all spare articles.

The caisson boxes of the Gatling guns will be filled with ammunition.

The Vandalia and Yantic will land their Gatling gun-carriages, without the guns or caisson boxes, to be coupled and used as a transportation wagon.

Lieutenant Belknap, of the Vandalia, will have charge of the landing of stores and provisions on the beach, and will turn them over to the quartermaster.

The organization of the brigade was as follows:

Capt. J. N. Miller, U. S. N., commanding naval brigade.

General staff.—Lieut. C. E. Colahan, adjutant-general; Pay-Inspector J. H. Stevenson, commissary; Surg. T. N. Penrose; Passed Asst. Paymaster C. W. McGowan, quartermaster; Lieut. R. Wainwright, military engineer; Ensign H. Eldridge, secretary; Naval Cadet R. Welles, aid; Naval Cadet C. W. Hazeltine, signal officer.

Marine battalion: Capt. J. M. T. Young, U. S. M. C., commanding; first company, Lieutenant Goodrell; second company, Lieutenant Gulick; third company, Lieutenant Bates.

Infantry battalion of seamen: Lieut. R. P. Rodgers, U. S. N., commanding; Lieut. R. T. McLean, adjutant; first company, Lieut. W. W. Kimball; second company, Naval Cadet W. L. Capps; third company, Naval Cadet Littlehales; fourth company, Lieut. John Downes; fifth company, Lieut. S. C. Paine; sixth company, Lieut. G. H. Peters; seventh company, Lieut. York Noël; eighth company, Ensign F. R. Wall; ninth company, Ensign J. T. Newton; tenth company, Lieut. Alfred Reynolds.

The first, second, third, and fourth companies were from the Tennessee; the fifth and sixth from the Vandalia; the seventh and eighth from the Swatara: the ninth from the Yantic, and the tenth from the Alliance.

Artillery battalion : Lieut. T. T. Wood, U. S. N., commanding; Ensign W. S. Sims, adjutant; first platoon, Lieut. M. F. Wright; second platoon, Lieut. H. Hosley third platoon, Lieut. F. E. Sawyer; first section, Naval Cadet Ellicott; second, Naval Cadet Hulme; third, Naval Cadet Stout; fourth, Naval Cadet Palmer; fifth, Naval Cadet Seymour; sixth, Ensign Mayo.

The battery consisted of four 3-inch B. L. R's, from the Tennessee, Vandalia, Alliance, and Yantic, and two Gatling guns, from the Tennessee and Swatara.

Passed Assistant Paymaster Barry and Asst. Surg. T. C. Craig were detailed as assistants to the commissary and surgeon.

The following is a summary statement of the brigade:

Staff		9
Marine battalion:		
Officers	4	
Men	99	
		103
Infantry battalion:		
Officers	20	
Men	352	
		372
Artillery battalion:		
Officers	13	
Men	117	
		130
Pioneers:		
Officers	1	
Men	15	
		16
Commissary department:		
Officers	1	
Men	6	
		7
Medical department:		
Officers *	2	
Men	7	
		8
Signal corps:		
Officers *	1	
Men	2	
		2
Bugiers		4
Officers' cooks and servants		9
Total		660

The site selected for the camp was in all respects excellent, whether from a sanitary point of view, its proximity to the landing-place, or for the immediate object of the encampment—drill. (See Plate XI.)

---

* One already counted on staff.

It was somewhat back from a bluff about 100 feet high, on the northwest end of the island; its soil was sandy, though well covered with sod; its surface was perfectly drained, and its surroundings furnished available space for the manœuver of a large body of men.

Its only drawback lay in the fact that good fresh water was not to be found in its vicinity. On this account it became necessary to supply the camp with water from the ships, which entailed an additional labor.

The beach upon which the landing was to be made was about 2 miles from the ships, and but a third of a mile from the site chosen for the camp.

Monday began with rain so that the landing was delayed; but shortly after 8 o'clock the rain ceased, signal was made to land the heavy material, and by 11.30, the boats having returned, the brigade was on its way to the beach.

A company of marines embarked at the first as a guard over the material landed. Upon the arrival of the brigade at the camp ground this company became the guard of the day, and sentinels were posted from it.

After the first day all the guard duty was performed by the bluejackets.

Owing to the lack of sufficient means of transportation (but two teams could be procured) much of the material for the construction of tents was not on the ground at the time of the arrival of the brigade at the site of the camp. The tents were all up, however, at 2 o'clock; the men had had their dinners, which had been brought on shore as indicated in the memorandum of instruction, the kitchens were ready for use, the latrines had been prepared, and trenches dug around the tents.

After this meal, which had been cooked on board ship, rations were drawn from the commissary and all food was cooked at the camp kitchens.

Later in the afternoon the company and battalion parades were assigned, and the following routine published:

DAILY ROUTINE.

5 a. m. Reveille. Outer line of sentinels called in; coffee; march to bath.
7 a. m. Breakfast.
7.30 to 8 a. m. Police camp.
8 a. m. Sick call.
9.30 a. m. Drill call and assembly; target practice with small arms.
11 a. m. Recall from drill.
11.30 a. m. Serve out dinner to cooks.
12 m. Dinner.
1 p. m. Police camp.
2.30 p. m. Battalion drill; target practice with B. L. R. and Gatlings.
4 p. m. Recall from drill.
5.30 p. m. Call for parade.
6 p. m. (or after parade). Supper.
At sunset outer line of sentinels posted.
9. m. Tattoo.
9.15 p. m. Taps.

The pioneers, with details from the battalions, under the direction of the military engineer threw up two light earthworks, in which the pieces of artillery were placed for the defense of the camp.

The general arrangement of the camp is shown in the accompanying plan. (Plate XI.)

The infantry battalion of seamen camped in column of divisions, with one tent to each company; the officers' tents being on the left flank opposite the division streets.

The tents of the marine battalion were in one row, in advance of the infantry battalion.

The artillery were camped on one street with tents on each side of it. The guns were parked in the street when not placed in the earthworks.

The kitchens were on the right flank of the camp of the infantry, and the latrines were on the same flank close to the bluff.

In the construction of tents the awnings, sails, light spars or capstan bars were used. The different forms and sizes of this material caused some variety in the appearance and proportions of the tents, and somewhat impaired the regularity of the camp lines.

The general design of the tents were as follows: Capstan bars or boat's masts were used for the end uprights, to which was lashed a boat's strongback or stun'sail boom as a ridge pole. An awning or sail was then middled over the ridge pole, and the tent raised. The uprights were sunk in the ground about a foot and well guyed to the front, rear, and sides. The leaches were hauled out to the pegs, and the ends of the tents were then closed with boat or other light sails. A shallow trench was dug around each tent to afford drainage.

The camp was now organized. After supper the long roll and call to arms were sounded and the brigade formed to resist attack.

DRILLS.

The hours assigned for drill were spent by the infantry battalions at battalion or company drill, principally the former. Much attention was given to skirmishing and the methods of attack, and the movements of the battalions were as a rule executed in a very creditable manner.

Companies were detailed for target practice, which was carried on throughout the day.

The artillery were exercised at the school of the section and battery, and at target practice with the B. L. R.s and Gatling guns, all of which were very instructive.

Thus there were two drills each day of an hour and half's duration in addition to the brigade parade. which was also instructive as in the formation of the brigade the men were manœuvered by battalions. Three days of such work gave the men an understanding of manœuvers which instruction on board ship, however careful, could never accomplish.

COOKING ARRANGEMENTS.

The regulation boat stoves gave much satisfaction, although more was required of them than should be demanded. Each stove cooked the food of 70 to 90 men. The ration to be cooked consisted of coffee, rice, potatoes, fresh meat, salt pork or canned meat, and tomatoes. The food was, as a rule, well prepared, but in order to provide for so large a number it was necessary to cook twice; that is, as much of the meal as the stoves could cook was prepared, placed to one side, and the remainder cooked before the meal. This was inconvenient, and necessitated the consumption of more fuel and labor.

A stove should be allowed for every 50 men. For this number of men the regulation stove can properly and conveniently cook any ration which may be issued. With it broiling, boiling, and frying may be done. The daily consumption of cord-wood is about four or five sticks. Ordinary camp fires were also used for various purposes, particularly for keeping hot that portion of the food first cooked.

At reveille on the morning of the 14th the men rolled their kits, had coffee, and began to break camp. When they went to breakfast at 7 o'clock all the tents were down, and all the material, except the stoves, which were in use, were ready for removal. At 7.30 four teams arrived for the quartermaster's work, and by 8.45 the camp was clear of all material and cleaned. The teams hauled the heavier articles and the men shouldered the spars and lighter material.

In re-embarking, the reverse of the programme for landing was observed, and after the boats had discharged the *matériel* at the ships and were on their return to the beach, a brigade parade was held, and the command marched to the beach, where it embarked, reaching the ship at 12.30.

The encampment of a naval brigade of 660 officers and men for three days was of a nature before unknown in our service; in fact, it is doubtful if so large a body of men-of-war's-men have ever served together on shore for so long a time (the Franco-German campaign excepted). It becomes, then, a subject of criticism and offers a fit opportunity to notice deficiencies and to draw lessons from the experience thus afforded.

The lack of equipment for a landing force from our ships became most apparent in making the preparatory arrangements for this encampment. The want of haversacks and canteens made it necessary to have food and water upon the ground before or on the arrival of the men, thereby hampering the transportation service. [Considerable advance has been made in the matter of equipment since this report was written.] This consisted of two teams hired for the occasion, one cart made of two Gatling-gun carriages, and details from the command. The difficulties encountered made most noticeable the necessity of providing proper means of transportation before undertaking operations on shore instead of trusting to improvised carts and material found on board ship.

The equipment for the carriage of a suitable amount of ammunition was most defective. Owing to the present (then) style of cartridge boxes (Hitchcock and Navy) each infantry man could carry but 20 rounds of ammunition without breaking the packages, although if this had been done the men from the Tennessee might have carried 40 rounds. But 40 rounds with little or no reserve ammunition is a very meagre supply for a man armed with a magazine rifle. [This has been remedied in the new allowance.]

The caisson boxes of the 3-inch B. L. R. contained 20 rounds of ammunition, and the Gatlings were supplied with 920 rounds packed in feed cases in their boxes.

No ship in this squadron is supplied with a boat carriage for the B. L. R. For boat operations then the old 12-pdr. howitzer must be used. Comment on this is needless.

But one cart (referred to in the memorandum of instructions) could have been made from the material of this squadron for the transportation of reserve ammunition.

Considering the variety of forms and the sizes of the canvas used and the fact that these could not be in any way altered, the tents were probably as good as could be devised under the circumstances.

Their size rendered it difficult to make the sides taut, so that in heavy rains they would probably not have shed the water well, and their considerable weight made their transportation and construction difficult and slow.

HAMMOCK ROLLS AND INTRENCHING TOOLS.

The hammock rolls proved a most awkward make-shift. It was necessary to provide some means of carrying the men's blankets and clothing, as well as to give them something upon which to lie. But the rolls were very stiff and uncomfortable and were not suitable for carrying a proper supply of clothing.

Haversacks, canteens, and means for properly carrying clothing, should certainly be provided.

The intrenching tools were not well adapted to, and were insufficient for, the end desired. In these days of precise and destructive fire-arms the supply of tools for hastily providing cover should be well considered.

Such were the chief defects noted. They were defects certainly vital, due to the utter lack of equipment, and so apparent that they may serve to induce the Department to appoint a board to consider the subject of the proper equipment of the landing forces of our vessels.

This equipment should be such that each man might be enabled to carry his arms and ammunition, means for providing cover against fire, his water and ration, his shelter and clothing, and yet not destroy the mobility of the force.

A naval brigade should possess great mobility, consequently shelter-tents only should be provided to shelter the men. Should the brigade go into a permanent encampment suitable means could be provided which would be adapted to the circumstances.

Having drawn attention to the deficiencies it becomes the more agreeable duty to enumerate the many good points observed.

The camp was well kept and policed; the guard duty was well performed by the blue-jackets, who quickly appreciated the responsibilities of the position of the sentinel and promptly fulfilled all of the duties; the spirit and conduct of the men were excellent, and the battalion and skirmish drills, the artillery and Gatling practice, were alike creditable to officers and men. In fact, had the encampment lasted a week instead of three days, it is probable that the brigade, as far as its *personnel* was concerned, would have been in good condition to have undertaken any operations for which they might have been called upon in time of war.

It was noticeable that the sergeants and corporals chosen from the petty officers and leading men performed their duties intelligently and with force, and that the men in general soon understood the intention of the manœuvers, and adapted their movements to the accidents of the ground and obstructions, and to the plans of attack and the value of cover.

Another fact was apparent. The men who were most distinguished as seamen were as a rule most prompt and exact in their duties on shore.

It is well for naval officers to realize that the preparation, equipment, and uniform organization of our landing forces are among the most important subjects to which they may give their attention, having in mind that such detachments have been landed at short notice in the ordinary times of general peace to protect American interests abroad, and are liable to be called upon for more serious operations near the sea-coast to enforce the Government's demands upon states or tribes which listen to no other argument than force.

This encampment was organized and undertaken upon the short notice of two days (one of which was Sunday). The experience gained was most valuable. It has accentuated our shortcomings, the necessity of equipment, and the fact that the naval brigade, if properly conducted and equipped, is capable of important operations on shore. If, as is to be desired, each succeeding summer may furnish an opportunity for like manœuvers, it is hoped and may be expected that in the course of a few years we may be in position to land, whenever called upon, a force in all respects prepared for any military operations which seamen may be called upon to perform.

SHIPS.

ENGLAND.

THE RENOWN AND SANSPAREIL.

The first of these ships is being built by Armstrong, Mitchell & Co. and the second by Samuda Bros. The specifications were issued by the Admiralty in March, 1885, and there may be slight changes in them.

These ships are the largest laid down for the English navy since the Inflexible, twelve years ago, and are to be finished in three and one-half years. They are to cost £640,000 and £601,000, and will be of the following dimensions: Length, 340 feet; breadth, 70 feet; draught, 27 feet 3 inches; displacement 10,470 tons. They will be of steel, with longitudinal framing, double bottoms, and transverse water-tight bulkheads; will have ram bows of unequaled strength; five above-water torpedo ports and four below-water.

There will be two 110-ton B. L. R's in a single turret on the main deck, with a range of fire from ahead to 60° abaft the beam. The upper and spar decks are partial, not extending as far forward as the turret. On the upper deck twelve 6-inch B. L. R's are mounted in broadside, and on the spar deck is an 18-ton 9.2-inch gun mounted on a turn-table as a stern-chaser. There will also be many machine and rapid-firing guns and Whitehead torpedoes. The turret, breastwork, protecting turret gear, and water-line belt amidships, will have 18-inch steel-faced armor and the transverse bulkheads at the belt ends will have 16-inch armor. The midship citadel thus formed is roofed over by a 3-inch armored deck, and 3-inch armored decks reach from the lower edges of the citadel to the extremities. The 6-inch batteries are protected at their ends by 6-inch steel-faced armor screens, by 3-inch traverses between the guns, and by 3-inch armor on the sides—the 3-inch armor being in three thicknesses of ½-inch and 2-inch plates. There is an armored loading tube (2-inch) for the stern-chaser. All backing will be of 6-inch teak except that of the 6-inch screens, which will have 10 inches of teak. The armored pilot towers will weigh 80 tons.

The ships will be driven at an estimated speed of 15.5 knots by twin screws with independent engines of the vertical inverted three-cylinder type, the stroke of piston to be 4 feet and the cylinder diameters 38, 58, and 88 inches for the high, intermediate, and low pressure cylinders; the aggregate I. H. P. to be about 8,500, and the revolutions 95. Steam of 130 pounds will be furnished by eight boilers of Siemens-Martin steel, with a forced draught of 3-inch water pressure.

THE BENBOW.

The Benbow is one of the Admiral class; was laid down in November, 1882, launched in June, 1885, and will be ready for service about the spring of 1887. The following are her principal dimensions: Length, 330 feet; breadth, 68 feet 6 inches; draught, 27 feet 3 inches; displacement, 10,050 tons.

She is a steel armor-belted, barbette-turret, twin-screw ram. She has about two hundred water-tight compartments so arranged that practically she has three skins as high as the main deck.

Although very much larger the installment of her armament is much like that of the Boston and Atlanta. She carries two 110-ton 16¼-inch B. L. R's in barbette towers, one at each end of the ship, on the main deck. These guns have arcs of fire of about 270°. With 900 pounds of powder they throw an 1800-pound projectile with a velocity of 2,020 feet, giving an estimated energy of 61,000 foot tons, about twice that of the 80-ton guns, and will be the most powerful guns existing; Krupp's 119-ton gun will have only 46,000 foot tons of energy. Between the barbettes is a battery of ten 6-inch guns, also on the main deck. The extreme guns of this battery have ports enabling them to fire fore and aft as well as on the broadside. On the spar deck, which extends between the barbettes, are eight 6-pounder rapid-firing guns mounted in broadside with ¾-inch shields attached to their carriages. In half-turrets on the bows are two machine-guns, and four more are on the quarters. There will be a .45-inch Nordenfeldt at each corner of the spar deck and eight Gardner guns mounted on the armor screens which protect the 6-inch battery from raking fire. The single military mast will also have two machine-guns in the top. The unoccupied ports of the extreme guns of the 6-inch battery are filled by rapid-firing guns. There will be a torpedo-launching tube in the stern and two on each broadside. The armor on the belt is 18 inches thick and steel faced. It is 150 feet long and 7.5 feet deep, of which 5 feet is below water; the armored bulkheads at its ends are 16 inches thick. There is a 3-inch armored deck in three thicknesses of 2-inch and ½-inch plates about 3 feet below the water-line, curving down at its ends and sides to meet the armor belt. A protective deck reaches from the lower edges of the armored bulkheads to the extremities. The 6-inch battery is protected from raking fire by 6-inch steel-faced armor screens reaching from the sides to the barbettes. The sides of the ship at the battery deck are of 1-inch steel. The barbette turrets are of 14 to 16 inch inclined steel-faced plates with armored loading-tubes. The conning tower is abaft the forward tower with 9 to 12 inch compound armor and an armored tube for communication and steering-gear. All along the length of the engines and boilers there is 9 feet of coal protection, with wing-passages outside the coal for communication, &c.

There are two separate engine-rooms and four separate boiler-rooms. The engines will develop 7,500 H. P. with natural draught and 9,800 with forced draught. The contract speed is 16 knots, but 17 will probably be reached. The coal supply is ordinarily 900 tons, but there is room for 1,200. The ship will carry a second-class torpedo boat, a 48-foot picket boat, a 37-foot steam-launch, besides the usual complement of boats; and her crew will number 450.

ORLANDO—UNDAUNTED—NARCISSUS—AUSTRALIA—GALATEA.

These five ships are of the belted-cruiser class, and the contracts for building them were closed about the end of April, 1885. They are to be finished in two and one-fourth years.

The Australia and Galatea were awarded to Napier & Sons, of Glasgow, for £215,000 each. Two of the others were given to Palmer & Co., Jarrow, and the fifth to Earl & Co., Hull.

These ships are all built of steel, and are to be developments of the Mersey class, as that class was of the Iris. The following are the dimensions of the new class: Length, 300 feet; breadth, 56 feet; draught, 21 feet amidship; displacement, 5,000 tons.

The armament will be two 18-ton 9.2-inch guns mounted on the upper deck as bow and stern chasers, with arcs of fire of about 270°; also ten 4-ton 6-inch guns on the upper deck between the heavy guns. The four extreme guns of the 6-inch battery are mounted on half-turrets on the sides and command arcs of 159°, of which 4° is on the opposite side of the ship. The other six guns are mounted on central-pivot carriages in recessed ports and command 60° forward and as much abaft the beam. The large ports necessitated by this arrangement are filled by circular steel shields revolving with the carriages.

On the main deck amidships are four Nordenfeldts, two on each side, firing through long, low ports with arcs of 120°, and four more are on the same deck in half-towers, one on each bow and quarter. There are also six rapid-firing 6-pounders on the main deck in half-towers, two of which are forward of the first-mentioned Nordenfeldts and four abaft them. The four extreme 6-pounders fire in a fore-and-aft line.

On the protective deck are mounted four torpedo-launching carriages, one on each bow and quarter. They train within 10° of the fore-and-aft line and command 90°. On the platform deck are four fixed under-water launching tubes, below the armor belt. Two, firing broad on the bow, are at the corners of the armor belt and armored bulkhead; the other two are just abaft them and fire on the broadside. There are machine-guns in the tops. It is noticeable that in these ships the secondary battery is on the lower deck. The water-line is protected amidships by a 10-inch steel-faced armor belt 200 feet long. An armored bulkhead crosses the ship at each end of the belt.

An armored deck, of from 2 to 3 inches, at the upper edge of the belt protects the machinery, and the ends are protected by an armored deck extending from the lower edge of the armor belt. The coal is an important part of the armor. The bunkers extend all along the midship part of the ship just above the protective deck, with thwartship bunkers at their ends, and walls of coal about 6 feet thick run the length of the boilers and machinery, between the protective deck and the inner bottom, leaving wide, empty wing-passages outside of them. There is also a conning tower with 13 inches of armor abaft the forward 9-inch gun, with an armored communication-tube and armored loading hoists for the heavy guns.

The engines are to work independent twin screws, and will be the first in the royal navy of the triple expansion type; the steam pressure will be 125 pounds, and will be furnished by four double-ended boilers working with forced draught in separate fire-rooms, divided by a longitudinal bulkhead. The H. P. will be 7,500, giving a speed of 17½ knots. The coal capacity will be 900 tons.

There will be two masts with fore-and-aft sails, pole topmasts, and very large protected tops; also duplicate steering gear, mechanical ventilation, &c.

THE POLYPHEMUS.

The Polyphemus was built at Chatham; was laid down in 1878, and launched in 1881. On her first trial trips her boilers proved unsatisfactory and were removed. She has now (May, 1885) just completed her final trial trips with most satisfactory results.

She is a twin-screw ram and torpedo vessel, and has no heavy gun armament. Her dimensions follow: Length, 240 feet; beam, 40 feet; draught aft, 21 feet 3 inches; displacement, 2,640 tons. The vessel is almost completely submerged, and depends upon artificial light and forced ventilation throughout her interior at all times. The armor protection is afforded by a 3-inch turtle-back rising above the water-line, but with submerged edges, made of small tiles of Whitworth compressed steel secured to 2-inch plates. She will have eight Nordenfeldt guns, but her principal weapons will be her ram and forty Whitehead torpedoes, launched from above-water carriages or through one bow and four broadside under-water launching tubes, the recent trials showing that this may be done at any speed. The steering gear is worked by steam, and besides the main rudder are two auxiliary ones under the bows which may be raised at will into recesses. The latter may be used at any time in conjunction with the main rudder, but are particularly effective when going astern.

The engines are of the horizontal type, and developed on trial 5,500 H. P., giving a speed of 17.847 knots, nearly a knot in excess of the estimate. The boiler pressure is 110 pounds, and the difficulty of making good the junction of the tubes and tube sheets caused the original boilers to be removed (through the bottom). The new boilers are eight in number, long and low, with two furnaces in each boiler, an intermediate fire-box, and the tubes beyond, and are in four independent water-tight compartments.

Two new Polyphemuses are to be laid down. They will be rather larger with a small gun armament, and an ordinary deck above the turtle-back will give greater habitability. This, with a greater coal supply, will give independent cruising power, which the present vessel was not meant to have.

THE SCOUT AND FEARLESS.

The Scout is classed as a torpedo cruiser. She will have a ram bow, a long poop and forecastle, a high rail amidships, and a three-eighth-inch steel protective deck over machinery. She also has a coal protection of five to six feet in thickness in wake of machinery. Coffer-dams are placed about all hatches and scuttles. The conning tower is on the forecastle and is protected by two inches of steel armor. The steering-gear is entirely below water.

Her principal dimensions are: Length, 220 feet; beam, 34 feet; greatest draught, 14.5 feet; displacement, 1,430 tons. She is to have two horizontal two-cylinder compound engines, of 26 and 46 inches diameter by 2 feet 6 inches stroke, driving twin-screws. It is estimated that the engines will develop 3,200 horse-power and a speed of more than 16 knots. The boilers, four in number, are cylindrical, 10 feet in diameter by 18 feet in length, and are built of steel.

The Scout is to be armed with torpedoes, and is fitted with eleven launching tubes, ten above and one below water. The below-water tube is in the stem. Of the above-water tubes two are fixed, one to fire directly ahead and one astern, and the others, in broadside, are capable of being trained. She will also carry four 5-inch B. L. R's, two on the forecastle and two on the poop.

The Scout will be a fine sea-boat, and is designed to accompany the battle-ships of the fleet. Her coal capacity is 450 tons, and her probable cost $324,109.

The design of this class of vessel has been so favorably received that seven others of 1,600 tons displacement have been ordered, and are now in construction. Their names are the Archer, Brisk, Cossack, Mohawk, Porpoise, Tartar, and one not named. These vessels will have a protective deck throughout their length, and will carry a heavier battery than the Scout—six 6-inch B. L. R's on sponsons, two on the forecastle, two on the poop, and two in the waist.

FRANCE.

THE FORMIDABLE.

The Formidable is a first-class armored barbette-turret twin-screw line-of-battle ship, built of iron and steel. She was laid down in 1879, launched in 1885, at L'Orient, and will probably make her trial trip in 1887. Her probable cost is 16,000,000 francs. The following are her dimensions: Length, 104.4 meters (342 feet 6 inches); beam, 21.34 meters (70 feet); draught, 7.9 meters (26 feet); displacement, 11,336 tons. There is a double bottom under all the midship part of the ship, and eleven water-tight bulkheads, rising as high as the armored deck, or 1.10 meters (3 feet 8 inches), above the water-line. Besides, a number of longitudinal bunkheads complete her subdivision and give her rigidity. The Formidable has a ram bow and several torpedo-launching tubes. Her armament consists of three 75-ton 42-centimeter (16.5-inch) guns in barbette turrets, all on the midship line, of twelve 14-centimeter (5.5 inches) in broadside, and eight Hotchkiss guns, of which two are mounted on the signal masts. The turrets have 40-centimeter (15.7-inch) steel armor on their sides, with steel bullet-proof hoods capping them. The whole water-line is protected by a steel belt varying from 35 centimeters (13.7 inches) at the extremities to 55 centimeters (21.6 inches) amidships, and there is a deck armored with 8-centimeter (3.1-inch) plates over all its length, except over the boilers and machinery, where it is 10 centimeters (4 inches). The total weight of armor is about 3,900 tons. Her engines are both of the compound three-cylinder type, which will develop 8,320 I. H. P., with forced draught, giving a speed of 15.2 knots. The coal supply is 800 tons, good for 1,650 miles at full speed, or 3,000 at 10 knots. Although she has two military masts she will be without sail power. Her crew will be 500 men.

CAÏMAN.—Laid down at Toulon in 1877. Launched in 1885.
INDOMPTABLE.—Laid down at L'Orient in 1877. Launched in 1883.
REQUIN.—Laid down at Bordeaux in 1878. Contract built. Launched in 1885.
TERRIBLE.—Laid down at Brest in 1877. Launched in 1881.

These ships are armored twin-screw barbette-turret ships, built of iron and steel, and are meant for coast-guard use as well as for battle ships.

The following are the Caïman's dimensions: Length at water-line, 84.8 meters (278 feet); breadth, 18 meters (59 feet); draught, 7.50 meters (24 feet 8 inches); displacement, 7,230 tons.

She has a heavy ram bow and a torpedo outfit, and will be armed with two 75-ton 16.5-inch guns, each in its own turret, one forward and one aft. Each gun has an arc of fire of 270°. There are besides four 10-centimeter (3.9-inch) guns in barbette at the corners of the spar deck, which reaches between the heavy guns, and Hotchkiss guns. She has 45-centimeter (18.6-inch) armor on the turrets, and 35 centimeters to 50 centimeters (14.8 to 20.6 inches) on the water-line belt, and 8 centimeters (3.1 inches) on the armored deck. There are also steel hoods over the breech of the heavy guns. The engines, from Creuzot, are of the three-cylinder compound type, and are to develop 4,800 H. P., with natural draught, giving a speed of 14 knots. The boilers are twelve in number, with two furnaces each, and are placed with their backs to the midship line. There are four smoke-pipes, two on each side. Just forward of the smoke-pipes is the conning tower, and forward of that is the tripod foremast, and then comes the forward gun. Abaft the smoke-pipes at some distance is another tower, then the tripod mainmast and the after gun. The masts are only for signaling and mounting Hotchkiss guns. The crew will number 500. Cost, about 10,500,000 francs.

THE MILAN.

This vessel was designed in 1879 for a torpedo dispatch vessel, but is now intended solely as a scouting vessel. The trials of her engines were completed in May, 1885. She was built at St. Nazaire by contract, and has the following dimensions: Length, 92.4 meters (303 feet); breadth, 10 meters (32 feet 10 inches); draught, 3 meters forward, 4.60 meters aft (9 feet 10 inches and 15 feet 1 inch); displacement, 1,550 tons. She is built of steel and is very light, and has a swan-breasted ram bow. She is unprovided with torpedoes. Her armament consists of five 10-centimeter (3.9-inch) B. L. R's on hydraulic carriages, one on the bow, one on the stern, and the others on the broadside on shifting pivot carriages, to fire on either side, and eight 37-centimeter (1½-inch) Hotchkiss guns. She has twin screws, each worked by two compound tandem engines, and Belleville boilers. On her trial, at a little more than load-draught, she made 18.4 knots in a rather rough sea, developing 4.132 H. P. with natural draught; more than had been expected with forced draught. This trial proves the Milan the fastest man-of-war in existence. Her rig is that of a three-masted schooner, and her coal supply is 300 tons.

BELLEVILLE BOILERS.

The Belleville boiler is of the same general type as the Herreshoff boiler, well known in this country.

As the result of extensive trials on board the French man-of-war Voltigeur, of 811 tons and 1,000 H. P., this type is regarded with great favor in the French navy, and has been fitted in the new fast cruiser Milan, of 1,640 tons and 3,800 H. P.

The Voltigeur has six boilers—three on each side—placed back to back, separated by sheet-iron plates, and the group is roofed over with sheet-iron, serving to collect the gases of combustion and direct them to the smoke-pipe.

The furnaces are rectangular, about 4½ feet square, with two doors on account of their width, and the grate-bars are very deep and undulating, so that they touch each other, forming lozenge-shaped air-spaces. This keeps the grate-bars cool, prevents clinker, and gives them a longer life. [In the latest boilers the grate-bars are tubular, and the feed-water passes through them on its way to the boiler, thus accomplishing the same result.] The walls of the furnaces are of fire-brick, which causes a very high temperature in the combustion chamber. Over each furnace are five "elements," or nests of tubes, forming the boiler. Each nest consists of two tubes horizontally and nine tubes vertically, joined together in pairs at their ends, so that water enters the first tube at the bottom, passing successively through all the tubes till it issues from the last as steam. The heated gases pass directly upward between these water-tubes, and their direct impact produces the maximum heating effect.

Each element is connected by its first lower tube with an automatic feed-regulator, separate for each boiler. On account of the small contents of the tubes it is necessary that the supply of feed-water should be constant and regular. The last tube is connected with a steam-drum or "purifier" at the top of the boiler, which serves the double purpose of drying the steam, which comes up very wet, and of freeing from impurities the feed-water which flows through it. The purifier is cylindrical and contains a plate which gives a rotary motion to the entering steam, freeing it from the water in it by centrifugal force. The water from the feed-pump enter ing the purifier comes in contact with the steam, and the resulting quick rise of temperature precipitates the calcareous matter, which, however, is carried in suspension to the mud-drum, where it is blown out, while the water goes on to the feed-regulator.

Before the steam gets to the boiler it passes through a general purifier, similar to the separate ones attached to each boiler.

The following are the advantages claimed for the Belleville boiler:

(1) Slight danger in case of rupture, owing to small amount of water contained in the boilers.

(2) Use of high pressures without danger.

(3) Steam pressure is quickly raised.

(4) Economy of fuel.

(5) Light weight.

(6) The boilers are low, and may be kept below the water-line.

(7) Pressure in boilers may be varied quickly without danger of foaming.

(8) No water is carried over to the cylinders.

(9) Facility for repairs, as any element may be dismounted in a short time while the others remain for service.

(10) Easily kept in order, as all parts are readily accessible.

(11) Easily put on board, as it is made of small pieces which may be assembled on board.

(12) On account of the high temperature of the combustion chamber hard coals may be used without the disadvantages usually attending them.

The Board which examined the boilers in 1880 found that their economy of fuel was not great, that they were complicated, and that firing was harder work, but the new tubular furnaces are said to be easy to work. The Board's *first objection was contradicted by the results of an extended cruise.*

BELLEVILLE SPEED REGULATOR.

The main engine-shaft works two little pumps which force water through a regulator against the pressure of a spring. The outflow of the water is by a graduated valve. The spring of the regulator controls the throttle-valve of the engine. It is evident that if the speed of the engines or position of the valve is altered the throttle-valve will move, owing to the change of pressure on the spring. The delivery of the pumps, the size of the valve, and strength of the spring are so proportioned that at the normal speed of the engines sufficient steam is admitted to maintain that speed. The apparatus is thus a quick-acting speed regulator or governor if left to itself, while by working the cock controlling the outflow the speed may be altered. By connecting this valve with the captain's conning tower he is given instant and direct control of the speed of the ship.

ACHÉRON.—Launched at Cherbourg May, 1885.
COCYTE—PHLÉGÉTHON—STYX.—Building at Cherbourg.

The Achéron is a twin-screw armored steel gunboat of the following dimensions: Length, 55.2 meters (181 feet); breadth, 12.30 meters (40 feet 4 inches); draught, 3.6

meters (11 feet 10 inches); displacement, 1,640 tons. She carries a 27-centimeter (10½-inch) gun in a barbette turret forward, and two 10-centimeter (3.9-inch) guns amidships, one on each side. The bridge reaches over them, and the sides tumble home, to give each a full semicircle of firing arc. At the forward edge of the bridge is the circular conning tower, out of which rises a military mast. The whole water-line is belted with 9½ inch armor. There will be four boilers, each with one furnace, and the speed will be 13 knots.

CONDOR—ÉPERVIER—FAUCON—VAUTOUR.

These ships are of the class officially known as cruising torpedo-ships (croiseurs-torpilleurs). They are identical in design. The first two are building at Rochefort and the others at Toulon.

The Condor is the most advanced, and was launched in May, 1885. She is built of steel, and the following are her principal dimensions: Length, 69.75 meters (229 feet); breadth, 8.9 meters (29 feet); draught, 4.24 meters (14 feet); displacement, 1,260 tons. She has a swan-breasted ram bow and five above-water torpedo-launching tubes installed between decks, two on each broadside and one as a sternchaser. She has, besides, five 10-centimeter (3.94-inch) guns, one of which is a stern-chaser under the poop, two are bow-chasers under the forecastle, firing from ahead to the beam, and two more are in barbette half-turrets abreast the smoke-stack and are protected from plunging fire by the bridge which extends over them. In order that these two guns may command the entire horizon, the sides tumble home very much to allow them fore-and-aft train. There is an armored deck reaching fore and aft, protecting the machinery, magazine, and steering gear, and the ship is divided into water-tight compartments above the armored deck. She has twin screws, with engines aggregating 2,000 I. H. P., and giving an estimated speed of 17 knots, and is three-masted with leg-of-mutton sails. The officers' quarters are under the poop.

BOMBE—COULEUVRINE—DAGUE—DRAGONNE—FLÈCHE—LANCE—SALVE—SAINTE-BARBE.

These vessels form a squadron of torpedo-dispatch boats (avisos-torpilleurs). The construction of the first six was given to a private firm, Forges et Chantiers du Havre, and the Bombe, the first of the squadron, was launched on April 16, 1885. She is built of steel and of the lightest possible scantling. Her principal dimensions are as follows: Length, 187 feet 10 inches; breadth, 20 feet; draught, 5 feet 6 inches; displacement 321 tons. She has a ram bow and two torpedo-launching tubes, and is armed with two 9-centimeter (3.54-inch) guns and three machine-guns. The engines work twin screws, and the I. H. P. is to be 1,800, giving an estimated speed of 17 knots. In June, 1885, the Bombe made 18 knots. The coal bunkers extend over the boilers. She is three-masted with leg-of-mutton sails.

The following is the classification of torpedo vessels and boats recently adopted in the French navy:

I. Torpedo-cruisers (croiseurs-torpilleurs): Displacement of from 1,260 to 1,280 tons.

II. Torpedo-dispatch boats (avisos-torpilleurs): Displacement from 320 to 360 tons.

III. Sea-going torpedo boats (torpilleurs de haute mer): Displacement of 50 tons and over.

IV. Coast-guard torpedo boats (torpilleurs-garde-côtes): *a*, displacement 25 tons; *b*, displacement 50 tons.

V. Picket torpedo boats (torpilleurs-vedettes): Displacement less than 25 tons.

ITALY.

THE RUGGIERO DI LAURIA, FRANCESCO MOROSINI, ANDREA DORIA, RÉ UMBERTO, AND SICILIA.

Besides the Italia and Lepanto, launched in 1880 and 1882, and now being completed, the Italians continue to make other formidable additions to their fleet.

The Ruggiero di Lauria, Francesco Morosini, and Andrea Doria, are in different stages of advancement; while the Ré Umberto and Sicilia have recently been laid down.

The Lauria was launched in August, 1884, and the Morosini in June, 1885. These vessels are of the same size as the Duilio, with all the improvements of construction, armament, and armor made since 1875. Their displacement is 10,000 tons and their horse-power 10,000.

The Doria, not yet launched, and the Ré Umberto and Sicilia are to be sister ships to the Italia. It is intended, however, to give the latter pair of ships 15,000 horse-power.

All these ships are to carry four 100-ton B. L. R's, in addition to a number of 6-inch B. L. R's, rapid-fire and machine guns. They will be protected with 17.7–18.5 inches of steel armor.

THE GIOVANNI BAUSAN.

This vessel was laid down by Sir Wm. Armstrong and Co. at Elswick in 1882, and was delivered in May, 1885.

She is a steel cruiser, schooner-rigged, similar to the Esmeralda but rather larger, having the following dimensions: Length, 280 feet; breadth, 42 feet; draught, 18½ feet; displacement, about 3,100 tons. She has a ram bow and three under-water launching tubes for Whitehead torpedoes. Her armament consists of two 10-inch B. L. R's, mounted as bow and stern chasers, loaded and worked by hydraulic gear, with arcs of fire of 240° each; six 6-inch 4-ton guns on Albini central-pivot carriages mounted in broadside; two 6-pounder rapid-firing guns of the Elswick type, and Hotchkiss and Nordenfeldt machine-guns. The guns are protected by heavy steel shields attached to the carriages, and the light guns aloft are mounted in small revolving turrets. There is an under-water protective steel deck 1½ inches thick and cork-filled cellular compartments along the water-line. The steering gear is hydraulic. There are twin screws, and the engines developed upon trial 6,000 I. H. P., making 116.5 revolutions with a speed of 17.5 knots. The engines and boilers are of the Esmeralda type. The coal supply is 600 tons, good for 5,000 miles at 10 knots.

THE ETNA, STROMBOLI, AND VESUVIO.

These vessels are classed as torpedo-rams and are now in process of construction; the first at Castellamare, the second at Venice, and the third at Leghorn. The Stromboli will be launched during the summer.

These are the largest torpedo-rams yet laid down by any nation. They are similar in design to the Giovanni Bausan. Their principal dimensions are: Length, 284 feet; beam, 43.3 feet; draught, 19.4 feet; and displacement 3,474 tons.

THE ARMOR FOR THE LEPANTO.

It is known that after the armor trials at Spezia, in October and November, 1884, M. Schneider, of Creuzot, was awarded the contract for providing the armor plates for the Lepanto. The contract requires the delivery of the plates, of 48 centimeters thickness, at the price of 1,955 francs the ton. The total weight of armor required is about 1,700 tons. The order will be delivered in two lots, and one plate of each lot will be subject to a firing test.

This test will be under conditions much more severe than those governing that of the English compound plates intended for the Italia, which consisted in a single shot fired from a 45-centimeter gun, aimed at the center of the plate, with a force exceeding by one-quarter that necessary to have pierced a wrought-iron plate of the same thickness. In the middle of the anterior face of the plate, 2.50 meters wide x 3.20 meters long, will be traced an equilateral triangle, whose sides are 1.25 meters long, the apexes being distant from the nearest edge at least 70 centimeters.

A 45-centimeter cast-iron projectile will be fired at each apex. The energy of the first shot will be that which is theoretically necessary to pierce an iron plate of the same thickness. The projectiles in the last two fires are to have energy sufficient to pierce an iron plate of one-fourth greater thickness.

In order that the lot may be accepted it is required that none of the projectiles shall entirely pass through the plate, and that after the first two shots no piece of the plate shall be detached so as to uncover the backing; it is permitted that some pieces may be knocked off by the third shot.

If the plate thus tested does not satisfy the conditions, the contractor will have the right to present another of the same lot, to be subjected to the same proof; and the result will determine the definite acceptance or rejection of the lot.

It is believed in Italy that the Creusot Works will succeed in mastering these difficult conditions.

GERMANY.

THE OLDENBURG.

This ship was launched in December, 1884, by the Vulcan Company at Bredow, near Stettin. She was originally designed to be of the Sachsen type, but was essentially modified during construction, and is now much smaller than the Sachsen. She is intended for service in the Baltic principally. Her dimensions are as follows: Length, 75 meters (246 feet); breadth, 18 meters (59 feet); draught, 11 meters (36 feet); displacement, 5,200 tons. She is armed with six long 24-centimeter (9.4-inch) guns in the central battery, and two more of the same size forward. There are also four 15-centimeter (5.9-inch) guns on the poop, besides three 7-centimeter (2¾-inch) Hotchkiss guns and two 8-centimeter (3.1-inch) boat guns. There are torpedo-tubes, and a ram bow. The central redoubt is protected by plates of 33 centimeters (12.9 inches), from Dillengen. She has twin screws and compound engines, aggregating 3,900 I. H. P. each, with four cylinders. The speed will be 14 knots.

THE ALEXANDRINE AND ARCONA.

The Alexandrine was laid down at Kiel in July, 1881, and was launched in February, 1885. She belongs to the class of unarmored cruiser-corvettes, is barque-rigged, and has a two-bladed hoisting-screw. Her dimensions are as follows: Length, 68 meters (223 feet); breadth, 12.5 meters (41 feet); draught, 5 meters (16 feet 5 inches); displacement, 2,370 tons. She is of iron, sheathed with a double layer of teak, and coppered; and is armed with ten 10½-centimeter (4.1-inch) guns, four machine-guns, and one torpedo-tube. The speed will be from 14 to 15 knots, with a horse-power of 2,400. There are two fire-rooms, with four cylindrical boilers in each.

The Arcona was launched in May, at Dantzig, and is a sister ship to the Alexandrine.

RUSSIA.

THE TCHESME, SINOPE, AND CATHERINE II.

The first two are being built at Sebastopol by the Black Sea Steam Navigation Company, and the third at the Nicolaïef dock-yard. They are sufficiently advanced to be launched during the present summer. They are barbette battle-ships protected on the water-line by 10 to 15 inches of compound armor. Their dimensions are: Length, 314 feet; beam, 69 feet; draught, 25 feet; and displacement, 10,181 tons. They are to be fitted with three-cylinder compound engines driving twin screws, developing 9,000 horse-power and 16 knots speed.

The battery will consist of six 12-inch B. L. R's mounted in three pear-shaped towers covered with 12 inches of armor, one 6-inch pivot gun astern, and six 6-inch rifles in broadside. (It is probable that some of the barbette guns will be mounted on disappearing carriages.)

The cost of each of these ships is about $3,131,000.

THE ADMIRAL NAKHIMOFF, MOSKWA, ADMIRAL ARKASS, AND ALEXANDER II.

These are armored barbette cruisers of similar design, but different dimensions and armament.

The Nakhimoff is protected on the water-line by a compound armor belt of 8 to 10 inches thickness. Her principal dimensions are: Length, 333 feet; beam, 61 feet; draught, 25.9 feet; and displacement, 7,781 tons. It is expected that the compound engines will develop 8,000 horse-power and drive the vessel at 16-knot speed.

The battery consists of four 9-inch B. L. R's mounted in four barbette towers protected by 12 inches of armor, and ten 6-inch B. L. R's in broadside.

The Nakhimoff will be launched at St. Petersburg this autumn. Her estimated cost is $1,910,000.

The keel of the Alexander II was laid down this spring at St. Petersburg. This vessel will be somewhat larger than the Nakhimoff, will be protected by armor 14 inches thick, and will carry two 12-inch, four 9-inch, and eight 6-inch B. L. R's.

The Moskwa and Admiral Arkass are smaller than the Nakhimoff, being of 5,754 tons displacement. Their barbette armor is 12 inches thick, but the belt is reduced in thickness to 5.8 to 8.3 inches.

The Russian Government also intends to begin the construction at St. Petersburg of an armored vessel of 8,632 tons displacement. The battery will consist of two 9-inch and four 8-inch B. L. R's in barbette towers, and eight 6-inch B. L. R's in broadside.

BRAZIL.

THE AQUIDABAN.

The Aquidaban was built by Samuda Bros. She was laid down in June, 1883, and her trials were finished in May, 1885. She is a ship-rigged, twin-screw, armored turret ship of the following dimensions: Length, 280 feet; breadth, 52 feet; draught, 18 feet; displacement, 5,000 tons; is built of Siemens steel, has many water-tight compartments, and is sheathed with wood and copper as high as two feet above the water-line. She has a ram and five Whitehead torpedo ports. The armament consists of four 9-inch 20-ton Armstrong guns, mounted with hydraulic gear, in two echelonned turrets; four 5½-inch Armstrong guns, on Vavasseur carriages, mounted on the upper deck, two firing right ahead and two right astern; and fifteen Nordenfeldt guns.

The turrets have 10-inch steel-faced armor and revolve in an armored breastwork protecting the loading gear. The engines, boilers, and magazines are protected by a 10-

inch to 11-inch water-line armor belt seven feet wide. There is a 2-inch steel deck extending fore and aft, which dips below the water-line at the extremities, strengthening the ram and protecting the tiller and steam steering-gear, and the engines are of the three-cylinder compound type. The boilers are eight in number. On the measured mile trial they developed 5,270 I. H. P. with natural draught, giving 15.257 knots, the contract being for 3,500 H. P. and 14 knots. With six boilers and forced draught the I. H. P. was 6,210 and speed 15.8 knots. With one screw the speed was 11.5 knots with 15° helm-angle.

CHILI.

THE ESMERALDA.

In April, 1885, the Esmeralda ran from Valparaiso to Callao, a distance of 1,292 miles, in one hundred and eight hours. The last eight hours of the run the engines were just turning over. Allowing 4 knots speed for these eight hours, the distance run in one hundred hours was 1,260 miles, making the average speed 12.6 knots. The speed by the log for the one hundred hours was 14.56 knots. The revolutions varied from 75 to 90 a minute, averaging 82.3. The average consumption of coal per hour was 4,560 pounds per hour. The boiler pressure varied from 65 to 84 pounds, but was usually from 75 to 80 pounds. The wind was always very light. The current was favorable.

During the exhaustive trials before her departure from England the highest speed attained by the Esmeralda was 18¼ knots per hour.

The coal consumption is as follows:

	Tons per day.
At 18 knots	200
At 17 knots	150
At 16 knots	100
At 15 knots	80
At 12 knots	40–45
At 10 knots	25
At 8 knots	18

Coal capacity, 600 tons.

Revolutions at full speed, 120; at 12 knots, 70.

JAPAN.

THE TAKACHIHO-KAN AND NANIWA-KAN.

These ships, of the general type of the Esmeralda, were built by Sir Wm. Armstrong & Co. for the Japanese Government, and were launched May 16 and March 18, 1885, respectively.

They are twin-screw steel cruisers, of the fastest and most heavily armed type, and are the largest ships yet built by this firm, having the following principal dimensions: Length, 300 feet; breadth, 46 feet; draught, 18½ feet; displacement, 3,600 tons. They have ram bows and can discharge Whitehead torpedoes from four above-water ports, and are armed with two 28-ton 28-centimeter (10¼-inch) guns, mounted on central pivot carriages as bow and stern chasers; six 15-centimeter (5.9-inch) guns in broadside on central-pivot carriages; and ten 1-inch machine-guns and two rapid-firing guns, besides four Gatling's mounted in the tops of two military masts. All the guns except the Gatlings are on the upper deck and carry steel shields attached to their carriages. Each ship has a protective deck, from 2 inches to 3 inches thick, extending fore and aft, with the sides curving below the water-line, and the hulls are minutely subdivided.

The engine-rooms and fire-rooms are double, and the engines are to develop about 7,500 I. H. P., giving a speed of from 18 to 18½ knots.

ORDNANCE.

UNITED STATES.

The batteries of the new cruisers are in a forward state, and will be ready before the ships are completed. The 6-inch B. L. R's for the Atlanta are practically finished. One of the 8-inch B. L. R's will be proved shortly at Annapolis.

The building of these guns has been allotted as follows:

	5-inch.	6-inch.	8-inch.
To the Washington navy-yard	2	10	4
To the South Boston Iron Works		6	2
To the West Point Foundry		5	2
Total	2	21	8

To these should be added two 10-inch B. L. R's for the Miantonomoh and one 10½-inch for the Puritan. These are building at the Washington yard, but are in a more backward condition owing to the delays in the delivery of the gun forgings by foreign makers.

Designs are completed and calculations made for 12 to 16 inch B. L. R's.

The practice with the 6-inch (Mark I) may be referred to as offering the confident hope of better results as to velocity and pressure from the American brown powder than those given by the German cocoa powder. With a charge of 50 pounds of powder and 100-pound projectile at least 2,000 f. s. may be the velocity expected. The 6-inch B. L. R. has given a range of over 7,000 yards at 10° elevation.

The following table shows the weights of gun, charge, and projectile for each class:

Gun.	Weight of gun.	Charge.	Projectile.
	Pounds.	*Pounds.*	*Pounds.*
5-inch B. L. R	6,200	30	60
6-inch B. L. R	11,000	50	100
8-inch B. L. R	27,050	125	250
10-inch B. L. R.	55,000	250	500
10½-inch B. L. R	64,500	275	550
12-inch B. L. R	100,000	425	850
16-inch B. L. R	(*)	1,000	2,000

* One hundred and ten tons.

The secondary battery of Hotchkiss guns for the new cruisers is to be as follows:

Chicago.	Boston and Atlanta.	Dolphin.
Two 57^{mm} rapid fire. Two 37^{mm} rapid fire. Four 47^{mm} revolving cannon. Two 37^{mm} revolving cannon. Two Gatlings.	Two 57^{mm} rapid fire. Two 47^{mm} rapid fire. Two 37^{mm} rapid fire. Two 47^{mm} revolving cannon. Two 37^{mm} revolving cannon. Two Gatlings.	Two 57^{mm} rapid fire. Two 47^{mm} revolving cannon. Two Gatlings.

The Ordnance Department, Washington navy-yard, has annealed and is boring a 10-inch tube for a Woodbridge wire-wound gun for the Army.

THE HOTCHKISS RAPID-FIRING GUN.

The limit of weight imposed on machine-guns admits of very small calibers only unless the number of barrels is reduced, and to meet the need for a rapid-firing gun of fairly large caliber Mr. Hotchkiss designed his single-barrel gun, which fires from fifteen to twenty rounds a minute.

The following is a description of the principal features of the gun: It is fixed on a pivot, making it a non-recoil gun, is aimed by a man supporting himself on the shoulder rest attached to it, and has a pistol grip, with a trigger for firing.

The breech is closed by a wedge moving vertically in a slot through the gun, the front face of the wedge being perpendicular to the bore. The wedge has cut in its right face a peculiarly curved slot which engages the end of the crank, giving motion to the wedge. Inside the wedge is the hammer and firing arrangement, which is worked by a cocking cam on the crank axle.

Owing to the shape of the slot in which the crank works, when the breech is opened the wedge is motionless until the hammer is cocked, when the wedge descends. As the wedge clears the bore a slot in its left side throws the extractor, carrying the shell directly to the rear. The new cartridge is inserted and the reverse motion of the crank raises the wedge and brings the firing-gear against the trigger. Safety from accident is afforded by the fact that the firing-hammer cannot protrude through the face of the wedge until the wedge is home, and the trigger is quite disconnected from the rest of the firing-gear, acting only by contact.

Hotchkiss rapid-firing guns.

Caliber.		Length of gun.	Weight.	Weight of projectile.	Initial velocity.	Perforation point blank (steel).	Rapidity of fire per minute.	Crew.	Remarks.
Inch.	*Mm.*	*Inches.*	*Pounds.*	*Pounds.*	*F. s.*	*Inches.*	*Rounds.*	*No.*	
1.45	37	67.7	308	1.87	2,034	2.75	20	2	More powerful than ordinary 37-millimeter guns.
1.85	47*	77.0	397	8.30	1,706	3.00	20	2	To fill up port openings in forts for heavy guns when the great guns are not in use; removed in one minute.
1.85	47†	80.6	506	3.30	2,034	3.93	18	2	Light deck armament and boat gun.
2.24	57	99.0	815	6.00	1,837	5.10	16–18	3	For deck, boat, and field use.

* Light. † Long.

ENGLAND.

NOTES UPON IMPROVEMENTS IN ORDNANCE.

No radical changes have taken place during the last year in guns building for foreign governments, though some advance has been made in details by which those now being put in service have been improved. England still holds the lead in the manufacture of heavy guns, and those now building for her navy will combine whatever is found good either in manufacture or principle.

The cup gas-check has given way to the De Bange obturator, and the screw breech-block has been placed in the jacket, instead of the tube. Great length of bore, large chambers, and slow or progressive powders are still the main features of foreign gunnery, though as a marked divergence from these may be cited the Hope system, which is at variance with almost all of the principles heretofore taught or practiced in gunnery. This system, which takes its name from Lieutenant-Colonel Hope, commanding First London Artillery Volunteers, consists in the instantaneous combustion of the entire charge and the motion of the projectile before the charge is ignited.

To accomplish this the cartridge is of peculiar construction. The metal case, such as is used for small-arms, he makes use of as the most perfect system of obturation. Through the center of the charge runs a hollow cylinder, the rear end of which contains 100 grains of fine quick-burning powder, while the forward end rests against the projectile. This he calls his small cannon, and is intended to start the projectile in motion before the combustion of the main charge. Along the entire length of this central cylinder are numerous holes of different sizes, those at the forward end being largest, and all being covered by paper or cloths. This cloth covering is thickest at the rear and decreases in thickness towards the front, where it is quite thin; the object sought being to ignite the charge simultaneously at many points and thus to cause what the inventor terms an explosion or instantaneous combustion of the entire charge. The charge is also of the most rapid-burning powder, and equal in weight to the projectile, which is also modified in shape, being pointed at the base as well as the point. By these means the inventor hopes to maintain the muzzle velocity for a longer time, as the form of projectile claimed is to be that offering least resistance in air.

To stand the heavy strain of explosion, Colonel Hope has patented a process of fluid compression by which he hopes to obtain a dense and homogeneous steel, but as this requires a new and expensive plant no guns as yet have been built upon this system. A hooped gun, however, representing his firing principle was built at Terre Noire, France, which at trial gave excellent results. It will be more accurately described in the French ordnance. The breech-block and chamber are also on a different system from that used in any large gun. The breech-block is in the form of a curved wedge hung by a double T-piece, on the roof of the bore to the rear, about which it pivots. The chamber is a perfect truncated cone, by which loading and withdrawing the metallic case is made easy, and the shoulder at the junction of the chamber and bore is done away with, as it is a very gentle slope from the breech to the cylindrical part of the bore.

The Armstrong 10.2-*inch Riband Gun.*—In April, 1884, experiments were carried on at Shoeburyness with Armstrong's new 10.2-inch B. L. R. on the riband system. The weight of this gun is 21¼ tons and its length 31 calibers. Over 70 rounds with high charges were fired without accident, though some fault was found in the cup gas-check and some scores were found in the bore from defective bands.

In these trials Palliser shells with Vavasseur rotating rings were used, the rings being placed in front of the old band. The following table gives some of the principal results obtained:

Charge.	Weight of projectile.	Initial velocity.	Pressure per square inch.
	Pounds.	*F. s.*	*Tons.*
245 pounds prismatic powder	450	2,040	21.9
240 pounds prismatic powder	450	1,978	21.6
235 pounds prismatic powder	450	1,950	20.2
235 pounds prismatic powder	500	1,848	20.2

With a charge of 260 pounds and projectile of 502 pounds this gun gives a penetration at the muzzle of 20.4 inches in wrought iron.

It will be noticed that the pressure in the bore was the same with 235 pounds of powder both with the 450 and 500 pound shot, which conforms to the principle as laid down by Colonel Hope, which is that the strain on the gun comes before the shot moves.

The Schultz system.—At Elswick two guns on this system were tried last March. These guns were of 6 and 9 inch caliber. Velocities as high as 2,296 f. s. were reached, but with very high pressures. This system has two distinct features: First, wire winding, and second, the independence of the breech coil, which relieves the tube from longitudinal strain.

Heavy guns building and ordered.—The English Government has ordered three 110-ton guns—one to be finished in October, 1885, one in January, 1886, and one in April, 1886. These guns will cost £19,500 each. They are intended for a charge of 900 pounds of cocoa powder and a projectile of 1,800 pounds.

From experiments with the heavy guns built for the Italian Government a velocity of 2,020 f. s. is looked for with a pressure of 17 tons per square inch.

In May the Government commenced the construction at Elswick of a 112-ton B. L. R. gun having a length of 522 inches, or nearly 33 calibers. This gun will have a caliber of 15.9 inches, and the carriage will weigh 91 tons.

New 5-inch gun.—The new 5-inch gun now manufactured at Woolwich, and miscalled the Vavasseur 5-inch gun, is a good representation of the new class of English breech-loading high-powered guns, embracing all the advantages of the various systems in vogue and combining in one weapon all that is thought to constitute perfection in gunnery. Its weight is but 38 cwt., though those to follow will weigh 40 cwt.

The general dimensions of this gun are: Length, 11 feet 7½ inches; extreme diameter of breech, 17½ inches; length of the cylindrical part of the bore, 25 calibers; diameter of powder chamber, 5¾ inches.

Weight of charge, 16 pounds; weight of projectile, 50; penetration in iron, 8.7 inches; initial velocity, 1,800 f. s.

It is built entirely of tough steel, and consists of an A tube and jacket, without any of the other tubes or coils common to other guns. The tube and jacket are secured together by a key-ring covered by a hoop. The De Bange obturator and percussion primer are used.

New 6-inch gun.—The new pattern 6-inch gun B. L. R., to be known as Mark IV, soon to be constructed in England, will have some improvements in the breech-closing mechanism and a modification of the rear end of the tube, which will be built heavier, to sustain a long-continued fire.

Gave way under fire.—During the last year two guns of new construction have given way in England—one a 6-inch and the other a 9.2-inch; the first on board the Active, and the second while under trial at Woolwich. The first was built at Elswick, and had undergone proof-firing. It was then put on board the Active for the trial of a Vavasseur carriage. The service charge is 34 pounds of powder and a 100-pound projectile, while at the time it gave way it was loaded with but 17 pounds of powder and an 80-pound projectile. Four and a half feet of the muzzle was blown off and fell in three parts. The break was five feet from the muzzle, on the left side of the gun, and extended at an angle of about 45° to a point on the right side about four feet from the muzzle. The fracture showed no imperfection in the steel. A committee that examined into the cause of the accident came to the conclusion that a tool or some other obstruction had been left in the gun, and that if the usual scaling charge had been fired the accident would not have occurred.

The 9.2-inch which gave way under experimental fire was a modern B. L. R. on the hoop system. It had been loaded at the time of the accident with 200 pounds of experimental powder (black cylindrical powder). The entire chase from 3 feet 2 inches forward of the edge of the trunnions burst into a multitude of fragments, some of which were carried nearly a mile. This accident seems to have caused distrust in this pattern, and the impression prevails that the chase is not heavy enough to stand the fire of a slow progressive powder, with which the strain is carried much farther forward than with the older kinds. No other solution has been offered for the accident, and it is thought that in future the chase rings will be carried nearer the muzzle. The remainder of the gun was uninjured.

New patents.—Among the important patents taken out last year in England for improvements in gun-construction and gun-carriages are the following:

By Albert Sauvée, for loading turret guns in any position: The improvement consists in a hollow central pivot of considerable size: that is, large enough to allow the projectile and the two half-charges to come up in a car at one time. This car is moved up and down the hollow pivot of the turret by hydraulic power, and by guides on the inside of the pivot and a lever on the car it is directed to the loading position in rear of the gun. This patent includes one also for checking the recoil of turret guns.

By Eardley Maitland, Colonel Royal Artillery, for locking hoops: This consists in making each hoop or ring with lugs and spaces of equal size and a space behind each lug equal in size to the lug itself. The hoops are fastened by placing one over the other, so that the lugs shall come in front of the spaces when it is forced on to the depth of the lug and turned, so that each lug comes behind its fellow. The vacant spaces are then filled with steel blocks which prevent any motion of the ring.

By Lieut. Col. William Hope, V. C., for an improvement in gun construction: It consists in an annular mold of great strength, into which steel is poured, and while still liquid subjecting it to great pressure by an annular piston moved by hydraulic power. When the metal has cooled below the welding point the core of the mold is withdrawn and mandrels of different sizes forced through the center of the casting, compressing the metal still more. This is continued, using a mandrel of larger size each time, until the metal has cooled and set.

THE LARGEST GUN YET DESIGNED.

A monster breech-loader, to be constructed at Woolwich on the wire-wound system, has just been designed for coast defense. It far surpasses any gun yet proposed. Its general dimensions are as follows:

Weight, 156 tons; weight of largest forging, 30 tons; weight of powder charge, 1,700 pounds; weight of projectile, 2,000 pounds; total length, 61 feet 11 inches; length of bore, 700 inches, or 41 calibers and over; estimated muzzle velocity, 2,500 f. s.

FRANCE.

For coast-defense guns, the French are now constructing cast-iron bodies, hooped and tubed with steel, of the model of 1870 and 1871, but with longer and larger chambers. The calibers of those now building of this pattern are the 27 and 32 centimeter. The guns are also longer than the model of 1870, having a bore of 25 calibers, which will increase the velocity, so it is hoped, by some 35 or 40 meters. As yet none have been subjected to proof.

The guns building for the navy are all of steel. Those of the model of 1875 to 1879 are hooped and tubed, and intended for the armored ships. These guns are of 34 and 37 centimeters. They have a length of bore of 21 calibers. The 37-centimeter will weigh from 72 to 75 tons and will throw a projectile of 560 kilograms (1,232 pounds) at a velocity of 620 meters per second (2,034 f. s.).

The largest range of calibers, however, are being built on the model of 1881. These are of steel, hooped, but not tubed, and are of the following calibers: 6½, 9, 10, 14, 16 (light), 16 (heavy), 24, 27, 34 (short), and 34 centimeters (long).

The 34-centimeter gun will weigh 54 tons. These guns, beginning with the 14-centimeter, have great length of bore, viz, from 28 to 30 calibers, except the 34-centimeter (short), which has a length of 21 calibers. No change is to be made in the projectiles at present in use, except for the 14-centimeter gun, which will use a shell of 30 kilograms, instead of 28 kilograms.

Experiments being carried on at Gavre will, it is expected, end in the adoption of the army shrapnel for the lighter guns, viz, of 6½, 9, and 10 centimeters. This shell has but a small angle of divergence.

The proof of the 6½, 9, 10, 14, and 16 centimeter (heavy) has already been made. In the last two calibers velocities of 600 meters (1,968 f. s.) have been reached with a pressure of 34,300 pounds per square inch, using a shell almost double the weight of powder charge. Equal success is expected in the guns of larger calibers yet to be proved.

New patents, &c.—Colonel De Bange has this year patented an improvement on his gas-check, which has been so universally adopted. It consists in using a double, instead of a single ring of asbestos, and also an improved primer, preventing entirely the escape of gas.

In the new patent the plug has a central hole through its entire length, into which is inserted a bouche, which is screwed into the back end of the hole and reaches a little farther than the front end of the plug. This bouche has a block and pin in the face of the plug, preventing it from turning and at the same time holding the movable head of the plug in place. The under side of the movable head has a projecting annular flange separating the inner and outer rings of asbestos. The outer one serves as a gas-check for the plug itself, while the inner ring serves as a gas-check for the bouche. The primer has also the same general principle as the breech-plug, viz, that of a movable head and an elastic ring back of it. Upon this movable head is an ordinary straight friction tube, the wire of which ends in a conical head. On the side of the primer are two lugs which fit in two slots in the rear end of the bouche, so that a partial turn secures the primer in place in the same manner as the breech-plug is secured. The action of this primer is simple. At the moment of firing the shock of discharge forces back the movable head of the primer, compressing the elastic ring, thus closing the passage of gas between it and the bouche, while the cone upon the end of the friction wire is hauled tightly into hole at the rear end of the friction tube, thus closing all passage of gas around the friction wire. The primer can only be introduced when the breech-plug is entirely closed.

It is claimed that this new improvement renders the loading more rapid and prevents all escape of gas, so that cleaning the breech apparatus during action is not required.

The Hope high-powered gun of 127 millimeters (5 inches) built at Terre Noire was last year tested with good results. It is constructed entirely of steel, and consists of a central or A tube with two series of strengthening hoops. The first series consists of three hoops, the rear one being secured to the A tube by a screw thread, while the second is locked to the first by being shrunk over it at the front end, where there is a slot in which fits a corresponding ledge on the second ring. The third is secured to the second in like manner. The second series consists of five hoops, three of which are one meter in length. The fourth is the trunnion ring, and the fifth is a little less than a meter in length. This series is locked to the second, so that the entire gun forms as near as possible one compact mass. The breech is closed by the ordinary screw plug. The powder-chamber is 2¼ meters long, or about 16 calibers. The charge is 30 kilograms, or about 66 pounds, which is also the weight of the projectile. The length of the rifled portion of the bore is 24 calibers, and has a right-handed twist with 24 lands. The projectile is 3 calibers long.

Two series of trials were made last year with this gun. The first was at a steel plate 195 millimeters (7.7 inches) thick. The first shot was fired with a charge of 14 kilograms (30.8 pounds), when the pressure in the bore was 3,287 kilograms per square centimeter (46,957 pounds per square inch). The plate was pierced, though the projectile broke in four pieces. The velocity at this discharge was 585 meters (1,919 f. s.). At the second fire a charge of 12 kilograms (26.4 pounds) was used, when the muzzle velocity was 567 meters (1,860 f. s.), and the pressure 2,892 kilograms per square centimeter (41.314 pounds per square inch). At this fire the plate was broken in half, while the projectile, which was of soft steel, remained uninjured.

In the second series the plate used was 257 millimeters (10.1 inches) thick, also of steel.

The first shot of this series was fired with a charge of 21 kilograms (46.2 pounds), when the pressure rose to 3,988 kilograms per square centimeter (56,970 pounds per square inch), giving a velocity of 630 meters (2,067 f. s.). With the second fire the powder charge was reduced to 20 kilograms (44 pounds), when the pressure fell to 3,616 kilograms per square centimeter (51,657 pounds per square inch) and the velocity to 622 meters (2,040 f. s.). There is good reason for believing that these experiments have been carried further and that a velocity of nearly 2,500 feet per second has been reached, but so much secrecy surrounds the experiment made by Colonel Hope that more accurate data cannot be obtained.

Colonel De Bange is now building in France a new gun of his own patent. This gun is intended for coast defense and will be of the following general dimensions, &c.:

Caliber, 34 centimeters (13.4 inches); weight, 37,000 kilograms (37 tons); weight of projectiles, 400 kilograms (880 pounds); weight of charge, 180 kilograms (396 pounds); muzzle velocity, 600 meters (1,968 f. s.).

It is claimed that this gun will have a range of 12 miles.

Guns furnished for re-arming the navy.—In 1879 it was decided by the French Government to rearm the navy with modern high-powered guns. The following under this decision have already been put in service: 3 guns of 42 centimeters (16.5 inches)—(four more also about ready); 21 guns of 34 centimeters (13.3 inches); 21 guns of 32 centimeters (12.6 inches); 9 guns of 27 centimeters (10.6 inches).

The following will be delivered during 1885: 4 guns of 42 centimeters (16.5 inches); 3 guns of 37 centimeters (14.5 inches); 7 guns of 34 centimeters (13.3 inches); 14 guns of 27 centimeters (10.2 inches).

In 1886 there will be delivered: 4 guns of 37 centimeters (14.5 inches); 3 guns of 34 centimeters (13.3 inches); 10 guns of 27 centimeters (10.2 inches).

GERMANY.

In Germany the tendency is towards very long guns, slow-burning powder, and heavy projectiles. The following guns are now being experimented with or building:

Diameter of bore.		Length (calibers.)	Remarks.
In centimeters.	In inches.		
15	5.9	25	
15	5.9	30	
15	5.9	35	
21	8.2	30	
21	8.2	35	
24	9.4	35	
26	10.2	35	
28	11	35	
30.5	12	25	
30.5	12	35	37.7 tons.
35.5	13.9	30	49.2 tons.
[1] 40	15.7	35	58.5 tons.
45	17.7	25	120 tons.

NOTE.—Deduct three calibers to obtain the length of bore.

[1] The 40-centimeter gun is intended for the coast defense of Italy.

All of these guns are intended for the navy or coast defense. The heavy steel shells have been adopted for all armor-piercing projectiles.

The Germans are working towards the use of but two brands of powder differing in density, the denser being for the larger calibers. In the last trials the powder adopted was the prismatic with large holes. This class was also tried in France and England with satisfactory results. The French factory of Sevran Livry has produced several samples of prismatic powder which compare very favorably with the German powders.

The weight of the projectile used in experiments with these guns often exceeded in weight four times that of the solid spherical shot of the same caliber, and some were as much as 3.3 calibers long.

Had French instead of German projectiles been used the muzzle velocities would have been as follows:

For guns of 25 calibers in length, 580 meters, or 1,902 f. s.

For guns of 30 calibers in length, 615 meters, or 2,017 f. s.

For guns of 35 calibers in length, 640 meters, or 2,099 f. s.

These velocities would have been obtained with pressures not above 2,400 kilograms per square centimeter (34,285 pounds per square inch), except in the gun of 45 centimeters, where the pressures would have reached 2,600 kilograms per square centimeter, or 37,143 pounds per square inch. The use, however, of the heavy projectiles of the Germans decreases the muzzle velocity and increases the pressures, so that in the late trials the pressures rose as high as 2,700 kilograms per square centimeter (38,571 pounds per square inch), while the velocities did not exceed 565 meters per second, or 1,853 f. s.

TORPEDO BOATS.

ENGLAND.

The Eastern war-cloud has given great impulse to the development of the English torpedo fleet, the following additions to it having been made since March:

Purchased from Chili	4
Received from Thornycroft & Co	2
Ordered from Thornycroft & Co	25
Ordered from S. White	20
Ordered from Yarrow & Co	4
Total	55

The two (Nos. 21 and 22) recently delivered by Thornycroft & Co. are large sea-going boats. Their principal dimensions are: Length, 113 feet; beam, 12 feet 6 inches; draught, 2 feet forward and 6 feet aft. These boats are fitted with three launching tubes; two in the bow are fixed, while the third, near the stern, can be trained from below the deck and fired from the pilot-house. During their three-hour speed trials in the Solent these boats maintained speeds of 19.73 and 19.97 knots, the engines developing upward of 700 H. P. At moderate speed these boats can steam, without recoaling, 1,100 miles. They carry one Nordenfeldt gun.

The boats recently ordered from Thornycroft are to be of larger and improved type. They are to be built of steel, with fourteen water-tight compartments, and will carry 20 tons of coal, which, at 10 knots speed, will enable them to steam 2,000 miles. Their principal dimensions are: Length, 125 feet; beam, 12 feet 8 inches; draught, 6 feet 2 inches aft; estimated speed, 19 to 20 knots.

These boats will be fitted with five torpedo-tubes; one on the bow, one on each side of the pilot-house, and two astern; all except the bow tube mounted on towers capable of being trained through a considerable arc. In addition to their torpedo armament they are to carry two Nordenfeldt guns.

The cost of each of these boats is to be £11,000. Their speed is not so great as that of other boats, but the advantages of the all-around fire of their torpedoes quite compensate for the loss of speed.

The new class known as torpedo hunters (or catchers) is well represented by the boat now building at Mr. White's yard at Cowes. This boat is constructed on Mr. White's turn-about principle, which gives great turning powers when going ahead or astern. A boat of 100 feet length built on this plan has a turning circle of 75 yards diameter when going ahead, and 115 yards when going astern, in comparison with the circle of 350 yards diameter for a boat of 84 feet length built on the ordinary plan.

The torpedo hunter building at Mr. White's is to be 150 feet in length, 220 tons displacement, and is to have a speed of 18 knots. It will be fitted with four torpedo-tubes, one firing directly ahead, one on each bow, and one astern.

FRANCE.

VOYAGE OF TORPEDO BOAT NO. 68 THROUGH THE RIVERS AND CANALS OF FRANCE.

An important feature in the general system of French home-defense is illustrated by the voyage of torpedo boat No. 68 from Havre to Toulon, through the canals and inland waters of France, in May last.

The strategic importance of this interior line of communication from the English Channel to the Mediterranean is most obvious, and the superiority of the French torpedo fleet over that of the English will be greatly increased by the facility with which boats may be transferred from one sea to the other.

Torpedo boat No. 68 was built by Normand & Co., of Havre; is 108 feet long, 10.8 feet beam, with 6.4 feet draught at 49 tons displacement, and has developed a speed of 21 knots. As the canals do not admit of the passage of boats of this draught, it was necessary to lift the boat by means of caissons and cork belts, specially fitted before the voyage, in order to reduce the draught to 4.1 feet.

NIGHT ATTACK OF TORPEDO BOATS.

During the past spring an interesting experiment was made by the French squadron of evolutions, consisting of four armored vessels and three torpedo boats under the command of Vice-Admiral Duperré, to ascertain the practicability of a successful attack upon a fleet by torpedo boats. Signal was made during the early evening to prepare to receive such an attack, and three torpedo boats left the squadron to return under the cover of night. Warning was given that the attack was to be expected after midnight and before 3 o'clock a. m. The night was dark, but the electric light searched the sea and additional lookouts kept vigilant watch. It was decided that any vessel which allowed a torpedo boat to approach within 50 meters without being recognized and exposed to the fire of rifles and machine-guns was to be considered destroyed.

Suddenly, and within the specified time, three red lanterns were almost simultaneously displayed within 40 meters of some of the vessels of the squadron, which indicated that three torpedo boats had successfully passed within the dangerous zone and had penetrated it to a distance which secured the destruction of most of the squadron.

These torpedo boats had accompanied the French squadron during their entire cruise, and upon one occasion were able to keep the sea when some of the armored vessels (coast defense ships) were obliged to seek a harbor, and it is said that their speed was from 14 to 16 knots while that of the ships was reduced from 14 to 7 knots.

GERMANY.

The German Government in developing its coast defenses has placed great reliance upon torpedoes and torpedo boats, and has made a departure from the usual custom by placing all coast defenses (fortifications included) under the direction and control of the navy. The fleet of torpedo boats is to be increased to 150, and the plans and arrangements for closing the principal harbors are so complete and precise that but a few hours' notice is necessary to place all the mines in position and prepare the torpedo flotilla for service.

In the last type of torpedo boat received from Yarrow the German admiralty has found a very desirable addition to its fleet. This boat is 120 feet long, 13.2 feet beam, 5½ feet draught, and 65 tons displacement. It carries 25 tons of coal, and has steamed at a speed of 19 knots for three hours. The boat is exceedingly steady in a seaway, and is so constructed and arranged that it may steam fifty miles should the engine-room compartment be filled with water. It is fitted with two torpedo-tubes.

The latest German torpedo boats are 35.9 meters (109 feet 5 inches) long, 3.81 meters (11 feet 7 inches) wide, and displace 75 tons at a draught of water 1.88 meters (6 feet 2 inches). They launch 35.5-centimeter (14-inch) torpedoes from two tubes, are masted, and can travel with sail-power only. They carry a large quantity of coal, 22 tons, which enables them to travel 3,000 miles at 11 knots. The coal is disposed so as to afford great protection to the boilers and machinery. There are comfortable quarters for officers and crew. These boats are fitted with a cooking-stove, a Normandy condenser, two Hotchkiss guns, and an electric search-light. Their total cost, complete in every respect, is only $50,000. The German Government is getting some of these boats from Thorncroft, in England, and others at Stettin. The German-built boats have given better results than the English.

In March, 1885, the German Government had two torpedo boats building by Thorncroft and one by Yarrow, while the Weser Company was building six, the Vulcan Company ten, and the Schichau Company six; making a total of twenty-two building in Germany.

AUSTRIA.

Yarrow & Co. are building two torpedo boats for Austria which will have the highest speed yet attained.

Their dimensions are: Length, 135 feet; beam, 13.75 feet. They are to develop 1,100 1,200 H. P., and are to have a speed of 24 knots when light, and 22 knots when loaded ready for service.

TURKEY.

The Turkish Government has ordered six torpedo boats from the *Société des Forges et Chantiers de la Méditerranée*.

Their dimensions are: Length, 101.7 feet; beam, 11.7 feet; draught, 5.7 feet; displacement, 42 tons. They are to be fitted with two torpedo tubes in the bow, and are to carry a spar torpedo as well.

Upon its trial (in April) one of these boats while at her load displacement, carrying twenty-four persons, made 20.3 knots over the measured mile.

JAPAN.

The Japanese Government has made a contract with Messrs. Yarrow & Co., of Poplar, for the construction of a sea-going torpedo boat of exceptionally large dimensions and novel design. It will be armored with steel plates 1 inch thick throughout the central portion of the vessel, inclosing the machinery compartment, so that the vital parts of the boat may be protected from machine-gun fire at a range suitable for discharging the Whitehead.

The dimensions of this new boat are: Length, 166 feet; beam, 19½ feet; and it will have a speed of 19 knots. It will carry several machine-guns in addition to the four discharging tubes. Exceptional maneuvering powers are expected from the system of propulsion by twin screws.

TORPEDOES.

UNITED STATES.

THE HOWELL TORPEDO.

In the report of the Secretary of the Navy for 1884, volume 1, pages 528–531 and 543–547, may be found a description of this torpedo, with an account of its trials in June, 1884, before a board of naval officers.

A further series of preliminary trials of a newly-constructed torpedo of this type was made at the Washington navy-yard, June 26–27, 1885. The torpedo used was 8 feet 10½ inches long, 14 inches maximum diameter, and weighed 296 pounds with 50 pounds of lead to represent the charge.

It attained a speed of 14½ knots for a distance of 640 feet with but ninety turns of the wheel, and towing a small wooden buoy used to recover the torpedo.

No automatic torpedo of this size has reached such a speed; and the charge, 70 pounds, is greater than that carried by any but the largest Whiteheads.

The torpedo broke water twice on one occasion and four times on another. This may be accounted for to a large degree by the towing effect of the buoy. The steam pressure available for conveying motion to the wheel on this trial was but 40 pounds, while with steam at higher pressure 168 revolutions have been obtained. (The strength of the wheel will permit of more than 250 revolutions.)

The trial made July 1 with the same torpedo gave very satisfactory results. The accelerator operated for 1 minute 20 seconds, giving about 115 turns. The speed was not noted, but the torpedo did not come to the surface during its run, in spite of the towing buoy, and its range on this occasion was about 450 yards.

It may be fairly expected that a considerable addition of speed and weight of charge will be obtained from the future torpedoes of this type, which is now regarded with much interest and favor as a weapon powerful for offense and defense.

The cost of the Howell torpedo is at present about $300. When made in large numbers a considerable reduction of price may naturally be expected.

TORPEDO IMPROVEMENTS, ETC., ABROAD.

Many patents have been taken out and many experiments made abroad during the past year with torpedoes of all kinds and classes, but the Whitehead is still the most reliable and generally used. Improvements have of late been made in its construction that have increased its destructive power and accuracy much beyond the models of former years. Phosphor-bronze is superseding steel in the construction of new Whitehead torpedoes, as it admits of their being accurately adjusted by trial runs, and stored away without being taken apart to clean, as was required with the old steel ones. Those built in Germany are all of this metal, and are of fine workmanship and extremely accurate. Out of sixty runs made at Kiel a short time since, the mean error in direction at 400 meters was only 2.4 meters, and the depth was within a small decimal of what the torpedo was intended to maintain. The latest improvement in this weapon has been the increase of the charge to 70 pounds of gun-cotton and the increase of the speed to 25 knots. This last torpedo is 14 feet long and maintains its speed of 25 knots for 433 yards. One of the uses the German Government proposes to make of this torpedo is to sink several in a caisson in the middle of the channel and pointing in a known direction, so arranged that they may be fired from shore by electricity. By this means the range is much increased.

The various adjustments have of late been so simplified that the distance at which success is almost certain has risen from 200 meters to 500 meters, while inside of 300 meters failure is almost impossible, and the greatest deviation at 500 meters is not over 6 or 8 meters. At the same time its motive power has been so increased that it is now sufficient for a distance of four knots, which is almost double its former run.

The failure of the machinery that once was so common is now the exception.

Lastly, with these many improvements the price has fallen from £375 to £300.

BRENNAN TORPEDO.

The London Times states:

"For a year or so past experiments have been carried out to test the powers claimed for a new torpedo invented by a young Australian, Mr. Brennan, and offered by him to the British Government. The Admiralty allowed the inventor to use a casemate on the upper tier of Garrison Point Fort, Sheerness, and a torpedo factory was erected outside the fort with a tramway running down to the sea-beach. The trials have taken place, and the mechanism has been so far perfected as to admit of an official inspection. This has proved so satisfactory that the Admiralty have already agreed to adopt the torpedo as a part of the national armament. The new torpedo is impelled by a steam-engine within the fort, which acts upon it by winding in very rapidly two wires coiled around reels within the torpedo. As the wires are independent of each other and actuate different propellers the torpedo can be steered from the engine with great accuracy. It is even practicable to stop the torpedo in full flight and send it on again, but this tries severely the endurance of the wires, which are very small.

"Jets of light are produced by some chemical agency, and are simply to indicate the position of the torpedo at night; being screened in front, they are visible only to observers in the rear."

While the Times is authority for the statement that this torpedo has been accepted by the English Government, many professional authorities do not place high value upon the invention.

TORPEDO EXPERIMENT IN SPEZIA, 1885.

A caisson with a triple hull of steel, representing a section of one of the newly-designed ships (probably the Umberto and Sicilia), was moored in the Bay of Spezia. This caisson was covered with an armored deck and ballasted to float at the proper depth to represent properly the vital parts of the ship.

A Whitehead torpedo was fired at this target. The explosion of 27 kilograms (60 pounds) of gun-cotton broke through the first and second bottoms, but the interior hull remained intact, and the stability was not materially impaired.

A second torpedo was fired at the caisson, but on this occasion the explosion took place against a compartment filled with coal. This time the outer bottom only was broken, and it is said that the second and third system plates showed no signs of rupture.

From these experiments the Italian commission concludes that triple thicknesses of plates, properly fastened and supported, will protect the interior of a vessel from the explosion of the Whitehead torpedo. In consequence, orders have been given to begin the construction of the newly-projected ships.

THE NORDENFELT SUBMARINE BOAT.

The boat is of the so-called "cigar shape." Its length is 64 feet, with a diameter of 9 feet at the center; but a small conning-tower on top and the sponsons on the sides increase the extreme dimensions to length 64 feet, beam 12 feet, and depth 11 feet.

It is built of the best Swedish mild charcoal steel. The plates in the center are five-eighths of an inch thick, but decrease in thickness to three-eighths of an inch at the extremities. The hull will withstand a pressure of 100 feet of water. The conning-tower, 12 inches high, is fitted with a cover which can be readily swung upon a pivot to give easy ingress or egress to the three men who form the crew. This cover has a glass cupola, protected by a shield, so the officer in charge standing in the tower may have an all-around lookout.

Sponsons on either side of the boat form wells for the protection of two propellers so placed as to exert their effort in a vertical direction. The boat, which is always kept horizontal and always buoyant, is submerged by means of these propellers to any desired depth, or is permitted to rise to the surface. This is one of the distinguishing features of this invention. Since the boat is always buoyant and submerged by the mechanical power of the propellers working in a vertical direction, it will not sink should any part of the mechanism become out of order, but will of its inherent buoyancy rise to the surface.

The four-blade propeller, at the stern, is 5 feet in diameter, with a pitch of 7 feet 6 inches. The rudder for lateral steering is placed abaft this propeller.

The horizontal position before referred to constitutes another distinguishing feature, and is maintained by a system of weights acting on a pair of balanced horizontal rudders which constitute the "longitudinal stability apparatus." These rudders, placed in the bow of the boat on either side, are secured to one axle. They are always kept in the horizontal position by a weight attached to an arm acting in a plane at right angles to the rudder axle. This weight will always maintain its arm vertical, and since this is in a plane at right angles to the rudders they will always be held horizontal. The same effect may be produced by the weight acting upon the valves of a hydraulic engine controlling the rudders.

When the length of the boat is considered, the necessity of the "longitudinal stability apparatus" to prevent the ends of the boat striking the bottom is obvious, and as the apparatus is said to be perfectly effective, the boat can operate in shallow water.

The machinery is actuated by steam which is derived while the boat is on the surface of the water, from an ordinary marine boiler in which any fuel may be used; but as the draught is forced, anthracite coal is preferred as making least smoke and sufficient steam.

When the boat is submerged steam is supplied by means of the heat stored in water while the boat was on the surface. This hot water is carried in two tanks, as well as in the boiler, and is 8 tons in weight. The propulsive force is obtained by a compound surface-condensing 2-cylinder engine. The cylinders are of 12 and 25 inches diameter with a stroke of 10 inches. There are in addition two small engines of 4 inches diameter by 6 inches stroke, which are used to drive the blower when on the surface and the vertical side propellers when under water.

The boat is fitted with an apparatus for cooling the air, indicating the life-sustaining properties of the air, indicating the depth at which the boat is working, and an automatic arrangement to stop the vertical propellers when the boat has arrived at a given depth and to start them again as it begins to rise. These, together with a compass, thermometer, and barometer, give all necessary information to the commander.

Powerful pumps are fitted in case leaking should occur, besides which the boat may be much lightened by blowing out the 8 tons of hot water carried.

No compressed air nor chemical method of purifying the air is needed, as the boat has sufficient air space to render such arrangement unnecessary.

The crew can quickly get out of the boat by swinging off the conning-tower lid, which can be done at any depth at which men can withstand the pressure of the water.

The following are some of the actual experiences obtained from the first boat:

Four men have been shut up in the boat for six hours without any connection with the outside atmosphere and suffered no inconvenience.

The longest period that the boat has remained under water with cupola submerged, with crew on board, without coming to the surface, is one hour.

The greatest depth at which the boat has been operated is 16 feet below the surface.

It has always been practicable to keep the boat within 1 foot of the desired depth.

The greatest distance the boat has traveled when completely closed and driven only by the heat stored in the hot water is 16 miles. The speed maintained on this occasion was 3 miles per hour, the initial pressure in the hot-water tanks being 150 pounds to the square inch, so that it is claimed that the boat can be relied upon to make 12 miles under water. The greatest speed recorded is somewhat over 8 knots on the surface.

The greatest distance made as an ordinary surface steamer, without recoaling, is 150 miles. The boat has made the passage from Stockholm to Gottenburg, by the inner route, stopping at different ports for coal. On this passage it experienced rough weather and proved itself seaworthy. (The telescopic smoke-pipe was then raised as in an ordinary boat.)

The present boat is constructed with a view of being armed with one Nordenfelt controllable towing torpedo, and one Whitehead torpedo to be fired from a tube in the bow. With an increase of size the boat could travel greater distances, have greater speed, and could carry three Whitehead torpedoes.

The peculiar advantages of this invention are those common to all submarine boats—secrecy of movement, whether for attack or defense, or for avoiding an enemy's lines or lookouts.

◆

PLAN SHOWING HEADQUARTERS' AND GARRISONS Nos. 1, 2, & 3.--COLON.



A.—Hospital.
B.—Post 1.
C.—Machine-shops P. R. R.
D.—Post 2.
E.—Church.
F.—Washington Hotel.
G.—U. S. Naval Storehouse.
H.—Dwelling Supt. P. R. R. Headquarters.
I.—Burt Barracks, Post 3.
1, 2, 3, 4, 5, and 6.—Barracks occupied by Blue Jackets and Marines.

PLAN OF POST No. 4, PACIFIC MAIL CO.'S PROPERTY.



A.—Barracks.
B.—Barracks.
C.—P. M. S. S. Co.'s office.
D.—P. M. S. S. Co.'s wharf.
E.—P. M. S. S. Co.'s steamer.
H.—Kitchen.
I.—Wharf rebuilt by carpenters of Tennessee.
K.—Boats belonging to Expedition.
P.—Canal Co.'s shed.



MAP
OF A
RECONNOISSANCE
MADE NEAR
SAN PABLO,
BY
Lt. H. K. GILMAN. U. S. M. C.,
April 25, 1885.

A —Pont de Barbacoas. Iron: 6 spans. Total length, 617 feet. Width, 17 feet. Height above river, 34 feet.
B, B.—Breastworks, 60 feet above bridge. Distant 50 yards.
C.—Rifle-pit to protect rear.
D.—Breastwork. Distant 300 yards from bridge. Fort Josie.
E.—Military Garrison. San Pablo.
F.—Telegraph office.
P, P. P—Guard tents.

PLATE [illegible]


DOLPHIN
Boston
CHICAGO
Chicago

PLATE II. [illegible]

[illegible] AUGUST 11, [illegible]



PLATE 10. VIEW OF QUARTERS E. C. AN

FROM A PHOTOGRAPH TAKEN



7 OF THIRD GARRISON AT ASPINWALL.

[illegible]

Plate XI.



Camp Miller
Gardner's Island.

Scale 1" = 400'

INFORMATION FROM ABROAD.

PUBLISHED BY THE OFFICE OF NAVAL INTELLIGENCE.

WAR SERIES.

I.—Operations of the French Navy during the recent war with Tunis, 1881. Tran
lated from L'Année Maritime.
By Lieut. M. Fisher Wright.

II.—The war on the Pacific coast of South America between Chili and the all
republics of Peru and Bolivia.
Lieut. T. B. M. Mason.

III.—Report of the British Naval and Military operations in Egypt, 1882. Part I, te
Part II, plates.
Lieut. Commander Caspar F. Goodrich.

GENERAL INFORMATION SERIES.

I.—Observations upon the Korean coast, Japanese-Korean ports, and Siberia, see
during a journey from the Asiatic Station to the United States through Sibe
and Europe, June 3 to September 8, 1882. (Edition exhausted.)
By Lieut. B. H. Buckingham and Ensigns G. C. Foulk
and Walter McLean.

II.—Reports on the Exhibits at the Crystal Palace Electrical Exhibition of 1882.
By Ensign F. J. Sprague.

III.—Examples, conclusions, and maxims of modern naval tactics, 1884.
By Commander W. B. Hoff.

IV.—Papers on Naval operations during the year ending July, 1885.

NOTICE.

The office of Naval Intelligence will furnish the above publications, until the editions are exhaus
upon the personal application of officers.

The office of Naval Intelligence will assist officers in obtaining information printed by the Gove
ment.

JAN 4 1897
SEP 5
~~DU MAR~~
DUE APR '67 H
1243-546
CANCELLED



PLATE 10. VIEW OF QUARTERS 5, 6, AND

FROM A PHOTOGRAPH TAKEN B

D 7 OF THIRD GARRISON AT ASPINWALL.

[illegible] U. S. N.

Plate XI.



DOLPHIN
Boston
Chicago
Chicago



PLATE [illegible]

[illegible]

[illegible]



PLATE 10. VIEW OF QUARTERS 5, 6, AN

FROM A PHOTOGRAPH TAKEN

[illegible] 7 OF THIRD GARRISON AT ASPINWALL.

[illegible] U. S. N.

Plate XI.



INFORMATION FROM ABROAD.

PUBLISHED BY THE OFFICE OF NAVAL INTELLIGENCE.

WAR SERIES.

I.—Operations of the French Navy during the recent war with Tunis, 1881. Translated from L'Année Maritime.

By Lieut. M. Fisher Wright.

II.—The war on the Pacific coast of South America between Chili and the allied republics of Peru and Bolivia.

Lieut. T. B. M. Mason.

III.—Report of the British Naval and Military operations in Egypt, 1882. Part I, text. Part II, plates.

Lieut. Commander Caspar F. Goodrich.

GENERAL INFORMATION SERIES.

I.—Observations upon the Korean coast, Japanese-Korean ports, and Siberia, made during a journey from the Asiatic Station to the United States through Siberia and Europe, June 3 to September 8, 1882. (Edition exhausted.)

By Lieut. B. H. Buckingham and Ensigns G. C. Foulk
and Walter McLean.

II.—Reports on the Exhibits at the Crystal Palace Electrical Exhibition of 1882.

By Ensign F. J. Sprague.

III.—Examples, conclusions, and maxims of modern naval tactics, 1884.

By Commander W. B. Hoff.

IV.—Papers on Naval operations during the year ending July, 1885.

NOTICE.

The office of Naval Intelligence will furnish the above publications, until the editions are exhausted, upon the personal application of officers.

The office of Naval Intelligence will assist officers in obtaining information printed by the Government.

Plate XI.



Camp Miller
Gardners Island.

Scale 1" = 400'

INFORMATION FROM ABROAD.

PUBLISHED BY THE OFFICE OF NAVAL INTELLIGENCE.

WAR SERIES.

I.—Operations of the French Navy during the recent war with Tunis, 1881. Translated from L'Année Maritime.

By Lieut. M. Fisher Wright.

II.—The war on the Pacific coast of South America between Chili and the allied republics of Peru and Bolivia.

Lieut. T. B. M. Mason.

III.—Report of the British Naval and Military operations in Egypt, 1882. Part I, text. Part II, plates.

Lieut. Commander Caspar F. Goodrich.

GENERAL INFORMATION SERIES.

I.—Observations upon the Korean coast, Japanese-Korean ports, and Siberia, made during a journey from the Asiatic Station to the United States through Siberia and Europe, June 3 to September 8, 1882. (Edition exhausted.)

By Lieut. B. H. Buckingham and Ensigns G. C. Foulk
and Walter McLean.

II.—Reports on the Exhibits at the Crystal Palace Electrical Exhibition of 1882.

By Ensign F. J. Sprague.

III.—Examples, conclusions, and maxims of modern naval tactics, 1884.

By Commander W. B. Hoff.

IV.—Papers on Naval operations during the year ending July, 1885.

NOTICE.

The office of Naval Intelligence will furnish the above publications, until the editions are exhausted, upon the personal application of officers.

The office of Naval Intelligence will assist officers in obtaining information printed by the Government.

JAN 4 18

DUE '67 H

1243546